# ASSAM DISTRICT GAZETTEERS.

Volume II.

# SYLHET

BY

B. C. ALLEN, C.S.



#### Calcutta:

PRINTED AT THE CALEDONIAN STEAM PRINTING WORKS, 3, Wellesley Place.

1905.

Price Rs. 8.



TANK AT JAINTEAPUR. JAINTEA HILLS IN DISTANCE.

## PREFACE.

THE Gazetteer of Sylhet is nothing more than a general description of the district as a whole, and does not, as Gazetteers generally do, include a directory. There are, however, hardly any places in the district which are worthy of the name of town, and the little villages in which the people live do not call for a separate and detailed description. Places which are centres of local trade or of some industry have been specified by name, but to attempt to describe each of these villages would merely have resulted in the most tedious iteration. It should be added that the Gazetteer was compiled at a time when Assam was still a separate Province. and that when the Province is mentioned it is to Assam and not to Eastern Bengal and Assam that reference is made. My acknowledgments are due to the Deputy Commissioner for his kindness in examining the work in proof. सत्यमेव जयते

B. C. ALLEN.

SHILLONG, October, 1905.

## CONTENTS.

CH	٨	TOT	D	ซ	T
UJ11	А	$\Gamma I$	D)	n	ı.

PAGE.

#### Physical Aspects.

Area and boundaries—General aspects—Mountain system—River system—Swamps and marshes—

Geology—Climate—Earthquakes—Fauna ... 1-20

#### CHAPTER II.

#### History.

Early history—Gaur—Laur and Baniyachung—Koch invasions—The Jaintia Parganas—Sylhet under British rule—Khasi raids—Disputes on Cachar frontier—Riots at Sylhet—The Burmese war—Lushai raids—Floods—European settlers—The Cowry currency—Development of excise system—Early salaries—Public buildings—Sylhet in 1837—The mutiny year—Archæological remains

21 - 62

## CHAPTER III.

#### The People.

Density—Towns and villages—Growth of population—
Migration—Sex and marriage—Infirmities—Language - Caste—Brahmans—Sudras—Caste distribution—Muhammadanism—Mosques and tombs—
Hinduism—The Shahaj Bhajan—Sacred places—
Akhras—Christianity—Occupations—Leading families—Marriage customs—Hindu festivals—Amusements

63-112

#### CHAPTER IV.

PAGE.

## Agriculture and Forests.

Agriculture-Rice-Mustard, and pulse-Linseed and til - Sugarcane - Jute - Cotton - Garden Agricultural implements-Storage and threshing of grain-Causes affecting productiveness of land-Yield and value of crops-General remarks-Live stock-Floods-Development of tea industry-Labourers employed -Soil required - Varieties plant-System of cultivation and manufacture-

Green tea-Outturn and prices-Forests ... 113-148

## CHAPTER V.

#### Industries.

Lime-Pottery-Brass and bell-metal-Weaving-Boat building-Workers in wood-Carving and children's toys-Cane work-Other manufactures-... 149-166 Fishing-Lac

#### सत्यामेव जयन CHAPTER VI.

Economic condition of the people, Communications. Trade, Towns and Local Boards.

Subtenancy-Rates of reut-Rent law-Subtenancy in Jaintia-Subletting in the ilam estates-Wages-Prices-Food and dress-Houses and furniture-Economic condition of people-Scocial restrictions -Railway-Navigable rivers-Boat traffic-Roads Telegraph-Trade-Towns-Local -Post and ... 167-211 Boards ...

#### CHAPTER VII.

PAGE.

## General Administration.

Land revenue—Early settlements—The permanent settlement—The hill tracts—Temporarily settled estates—Disforestation—The Jaintia Parganas—Tea land—Land revenue collection—Excise—Income tax—Stamps—Public Works—Government—Administrative subdivisions—Criminal and civil justice—Registration—Police—Chaukidars—Volunteering—Jails—Education—Medical—Leper asylum—Surveys ... 212-273



#### CHAPTER I.

## PRYSICAL ASPECTS.

Area and Boundaries—General Aspects—Mountain System—River System—Swamps and Marshes—Geology—Climate—Earthquakes—Fauna.

The district of Sylhet (vernacular Srihatta), which occupies the lower valley of the Barak or Surma river, lies between 23°59' and 25°13' N. and 90°56' and 93°36' E. and covers an area of 5,435 square miles. It is bounded on the north by the Khasi and Jaintia Hills, on the east by Cachar, on the south by the State of Hill Tippera, and on the west by the districts of Tippera and Mymensingh.

The district is a broad and level valley bounded on either side by hills of considerable General appearance. height. On the north there are none of the low outer ranges that generally break the descent of a mountain system to the plain; the change is sharp and abrupt, and west of Therriaghat, the cliffs are like a Titanic sunk fence in some monstrous park, which drop 4,000 feet and more from the plateau above. Farther east the level falls, and the Jaintia Hills sink in an easy slope towards the plain. The mountains on the south belong to a different system, and run north and south instead of east and west; they do not rise like an unbroken wall along the southern frontier, but thrust out eight spurs into the plain itself. On the eastern boundary one of these spurs stretches right up to the Barak, and the Surma Valley at this point is only some ten miles in breadth. district is only a few feet above the level of the sea, is

intersected with numerous tortuous and sluggish rivers, and is dotted over with huge saucer-like depressions called haors, which are filled with water in the rainy season. Between June and September, a great part of Sunamganj, the north-westerly subdivision, goes under The banks of the rivers are the highest portions of the country and are lined with villages, but the rest of the subdivision is converted into a huge swamp covered with reeds and jungle grass. Here and there, there are islets of high ground which are always crowded with houses, but for a traveller passing through this country in the rainy season, it is difficult to realize that it supports a population of about 300 to the square mile. Further east the level rises, and the scenery is of a more normal type. Broad plains, covered with waving rice, are bounded on every side by what seems at a little distance to be dense and sombre forest. It is, however, only the jungle of bamboos, plantains, jack fruit, and mango trees, which completely conceal the houses of the cultivators; and a closer inspection shows that it is not one continuous belt of villages, but that the bamboo clumps are situated at varying intervals, and that it is only an optical delusion that makes them appear like an unbroken line. The scenery is monotonous, but in the summer time the wide expanse of green is restful to the eye, and near the hills the effect is very picturesque.

Round Sylhet town there are numerous low hills, covered with the freshest and most luxuriant turf; the bamboos which surround the villages are some of the most graceful of their kind, and the plain is bounded on the north by the bluest of blue hills. From Chhatak

the view is of a different character. Rivers and swamps extend on every side, but here and there are islets and ridges of high land, with lawns that slope to the water, dotted with shady trees that recall some garden washed by the waters of the Thames. To the south there are waving fields of rice, bounded with a long line of bamboos and palms; on the north the hills rise like a mighty wall from the waste of waters and jungle at their feet. summits are often clothed in clouds, through which the rivers hurry to hurl themselves over precipices one or two thousand feet in height. The cliffs are here as sheer as though carved out by some cyclopean mason, and even in that humid atmosphere no tree or plant is able to obtain a foothold on the smooth unbroken surface. Below these mighty precipices are steep slopes clothed in dense tropical forest. In the central portion of the district, the scenery is more tame, but towards the south. the hills again appear, though the ranges that are situated within the boundaries of Sylhet are too low to add much to the beauty of the scene. At the eastern end, near Karimganj, dense groves of the graceful areca palm make a pleasant foreground to the blue mountains of North Cachar, and the low isolated hills, that project some two or three hundred feet above the alluvium, serve to break the level of the plain. The rivers with which the valley is intersected are dotted over with native craft. and, even in the winter time, the country on every side looks fresh and green.

In the central and southern portion of Sylhet there is little waste or uncultivated land, except in the hills, which in their

natural state are covered with low scrub or bamboo jungle, and in the haors, which are lakes in the rainy season, and magnificent grazing grounds in the cold weather. In the north the Khasi and Jaintia Hills rise from swamps which recall the jungle that fringes the Brahmaputra, and there are wide stretches covered with reeds and elephant grass from ten to fifteen feet in height.

Roughly speaking, the district falls into the following To the north, there is the wall of hills along whose base the district boundary runs. At the foot of the hills there is a fosse or moat, a belt of country five or six miles wide, in places even more, which goes under water in the rains and is covered with high reed jungle. patches of which are cleared in the cold weather and sown with winter crops. This belt of flooded land is also found along the western border of Sylhet, though here, especially towards the south, it carries little jungle. In the south, the level gradually rises towards the Tippera Hills, and the spurs projecting northwards from this system afford a considerable area of high land suited to the growth of tea. The central portion of the district is a flat plain gradually rising in level towards the east. intersected with numerous sluggish rivers and water courses, and sinking here and there into great saucerlike depressions, which are being gradually filled by deposits of silt.

The Khasi and Jaintia Hills lie outside the borders of the district, and it is only at Chhatak,

Mountain system. Barakia, and Panduah, and in the northeast corner of the Jaintia Parganas, between Jaintiapur

and Mulagul, that the outlying ranges are represented by a few small hills that rise above the surface of the alluvium. A little to the north of Sylhet town there are numerous isolated hillocks, called tilas, from one to two hundred feet in height, and at Chiknagul, on the road between Sylhet and Jaintiapur, these hills take the form of ranges which cover an area of several square miles. A few more tilas are to be found between the Surma and the Kusiyara, near Golapganj and Madhuganj, but the rest of the country north of the Kusiyara and the Barak is a broad unbroken plain.

South of that river eight ranges of hills project from the Tippera system into the valley. On the extreme east is the Chhatachura range which starts from the Chhatachura peak, on the boundary of the Tippera and Lushai Hills, and forms the dividing line between the districts of Sylhet and Cachar. Chhatachura itself is 2,087 feet above the level of the sea, but the range gradually declines in height. The middle section, which bears the name of Saraspur, is only 1000 feet above sea level, while near the Barak at Badarpur it is only three or four hundred feet in height. On the western side of the Singla, or as it is more generally called, the Chargola valley, the Dohaliya or Pratapgarh bills stretch in a compact chain as far north as the Son bil. Beyond this point they break up into isolated tilas, which are continued right up to the Barak at Badarpur. The general height of the range is from four to five hundred feet, and the slopes are easy and gentle. The Pratapgarh range is separated from the Pathariya hills by the valley of the Langai. The Pathariyas are a tract of hilly country, from six to seven miles in breadth, which runs almost due north as far as Latu. Several of the higher peaks are from six to seven hundred feet in height, but the level rises gradually from the plain, and the slopes are very easy. The Harargaz, or Langla hills might almost be classed as a continuation of the Pathariya range to the south-west-Near the frontier they attain an elevation in one peak of over 1,100 feet, but the general height of the outlying spurs is only about one-third of this.

The Bhanugach or Rajkandi hills are a small low range south of the Shamshernagar railway station. Here they are stopped by the valley of the Manu, but reappear again on the further side, and under the name of the Ita hills, stretch nearly up to Fenchuganj. height they range from 150 to 300 feet. sira range lies between the Dholai on the east, the Manu on the north, and the road from Maulavi Bazar to Srimangal on the west. They rise gently from the plain to heights varying from 150 to 300 feet, and are rather a tract of elevated land than hills, in the sense in which that term is usually employed. The Satgaon and Raghunandan hills are two low ranges to the west. The railway runs along the foot of the Raghunandans from Itakhola to Shahji Bazar, and crosses the Satgaon hills near the station of that name. They contain no peaks of any height, and in general appearance resemble the Balisira range. In their natural state all of these hills are covered with tree forest, bamboo jungle, or low scrub-The soil and level were, however, found to be suitable for tea, and large areas have been cleared on the lower slopes and cultivated with that plant.

The principal river of the district is the Barak, which rises on the southern slopes River system. The Barak or Surma of the Naga-Manipur watershed, flows through Manipur, Cachar, and Sylhet, and finally empties itself into the old bed of the Brahmaputra near Bhoirab Bazar, after a course, measured along its northern branch, of 560 miles. From Badarpur to a little beyond Haritikar, a distance of some seven miles, it forms the boundary between Sylhet and Cachar. At this point it divides into two branches, the more northerly of which is called the Surma, and as far as Jelalpur flows in a north-westerly direction towards the Jaintia Hills, and continues to form the boundary between Cachar and Sylhet. Here it enters the latter district, and after receiving the waters of the Lobha, flows a southwesterly course to Golapganj. From this point the stream again takes a northerly direction past Sylhet town to Chhatak, From Chhatak to Sunamganj its course lies near the base of the Khasi Hills, but at the latter town it again turns sharply to the south. A little to the north of Dirai it turns westward and enters Mymensingh, and flows partly through that district, partly along the Sylhet frontier. Near Ajmiriganj it is joined by the Kalni, and at Madna by the Barak, and the combined stream which is here known as the Dhaleswari, finally falls into the old bed of the Brahmaputra.

The lower channel is known at first as the Kusiyara, but after its confluence with the Manu it again divides into two branches. The northern arm is called the Bibiyana, and afterwards the Kalni, and rejoins the Surma on the borders of the district near Ajmiriganj. The

southern stream resumes the name of the original river, the Barak, and, after passing Nabiganj and Habiganj, falls into the Surma a little to the west of that place. Surma in its course through the northern portion of the district receives the following rivers which bring to it the drainage of the hills-the Lobha, the Hari, which under the name of the Kusiva, joins it a little to the east of Sylhet, the Goyain Gong, or as it is called in the lower part of its course the Chengar khal, the Bogapani, and the Jadukata. The rainfall in this portion of the district is extremely heavy, and is only exceeded by the phenomenal precipitation on the southern face of the Khasi and Jaintia Hills, the whole of which drains down into the valley. The plain is less than 50 feet above sea level, and the natural consequence is that the rivers are unable to carry off the enormous volume of water precipitated on their catchment areas. The whole of the district north of the Surma is a network of streams and channels which connect the principal rivers with one another, and during the rainy season the lower parts of the country go under water.

The principal tributaries of the Kusiyara are the Singla, the Langai, the Manu, the Singla the Gopla, and the Khowai. The Singla rises in the Lushai Hills, and flows between the Chhatachura and Pratapgarh ranges northwards to the Son bil. On emerging from this bil it is known as the Kachua, and falls into the Kusiyara a little to the east of Karimganj town. For the first eight miles of its course through the district, it flows through jungle land which is very sparsely peopled; but from

that point to its junction with the Kusiyara its banks are fringed with villages and tea gardens.

The Langai also rises in the mountainous country

beyond the southern frontier, and flows a northerly course between the Pratapgarh and Pathariya hills to within a few miles of Karimganj town. Here it turns to the south-west and finally disappears in the Hakaluki haor, but during the rainy season it is connected with the Kusiyara by a channel known as the Natia khal.

The Manu rises in Hill Tippera, and flows a tortuous north-westerly course between the Rajkandi and Ita hills, and along the northern face of the Balisira range past Maulavi Bazar, till it falls into the Kusiyara a little to the east of Bahadurpur. Its principal tributary is the Dholai, which collects the drainage from the Balisira and Rajkandi hills. The Gopla drains the low country between the Balisira and Satgaon hills, and the Khowai rises in Hill Tippera and falls into the Barak at Habiganj. Throughout the whole of its course its banks are lined with villages, and some of them, like Muchikandi and Laskarpur, are of considerable importance.

The country between the Surma and the Kusiyara or Barak exhibits much the same phenomena as are to be found in the northern section of the district. The rainfall is extremely heavy, the level falls but slightly towards the west, and the line of drainage is not clear and well defined. There is a whole network

of smaller streams, many of which flow from north to south, and rise from or disappear in haors, or swamps. South of the Barak, the level falls more steeply from the hills and the general trend of the drainage is towads that river.

The rivers possess the characteristics usually to be found in a flat alluvial country.

The current is sluggish, the course is tortuous, and the bottom muddy.

In the rains the waters are surcharged with matter washed from the surrounding hills, and in times of flood a large portion of this silt is deposited in the immediate neighbourhood of the stream. The result is that the banks of the rivers tend to become higher than the country at the back, and they are in consequence generally lined with villages. The extent to which these rivers are used for navigation is referred

to in the section dealing with communications.

Sylhet are the enormous quantity of rain water which is precipitated upon the district itself, or drains into it from the surrounding hills, and the absence of a sufficiently steep gradient to carry this huge rainfall off. As a natural consequence water tends to collect in the rainy season in every hollow, and the larger depressions, which are known as haors, are a distinctive feature in the district scenery. From June to September they are considerable lakes, but when the rains end the water gradually drains off, and during the

dry season is only to be found in the lowest parts of the haor. The remainder is covered with reeds and grass and is sometimes sown with winter crops. The level of these swamps is being gradually raised by the silt that is every year poured into them, and the submerged area is being gradually reduced. Statement A appended to this chapter shows what an enormous number of these swamps there are, and how they are distributed over every portion of the district, while Statement B contains the names of the most important haors.

The plain is of alluvial origin and is composed of clay and sand in varying proportions. Geology. The low isolated hills, which here and there project above the level of the alluvium, are formed of layers of sand and gravel, which are often highly indurated with a ferruginous cement. The hills to the south are composed of upper tertiary rocks, in which sand stone largely predominates. Although Sylhet lime is well known in the Calcutta market, and though an enormous quantity is every year exported from the district, the only lime quarry within the boundaries of Sylhet is the one at Jaflong, and even this is not worked at the present day. Deposits of coal exist near Pathariya in the Langai valley, but no attempt has yet been made to work them.

The climate of Sylhet is warmer and not less humid than that of the Assam Valley, but between the middle of November and the middle of February is fairly cool and pleasant. In

March the temperature begins to rise, but heavy rain in April and May prevents the development of the fierce hot weather that is such a trial to the residents in the plains of Upper India at this season of the year. in the appendix shows the average monthly rainfall at certain selected stations in the district. November to February are the four dry months, the average rainfall at Sylhet during that period being only 3.24 inches. During April and May, when precipitation in Northern India is at a minimum, some 35 inches fall at the sadr station, and in the four succeeding months the rainfall is even heavier. There is a marked difference between the rainfall in the northern and southern portions of the district. In Sunamganj it is about 210 inches in the year, at Sylhet 157, and at Karimganj 160. At Maulavi Bazar, on the other hand, it is only 104 inches and at Habiganj ten inches less.

Storms generally come from the south-west, and are usually welcomed as they relieve the oppressiveness of the atmosphere, but are seldom sufficiently violent to do serious damage. Flood is the normal condition of the northern and western portions of the district during the rainy season, but the people have learned to adapt themselves to the peculiar conditions of the country, and do not as a rule suffer any special inconvenience. In the following chapter reference is made to the floods which are said to have been the cause of terrible desolation and misery at the end of the 18th century, but no such calamities have occurred of recent years. In 1853, there was a high flood, and the annual inundation was more pronounced than usual in

the west of the district in August 1893, September 1897, and July 1903, but no very serious damage was done.

Sylhet, like the rest of Assam, is a seismic area, and earthquakes are referred to in some of Earthquakes. the earliest correspondence in the office of the Deputy Commissioner, though they do not seem to have been the cause of any serious damage. shock of 1869 was an exception. This earthquake was felt over an area of 250,000 square miles, from Upper Burma to Patna and Hazaribagh, and is supposed to have originated in a fissure about 20 miles long, situated at a considerable depth below the surface on the northern border of the Jaintia Hills. In Sylhet, the steeple of the church was shattered, the walls of the Court-house and the Circuit bungalow were cracked, and in the eastern part of the district the banks of many of the rivers caved There was no loss of life, and the damage done was inconsiderable in comparison with the havoc wrought by the great earthquake of June 12th, 1897.

This earthquake was felt over an area of 1,750,000

The earthquake of square miles, from Rangoon in the south-east to Kangra in the northwest, from the Himalayas to Masulipatam, and serious damage was done to masonry buildings over an area of 145,000 square miles.\* The area of maximum disturbance was a tract of country of the shape of a cocked hat, whose base line ran from Rangpur to Jaintiapur, while the top of the crown was near Barpeta. The first shock occurred at Sylhet about 4-50 p.m. and was not preceded

सत्यमेव जयते

Memoirs of Geological Survey of India, Vol. XXIX, p. 52.

by any special atmospheric conditions, though the inhabitants of a village at the foot of the hills north of Sunamganj stated that, for some days previously, they had heard continual explosions, which seemed to be taking place in the north-east, i.e., in the direction of Shillong. Nearly all the masonry buildings in Sylhet town were levelled with the ground. A new cutchery that was in course of construction at Sunamganj was thrown down, and the old cutcherry and the residence of the Subdivisional Officer only escaped because they were made of reeds, plaister, and timber instead of masonry. The residence of the Subdivisional Officer at Habiganj was also wrecked. In Maulavi Bazar and Karimganj no damage was done to public buildings, and very little injury was done even to the masonry buildings on tea gardens in the south of The banks of the rivers, especially in the the district. north, caved in and many people were drowned.

The list of casualties as finally reported was 545,

distributed as follows: Sylhet town
55, North Sylhet (rural area) 178,

Sunamganj 287, Habiganj 7, South Sylhet 8, Karimganj
10. These figures clearly show the enormous difference
between the violence of the shock as experienced in the
north and south of the district. In Sylhet town most
of the casualties were due to the collapse of masonry
buildings. The prisoners in the jail had a most fortunate
escape. At the time when the earthquake occurred they
were paraded in the yard preparatory to being locked up
for the night, and had the shock come half an hour later,
hundreds would in all probability have been killed.
Most of the deaths in the mofussil were due to drowning,

the unfortunate people being precipitated from the falling banks into the river, or swamped in the boats in which they were travelling at the time. One hundred and seventynine of the deaths in the Sunamganj subdivision were said to be due to drowning, 87 to the collapse of buildings, and 13 to the people having fallen into fissures in the earth. The Deputy Commissioner reported that there were several apparently authenticated instances of persons having been swallowed up like Korah, Dathan, and Abiram. In one case in Habiganj an old woman was sitting in an akhra,\* when the ground opened exactly beneath her and she disappeared. In another case in Sunamganj, a man and his wife were standing on the bank of a river, when a fissure suddenly opened near the woman, into which she fell. The husband caught her by the hair to save her, but finding his own position insecure let go his hold. woman sank into the crevasse, and her body was not recovered.

The village of Jugirgaon, opposite Sunamganj, subsided into the river, and there were 39 casualties in this place alone. Joynagar Bazar suffered a like fate, and here too 29 deaths occurred. Sunamganj itself escaped, but most of the people, traders and pleaders, high and low, were so alarmed that they left on the morning of the 13th, or took up their residence in boats. Out of some 90 masonry buildings in the subdivision, only five or six were left standing, and nearly 6,000 reed and walled houses are said to have been destroyed. Most of these huts were,

A kind of Vaishuavite monastery to which, however, women are admitted.

however, old and unsound, and would not in any case have lasted very much longer, so that under this head the material loss to the people was not large. Comparatively little damage was done to the district roads with the exception of the road from Sunamganj to Pagla, and from Salutikar to Companyganj. No less than six fine bridges on the latter road were ruined, and the light railway running from Companyganj to Therriaghat was wrecked. Considerable damage was also done to the Assam-Bengal Railway in the south of the district, as the banks had been but recently constructed and had not had time to be properly consolidated.

Elephants are sometimes found in the hilly country on the southern frontier of the district, Fauna. but are far from common. horned rhinoceros is also said to have been seen in that locality, but is extremely rare. Tigers are not very common, though they are found both in the north and south of the district; leopards are not so scarce. buffalo are occasionally found in the swamps at the foot of the Khasi Hills, and wild pig, sambar (cervus unicolor), hog deer (cervus porcinus), and swamp deer (cervus duvauceli) can be shot in the same locality. game include various kinds of duck and teal, snipe, jungle fowl, and marsh partridge. In 1903 only three persons were killed by wild animals, i.e., one by a tiger and two by wild pigs, but snakes were responsible for 75 deaths. Rewards were paid in that year for the destruction of 11 tigers and 10 leopards.

# Statement A.

Thana.				
	Tahirpur	•••	•••	28
	Dharmanasha	***	•••	40
Sunamganj	Dirai	•••	•~	31
SUNAMBANJ	Dirai Sunamganj Jagannathpur	•••		70
•	Jagannathpur	•••	•••	18
	(Chhatak	•••	•••	25
	(Lakhai		•••	7
	Madhabpur	O.,.	•••	5
	Banivachung and	Abidabad	•••	10
Habiganj	Baniyachung and Habiganj		•••	5
	Muchikandi	300	•••	3
'	Nabiganj	<i></i>	•••	7
	(Biswanath	9		6
1	Balaganj	4	•••	.14
	Sylhet	7	•••	7
NORTH SVIHET	Fenchugani		***	8
North Sylhet	Governghat	2.9	•••	16
	Golangani		•••	î
	Kanairghat	***	•••	16
	सन्यमन न	ात **	•••	10
ĺ	Maulavi Bazar	•••	•••	24
SOUTH SYLHET	Matiganj	•••	••	11
•	Matiganj   Rajnagar	••	•••	27
	(Karimgani			31
Karimganj	Karimganj Ratabari and Jaldhuh	Patharkandi	**	4
	Jeldhuh	***	•••	94

## Statement B.

Pargana in which situated and approximate Names of Haors. distance from Sylhet town. Banaiya in Pargana Dulali or about 22 miles S. W. from Sylhet. in Pargana Baniyachung or about 40 miles S. W. W. (I) Baram from Sylhet. Muktarpur or about 12 miles 8. E. from Bar Haor Sylhet. Barsoula Parganas Baje Jatua and Duhalia or about 18 miles W. from Sylhet. Barna " Pargana Renga or about 10 miles S. S. E. from Sylhet. (1) Benka Baniyachung or about 40 miles S. W. W. from ,, Sylhet. Chatal Gaharpur or about 12 miles S. from Sylbet, 11 Chaptihaor Naigang or about 35 miles S. W. from " 17 Sylhet. (2) Dekharhaor Pagla or about 30 miles W. by N. from ,, Sylhet. Baniyachung or about 35 miles S. W. from Ghuldhuba ,, Sylhet. Mandarkandi or about 36 miles S. S. W. from Gungijuri Sylhet. Baniyachung or about 40 miles S. W. W. (1) Habibpur from Sylbet.

Hail or Baruna in Pargana Chowalis or about 45 miles S. by W. from Sylbet.

Hailar haor in Parganae Sukhair and Betal W. S. W. from Sylhet.

Hailka in Pargana Regna or about 10 miles S. S. E. from Sylhet.

Hakaluki ,, ,, Pathariya or about 22 miles S. E. from Sylhet.

(4) Jamaikata ,, ,, Atuajan or about 25 miles W. S. W. from Sylhet.

## Statement B-contd.

	Numes of Haors,			Pargana in which situated and approximate distance from Sylhet town.
(3)	Jhinker ha	or in	Pergana	Ichakalas or about 16 miles N. W. from Sylhet.
(3)	Jilkar hao	r †,,	19,	Ichakalas or about 16 miles N. W. from Sylhet.
(2)	Jawar	"	,,	Lakhansiri or about 30 miles W. by N. from Sylhet.
	Kagapash	٠,,	"	Baniyachung or about 35 miles S. W. from Sylhet.
	Kawadigh	i ,,	"	Sameernager or about 25 miles S. W. from Sylhet.
	Maijal	,,	11	Gaharpur or about 12 miles S. from Sylhet.
(1)	Maka	,,	11	Baniyachung or about 40 miles S. W. W. from Sylhet.
(1)	Makalkand	li "	",	Baniyachung or about 40 miles S. W. W. from Sylhet.
	Makarei	**	**	Muktarpur or about 17 miles 8, from Sylhet.
<b>(</b> 4)	Mahai	"	17	Atuajan or about 25 miles W. S. W. from Sylhet.
	Muktarpur	11	,,	Muktarpur or about 12 miles S. E. from Sylhet.
(4)	Nalua	**	"	Atuajan or about 25 miles W. S. W. from Sylhet.
(4)	Parua	,,	"	Atuajan or about 25 miles W. S. W. from Sylhet.
(5)	Sanir haor	"	"	Laur or about 50 to 60 miles W. N. W. from Syhlet.
(2)	Shurash	**	n	Duhalia or about 30 miles W. by N. from Sylhet.

#### Statement B-concld.

	Names of Haors.	Pargana in which situated and approximate distance from Sylhet town.		
	Soulagarh in Pargana	Baje Jatua or about 18 miles W. from Sylhet.		
	Sowlahaor ,, "	Beraya or about 6 miles E. from Sylhet.		
(5)	Tangua " "	Bangsikunda or about 50 to 60 miles W. N. W. from Sylhet.		
	Togarhaor ", ",	Selberas or about 60 miles W. from Sylhet.		
	(Ramdigha)			

Note.—The numbers prefixed to certain names indicate that the haors bearing the same number are joined with one another when the floods are at their height and become large sheets of water interspersed with jungle.

सन्यमेव जयते

#### CHAPTER II.

#### HISTORY.

Early history—Gaur—Laur and Baniyachaung—Koch invasions—The Jaintia Parganas—Sylhet under British rule—Khasi raids—Disputes on Cachar frontier—Riots at Sylhet—The Burmese war—Lushai raids—Floods—European settlers—The cowry currency—Development of excise system—Early salaries—Public buildings—Sylhet in 1837—The mutiny year—Archæological remains.

Little is known of the history of Sylhet, but, like other countries in the early stages of civiliza-Early History. tion, it seems to have been split up into a number of petty chiefships. These were administered by little princelings, who enjoyed a certain degree of independence, though dominated at first by the Tippera State, and afterwards by the Muhammadans. The present Raja of Hill Tippera traces his family back to Drujho, one of the lunar race of kings, whose descendant Daitya is said to have fled after the battle of Kurukshetra to the jungles of Hill Tippera.\* It is possible that the ancestors of the Raja originally came, as is alleged, from Central India; but there seems to be little doubt that the Tipperas are closely allied with the Bodo or Kacharis, and it is generally thought that a considerable portion of the present inhabitants of Sylhet were originally descended from that stock. With regard to the claim made by the royal family to more exalted lineage, it should be borne in mind that more than one matrimonial alliance has been made

<sup>\*</sup> Vide report submitted to the Bengal Government by the Political Agent to Hill Tippera in 1875.

with the reigning houses of Cachar and Manipur, a fact which is not without its own significance.

A thousand years ago the Karimganj subdivision seems to have been included in the Tippera kingdom. In 640 A.D. the Raja wished to perform a sacrifice on an unusally imposing scale, and obtained five Brahmans from the Itwah village in Kanouj to preside over the ceremonies. Subsequently, with the object of retaining the holy men in this outlandish corner of the world, he gave them a grant of land which is said to have been situated in the Panchakhanda pargana in the Karimgani subdivision. This land was bounded on the north and west by the Kusiyara river, and on the south and east by the villages of Hankala Kukis, a tribe from which the Hakaluki haor is said to take its name.\* Various tanks and old ruins in the South Sylhet subdivision are ascribed to the descendents of these colonists. In 1195 A.D. a Brahman named Nidhipati, who was descended from one of the five original immigrants from Kanouj, received a grant of land in what is now known as the Ita pargana, from the Tippera king. From this family sprung Bhanu Narayan, who was given the title of Raja as a reward for services rendered in the capture of a rebel. Tradition has it that his house was located on the site now occupied by the Rajnagar thana, and the large tank in the immediate vicinity is said to have been excavated by his orders. His eldest son, named Subid Narayan, built a fort on the

<sup>\*</sup>A note prepared by Babu D. N. Chaudhuri is the authority for this statement and of the account given of Raja Subid Narayan. The copper plate, which is the authority for the grant, is said to be still in axistence in Hill Tippera.

Barua hills to the east of the Ita pargana, the ruins of which are to be seen at the present day. A tank called Balda sagar was excavated at the instance of his daughter, but he is best known by the Sagar dighi, a large tank which he had dug, and on the banks of which he proposed to build his house. He was, however, suddenly attacked by a Pathan from Murshidabad named Khowaj Osman, and in disgust committed suicide while worshipping in the family temple. A few years later Khowaj Osman, the ruins of whose fort is still to be seen in the Ita hills in the Srisurjya mauza, rose in revolt with other zamindars, and seized parganas Ita, Taraf, and Sylhet, but was subdued by Lodi Khan, grandson of Surwar Khan.

Gaur, or North Sylhet, was originally ruled by a line of Hindu kings. Nothing is known Guur or North either of their dynasty or fortunes. and they were probably petty local princes with less power and influence than that enjoyed by a big zamindar of Bengal at the present day. The downfall of the last Raja, Gaur Gobind, is said to have been due to his severity towards a follower of the Prophet. This man had sacrificed a cow to celebrate the birth of a son. animal was being dismembered a kite swooped down. caught up a piece of flesh, and dropped it in the house of a holy Brahman. On the matter being reported to the king, he ordered the unfortunate infant to be killed and cut off the father's hand. The man applied to his co-religionists for help, and an army was despatched under Sikandar Shah, but met with no success. A second force was then sent under Sayed Nasir Dey, which was

accompanied by the famous fakir Shah Jalal. This man had been born in Yemen in Arabia, and had been sent by his uncle to Hindustan. He had been given a sample of earth and had been ordered to settle wherever he might find earth of the same character as the sample he took with him. Shah Jalal crossed the Brahmaputra and the Surma on a mocholla or praying seat, and proceeded to reduce Gaur Gobind by methods which no ordinary man could be expected to The Hindu Raja had built himself a magical seven-storied tower, to which he retreated on the approach of the invaders. Shah Jalal each day offered up a solemn prayer, at the conclusion of which one of the stories of the tower collapsed. Gaur Gobind endured this mysterious destruction of his fortress for four days and then surrendered, and Shah Jalal, who, in the course of his prayers, had discovered that the earth of Sylhet resembled that of his uncle's sample, determined to take up his permanent abode in the newly conquered town. The administration of the country was made over to Sikandar Shah, and a mosque was erected for the great fakir who was really responsible for the victory. The mosque in which his bones now rest is regarded as a place of the greatest sanctity, and the tombs of his 360 disciples are still to be seen in almost every part of the town.\* The defeat of Gaur Gobind took place in 1384 A.D., and from that time onward this portion of the district was ruled by the Muhammadans.

The authorities on the subject of Shah Jalal are a note by Dr. Wise in J. A. S. B., Vol. 42, Pt. I., and an account of Sylhet written in 1874 by Sumbhoo Chunder Dey Munsif. Dr. Bloch is of opinion that the narrative of Shah Jalal's life is so thickly overgrown with fiction that it remains a matter of doubt whether he is a historical person at all. It is said that he died in 1195 A. D., and if this date is correct he obviously could have had nothing to do with the conquest of Sylhet.

At the time of the conquest of Sylhet by the Muhammadans, Laur, which is situated Laur and Baniya-chung. in the north-west corner of the district. was ruled by aline of Hindu princes.\* This family traced its origin to a Brahman named Keshab Misra, who had left Kanouj to seek his fortunes in the east. One of his descendants, named Ramnath, had three sons, the eldest of whom remained at Laur, while the second had a palace built for him at Jagannathpur, and the youngest was established at Baniyachung. The eldest son had no descendants, and Durbar Khan, the head of the Jaganuathpur branch, seized the whole of Laur, much to the disgust of Gobind Singh who was ruling at Baniyachung. On Durbar Khan's death, Gobind Singh endeavoured to obtain his share of Laur, but Durbar Khan's sons appealed to the Nawab of Murshidabad, who arrested Gobind Singh and carried him off to Murshidabad. There he was converted to the faith of Islam, and as a reward was given possession of the estates at Laur, though as a feudatory and no longer as an independent princeling. In 1744 A.D. Laur was burned by the Khasis, and many of the people moved to Baniyachung, where Abed Reza, the son of Gobind Singh, had already made his home. It was about this time that a tribute of 48 long boats was imposed on Baniyachung, and subsequently three-fourths of the estates were assessed to revenue. Abed Reza built a large fort in Laur, the ruins of which are to be seen at the present day, and his son Umed excavated a deep most round Baniyachung. The descendants of this noble house are

<sup>•</sup> Most of the information embodied in the following paragraph is merely traditional, and has been supplied to me by Babu Padmanath Bhattacharya Bidyabinod, M.A.

still living in that village, but have lost their wealth and influence and are in very reduced circumstances.

Another version of the origin of Baniyachung is that a merchant, who was travelling with a crew of Chung or Namasudra boatmen, anchored in the haor over the site on which the village was subsequently built. An image of the goddess Kali was in the boat. During the night the merchant dreamed that the goddess declined to leave the place, and informed him that, if he would only settle there a Brahman would become the ruler of the town. The waters gradually disappeared, as they do at the present day on the cessation of the rains, and a village was founded by the pious merchant. first Raja was a Brahman named Keshab Misra. One of his descendants, Gobind, quarrelled with the governor Sylhet, and was summoned to Delhi where he embraced the moslem faith. The story of the Baniya and his Chungs would seem, however, to belong to the category of myths. सन्यमेव जयने

In the latter part of the sixteenth century Silarai, the brother of the great Koch king Nar Narayan, is said to have defeated the Raja of Sylhet. The territories of this prince were near those of the Jaintia Raja, and he is described as being a very powerful monarch. As has been already pointed out, Sylhet proper had been conquered by the Muhammadans two centuries before, but it is possible that the chronicler may be referring to the king of Laur, or to some quasi-independent Raja south of the

Kusiyara.\* The battle lasted for three days, and was finally decided by a furious charge, headed by Silarai in person, in which the king himself and an immense number of his followers went down. His brother Asirai abandoned the unequal contest, and returned with Silarai to the court of Nar Narayan. The Koch prince restored to him his brother's kingdom, but imposed a tribute of 100 elephants, 200 horses, Rs. 3,00,000 and 10,000 gold coins, an assessment which must obviously have been a polite invention of the chronicler.†

The account given of 'Sircar Sylhet' in the Ain Akbari is very brief, and is largely taken up with the description of two birds, a fact which suggests that the author of this, the earliest of Indian gazetteers, knew but little of his subject, or he would hardly have had recourse to such uninteresting padding. Sylhet is said to be "very mountainous,"—save the mark—and to furnish many eunuchs for the seraglios. The products mentioned are soontara, "a delicious fruit in colour like an orange but of an oblong form," China root, and lignum aloes, and the military strength is put down at 1,100 cavalry, 190 elephants, and 42,920 infantry.

The Jaintia Parganas are situated in the north-east corner of the district, and stretch from Therriaghat to the Cachar frontier

The Muhammadans do not seem to have had a very firm grip upon their conquest and the Tipperas are said to have overrun Sylhet for a short time in the sixteenth century.

<sup>†</sup> The Koch King's of Kamarupa by E. A. Gait, Shillong, 1895, page 27.

along the base of the Jaintia Hills.\* To the south they are roughly bounded by the Surma river—roughly, for pargana Satbank lies on the left side of that river, while between Golapganj and Sylhet there is a block of permanently settled land, which does not form part of Jaintia, extending as far north as Salutikar.

The territory of the Jaintia Rajas included, in addition to this portion of Sylhet, the hills inhabited by the Syntengs, and from time to time they succeeded in exercising some control over the country lying between the Jaintia Hills and the Kalang in the Assam Valley. How the Syntengs came to be united under a single ruler, while their neighbours and kinsmen on the west remained split up into a number of petty principalities, we do not know. History is equally silent with regard to the manner in which the Jaintia Rajas became the rulers and absolute owners of a tract of land in the plains of Sylhet, which at the present day is largely by Muhammadans. The royal family were of Synteng origin, and, though they had for many years been under the influence of Hinduism, they still retained the curious Khasi custom of inheritance through the female. This custom ultimately brought about their downfall, as it was the desire of the Raja's sister for a son that led to the kidnapping and sacrifice of British subjects.

These fragments of Jaintia history prior to 1774 A. D. are taken from the Ahom Buranjis and a paper by Mr. E. A. Gait published in the Journal of the Asiatic Society of Bengal, Vol. LXIV, Part I, No. 3, page 242.

The following is a list of the Jaintia Rajas as recorded by tradition. Against the names of four of them have been inserted the dates at which from the evidence of coins, inscriptions, and the Ahom chronicles it appears that they were living:—

- 1. Parbat Ray.
- 2. Majha Gosain.
- 3. Burha Parbat Ray.
- 4. Bara Gosain.
- 5. Vijaya Manik.
- 6. Pratapa Ray.
- 7. Dhan Manik (1618 A. D.)
- 8. Jasa Manik.
- 9. Sundar Ray.
- 10. Chota Parbat Ray.
- 11. Jasamanta Ray.
- 12, Vana-Singh.

- 13. Pratapa-Singh.
- 14. Lakshmi-Narayana (1710 A. D.)
- 15. Ram-Singh.
- 16. Jaya-Narayana.
- 17. Bara Gosain (1731-1770 A. D.)
- 18. Chattra Singb.
- 19. Vijaya-Narayana.
- 20. Rama-Singh (1813 A. D.)
- 21. Indra Singh.
- 22. Rajendra-Singh, until the annexation in 1835 A. D.

In the latter part of the sixteenth century, the Jaintia Raja, like the king of Sylhet, was reduced to a state of vassalage by the Koch king Nar Narayan. But the decline of the Koches was as rapid as their rise, and the Jaintia king must soon have succeeded in throwing off their yoke. According to tradition, the Raja was forbidden to mint coins in his own name; and this perhaps is why so few have been found which bear the name of the king in whose reign they were struck. The Jaintia coinage was made of unusually base metal, and two rupees which were assayed in 1836 were valued at 3 annas and 4 annas 9 pie respectively.

Dhan Manik is said to have been at war with the Conquest of Jain-tis by Ahoms in 17th teenth century, and, in order to enlist

the Ahoms on his side, offered to give his daughter to their Raja, Pratap Singh, if he would send to fetch her through the Kachari country. The ruse was successful, the Ahoms became involved in war with the Kacharis, and the Jaintia Raja was delivered from his enemies. successor Jasa Manik, so the story goes, went to Kuch Bihar where he married a Koch princess. With her dowry he received the image of Jainteswari, or Kali, which subsequently attained so evil a notoriety on account of the human sacrifices offered to it, sacrifices which ultimately led to the downfull of the Raja. At the beginning of the eighteenth century Ram Singh, the Raja of that time, kidnapped the Raja of Cachar, who had retired through the hills before the armies of the greatest of the Ahom kings, Rudra Singh. The Kachari prince applied to his former enemy for help, armies were despatched through the North Cachar and Jaintia Hills, the two princes were arrested and taken to the Assam Valley, and Jaintia was annexed to the Ahom territories. Raja himself has no claim upon our sympathies, as he seems to have been entirely responsible for his own discomfiture. But, then as ever, it was a case of quidquid delirant reges plectuntur Achivi, and the fate of his wretched subjects was truly lamentable. Jaintiapur was plundered and burnt, about a thousand persons were tortured to death, and even the women were not spared but were deprived of their ears and noses.\* Rudra Singh formally notified the Muhammadan fauzdar of Sylhet that Jaintia had passed into his possession, and the two Governments prepared to exchange lists of the

An Ahom chronicle is the authority for this statement.

products of their respective countries, with the object of facilitating trade. But though their monarch submitted, the hardy mountainers, over whom his rule was ever of the lightest, declined to accept an alien yoke. They rose as one man, butchered the Ahom garrisons in the hills, and resumed their former free and easy life. The Jaintia Raja died in captivity, but his heir was established on the throne, and the Ahoms made no further attempt to exercise an effective jurisdiction over the territory entrusted to him. Communications were, however, maintained between the two valleys, and in 1757, envoys from Jaintia are said to have been received by the Ahom king in the portico of the Hajo temple, and to have complained that the Sonapur duar had been closed by the Khairam Raja. The king ordered it to be opened as trade between the valley and the hills was doubtless highly advantageous to both parties,

The first occasion on which the Jaintia Parganas were entered by the British was in 1774 A.D. when Major Henniker led a force against the Raja. The causes which provoked this expedition are not on record, but some years afterwards the Collector comments on the excellent effect produced, and on the correct attitude of the Jaintia people towards our frontier as compared with the insolent violence of the Khasis.

In 1821, some emissaries from this State were detected in the act of kidnapping British subjects, with the object of sacrificing them at the shrine of Kali. One of the culprits admitted that human sacrifices had been

annually offered for at least ten years, in the hope that the sister of the Raja might, through the intercessions of the goddess Kali, be blessed with offspring. The princess was always present on the occasion of each sacrifice, and bathed her person in the blood of the victim, whose throat was cut by the officiating priest.\* Suitable punishment was meted out, and a solemn warning was given to Raja that any repetition of this offence by the confiscation of followed his territories. 1824, he entered into an agreement with Mr. David Scott by which he acknowledged himself be dependant on the British Government, and pledged himself to abstain from entering into any negotiation with a foreign power. Three years later, a second attempt was made upon the liberties of British subjects, and in 1832, a similar attempt was at last crowned with success. Three out of the four men seized were sacrificed to Kali: the fourth escaped and reported the outrage to the authorities. The Raja was called upon to deliver up the culprits, and, as he declined to do so, his territories in the plains were annexed in 1835.

The rest of Sylhet passed into the hands of the East India Company in 1765. The first resident to be appointed was Mr. Thackeray, the grandfather of the famous novelist, who built a large house near the site on which the bungalow of the Deputy Commissioner now stands. He was succeeded by Mr. Holland, who made a regular settlement of the district; and in 1779 came Mr. Robert Lindsay, who acted as Collector for upwards of ten years, and of

O Asiatic Journal, Vol. XIII, p. 177.

whose administration there is an interesting account in the Lives of the Lindsays. A British district has obviously no history which can be reproduced in a condensed form in chronological tables. Many years are barren of incident, the crops are sown and reaved, the traders come and go, one generation gradually melts into another and there is nothing for the chronicler to report. The laws which govern the actions of the people are passed elsewhere, the orders by which the Collector of Sylhet is guided are issued at Dacca and Calcutta, the district is part of a corporate whole and is no longer a separate entity, to work out its ruin or salvation for itself. At the same time, interesting letters can be found which enable us to truce the gradual development of the administration, and in the following pages reference is made to such arrangements or events as seem of interest. No allusion has been made to the land revenue history, as this extremely complicated subject is dealt with in the chapter on land revenue.

Under Mughal, and for some time under British rule,

Frontier troubles. Sylhet was a frontier district, and was exposed to all the inconveniences that such a position usually entails. The Khasis were a continual source of trouble to the Muhammadans, and it was not long before they came into collision with the British. Difficulties seem to have first arisen in 1779. A letter from the Collector in that year refers to the value of the trade between Calcutta and Panduah, a village situated near Bholaganj, which a hundred years ago occupied the position which is enjoyed by Chhatak at the

present day. The Khasis seem to have been encouraged to adopt an offensive attitude by the conduct of some 'low Europeans,' who had treated them with undue deference; and Mr. Lindsay was compelled to ask for sanction to the construction of a small fort, surrounded by a brick wall, which would afford protection to the merchants. first serious outbreak, after Sylhet came under British rule, occurred in 1783, when the Khasis demanded the head of a havildar, whom they charged with having treated them with contumely. This calm request was naturally refused, whereupon they attacked the thana, and there was "considerable loss on both sides." Mr. Lindsay's own lime works did not escape, and his servants, so he says, were cut to pieces. Four years later the Khasis of Laur joined forces with the people inhabiting the submontane tracts: ravaged the parganas of Atgram, Selbaras, Bangsikunda, Ramdiga and Betal, and put to death upwards of 300 people.\* Troops were despatched without delay to the foot of the hills, but they found that the raiders had already retreated to their mountain strongholds.

A few months later Mr. Lindsay left Sylhet, and the office of Collector was assumed by Mr. John Willes, a gentleman who does not seem to have been endowed by nature with the character and temper that are best adapted for the administration of a turbulent and frontier district. At the end of 1788 a Khasi freebooter, named Ganga Singh, plundered the bazar and thana at Ishamati, and put to death one Bara Chaudri with his family. A native officer was then

सन्धर्मव जयते

Collector's letter No. 84, dated 26th October 1787.

deputed to enquire into the condition of the submontane tracts, and he reported that the people had been reduced by the Khasis to a state of abject misery and were living on grass and fish.\* Panduah was garrisoned by a force of sepoys, but in June 1789, the Khasis made a bold attack upon the place, and killed several of the rank and file, Two European merchants who were staying in the village escaped with difficulty, and the thanadar was at first reported to be killed. Mr. Willes at once addressed the Government at Calcutta, but seems to have been reluctant to take any action on his own responsibility. was sent to relieve Panduah which achieved its object, to the great satisfaction of the Collector, "without bloodshed," and in all his dealings with these savages he unfortunately displayed a mildness of character which only confirmed them in their lawless inclinations. His temper can be judged from a letter to Lieutenant Cheape, who was in command of the sepoys on the frontier, in which the following sentences occur: "I must conclude in entreating you in the strongest terms to shew in future all possible lenity to such persons as may be so unfortunate I further entreat you that as to be wounded. in no instance the sepoys be allowed to fire on any person except when in the direct act of opposition."

The Collector admitted to the Supreme Government that he had no authority on the northern frontier of his district, and that, if he were to summon the Khasi sirdar of any of the 137 villages cultivated by the Sylhet raiyats, "he would refuse to obey, threaten, and probably cut off

Ocilector's letter No. 123, dated 19th February 1789.

the head of the messenger, and then call down his relations from the hills to revenge what he would consider an insult." But while making these admissions, he does not seem to have been fully sensible of the desirability of making some attempt, at any rate, to assert the Company's authority. Some of his observations on the policy to be adopted were just enough. He pointed out that, since Major Henniker's expedition into Jaintia in 1774, the people of that country had abstained from raids into Sylhet, that submission and conciliatory measures had merely incited the savages to further violence, and that the Khasis must be taught that they were attacking the Company, and not the fauzdar of Sylhet, with whom in the times of the Mughals they seem to have carried on an intermittent warfare. He was, however, better in council than in action, and he does not seem to have made any attempt to personally suppress the "Punishment," he wrote to Lord disorders in his district. Cornwallis, " can hereafter be given, but that should not be attempted rashly by a Collector, whose passions may be engaged, whose motive may be suspected, and whose character may be implicated." He concluded by requesting that the Governor-General would act on his own discretion, as he, the Collector, was not well acquainted with the condition of the Khasis. Troops were, however, despatched to Panduah who quieted the hillmen for a time, but in 1795, the Khasis again raided on the plains.

In 1799, the Collector reported that the district had been freed from the vexatious inroads of the hillmen, and proposed that the submontane parganas should be measured up, as this

work had been left undone by Mr. Willes owing to the unsettled condition of the frontier. The Khasis seem at this time to have given little trouble, and in 1825 a medical man was deputed to report on Cherra Punji; but two years later a sepoy, a dakwallah, and a dhobi were murdered by the hillmen in the neighbourhood of Panduah. The Collector of that time was not the man to tolerate such outrages, and in the absence of the Agent to the Governor-General, he took upon himself to request the officer commanding the Sylhet Light Infantry to retaliate on the parties concerned, and, if they were in open arms against the Honb'le Company, to take such steps as might be necessary for their restraint. The steps taken seem to have been sufficient, but in 1831, two years after the massacre at Nongkhlao, a raid was made upon the village of Kanta The raiders were dispersed by the Sylhet Light Infantry under Captain Lister, and since that date the Khasis have ceased to be a source of anxiety or embarrasment to the Administration. सत्यमेव जयते

Trouble was, however, experienced on the eastern as well as on the northern frontier. In 1799, a Mughal, named Aga Muhammad Reza, entered Cachar from Sylhet, and for a time seems to have succeeded in making himself master of that country. He seduced the Naga Kukis from their allegiance, cut up some borkandazes sent against him by the Raja, and compelled that prince to take refuge in the hills. He then assumed the character and attributes of a prophet, styled himself Immaum Mehadri, and sent 1,200 of his followers to attack the Company's thana at Bondassye. This thana was garrisoned by one havildar and

eight sepoys. The Kacharis are said to have attacked this small force with 300 men and two three-pounder guns, but they were repulsed with some loss, after a smart engagement. The attack was renewed under the personal direction of the prophet, but in the meanwhile the thana garrison had been reinforced by 70 sepoys, and the Kacharis were driven back, with a loss of 90 men and 5 small pieces of cannon. Their leader made his escape, but was subsequently arrested, and peace and tranquillity were soon restored. So strong, however, had been his influence that many Hindus in the eastern portion of Sylhet are said to have abjured their faith and turned Muhammadan.

A few years later disputes arose with regard to the boundary between Sylhet and Cachar. Disputes with Raja of Cachar. 1807, a line was laid down by an amin, but very shortly after the completion of the work, the Raja's people trespassed upon the estate of one Mooluck Chund, filled up the ditches which had been dug along the boundary, and carried off the crops. An amin was again deputed to lay down the line, but, as soon as the crops ripened · for the following harvest, the Raja's people again appeared Raids were also made on pargana upon the scene. Chapghat, and the crops were forcibly cut and carried Stringent orders were accordingly issued to the native officer at the Badarpur thana to 'prevent these savage intruders from committing such ravages'; but subsequently it was found that Mooluck Chund's title to the land was very doubtful, and it appeared that the line laid down by the amin included a portion of the Raja's territory.

Trouble, however, was experienced from within as well as on the frontier. The natives Internal commo-tions. of the district were turbulent and unruly, and, as is not unfrequently the case in frontier tracts, had little respect for the majesty of the law. In 1779, a havildar and ten sepoys were despatched to put an auction purchaser in possession of his newly acquired estates in Balisira. The former proprietor resisted the officers of the law by force, killed two and wounded several others, and effectually prevented them from carrying out their orders. Not content with this, he proceeded to plunder two boats loaded with upwards of two thousand rupees worth of cowries, the property of Government. A stronger force was then sent from Sylhet which succeeded in giving the auction purchaser possession, and the former owner fled. But he fled only to return again with a large body of men, who surprised and fired the cutcherry, cut down the sepoys who offered them resistance, and made the others prisoner. The outlaw was, however, compelled again to fly, and was subsequently arrested by the authorities at Dacca.

Three years later there was a serious outbreak during the *Maharram* at Sylhet, of which the following account was given by Mr. Lindsay:—\*

"At this last place (Sylhet) the Musalmans had become uncommonly violent. The period of the Maharram, or annual festival of the Islam faith, was approaching, when a deputation from the Hindu inhabitants came privately to inform me that

<sup>·</sup> Vide Statistical Account of Assam, Vol. II, page 355.

they had certain intelligence that the Mahammadans meditated an assault upon our Government on that day, and that it would likely commence by an attack on the Hindu temples in the town. I told them that I could not believe it, as they had hitherto shown no indication of riot. My military force at that time being a good deal scattered in the Province, not more than forty or fifty men could be mustered fit for duty, and I desired my jemadar, or black officer, to have all in readiness in case of a fray. Nothing occurred during the day of the festival, until five in the evening, when the Hindu inhabitants rushed into my house in numbers, covered with marks of violence they had received from Mahammadans. I went into my room for a few minutes, dressed my pistols and gave them to my favourite black servant, desiring him to keep near me, and, if he saw me in danger, to put them into my hand. I carried a light horseman's sword under my arm. There was no time for delay, as the town was on fire in different directions. With my small force I marched to the place where the crowd was collected, and found to my surprise that the numbers were much more considerable than I expected As I advanced they retired to a strong position upon a hill, and there took post. I followed them to the top, and drew up my sepoys on a table-ground directly opposite to them, where they stood with shouldered arms. I then went forward with my black officer to hold a parley on the spot. I found their leader a priest of considerable rank, at the head of three hundred men. He was incolent in his manner. I was perfectly calm. I told him that I presented myself before him in the capacity of Head Magistrate; that I was informed a fray had happened, which I would investigate next day, and render justice where due; that my object at that moment was to compel him to lay down his arms and retire peaceably. He immediately drew his sword, and exclaiming with a loud voice, "This is the day to kill or to die, - the reign of the English is at an end!" aimed a heavy blow at my head. This I was fortunate enough to parry; but he struck so hard that my sword was broken, and a little more than the hilt remained in my hand. My black servant at the same moment thrust a pistol into my hand, which I instantly fired, and the priest fell; and so close were we in contact that his clothes were set on fire. My sepoys in the rear, seeing my dangerous situation, discharged a platoon while I stood in front, from which I miraculously escaped. My black officer and I rushed back into the ranks in time to prevent their giving way. We then charged with bayonets and drove the armed multitude over the bill.

"I had now time to look about me and survey the mischief that had been done in so short a time. The high priest and his two brothers were lying dead on the ground, and many of his dependents were wounded. On my side one sepoy was killed and six wounded. Most fortunately my people did not give way—if they had, every European in the place would have fallen. I now asked for my assistant, Mr.—, who I supposed had been killed; he soon appeared, and candidly informed me that the scene was too much for his nerves, and that he had retired during the combat. This event was of too serious a nature not to be reported to Government. They immediately ordered a reinforcement of troops, supposing me under temporary difficulty; but the tumult soon subsided, and the order was countermanded."

Mr. Lindsay was a firm and resolute Collector, but the strength of his conviction that there Raids on the east and north. would be no renewal of the disturbances. and his refusal of the proffered reinforcements, suggests that the number of rioters who fell was larger than he felt disposed to say. Again in 1786, one Radha Ram, a zamindar on the eastern frontier of the district, attacked the Chargola thana, with a following of Kukis, and killed and harried the villagers. Mr. Lindsay promptly despatched some sepoys to the place with instructions to burn the villages of Radha Ram's people, and to lift his cattle; and in a very short time the zamindar himself was seized. The letter that reports his capture to Mr. (afterwards Sir John) Shore curtly announces annoying fact that a tribe of hillmen had surprised the thana of Laur, killed the thanadar and twenty of his men, and made their way back into their mountain fastnesses. During the declining days of Mughal rule the administration had been lax, and it was some years before the people learned that the authority of the Company could not be set at defiance with impunity. The fact that at this time there were neither criminal nor civil courts in Sylhet was also said to be a source of difficulty. Suitors had to proceed to Sultansi which was a considerable distance from their homes.

The aggressive conduct of the Burmese in 1824 Surmess War in 1824. caused some anxiety in Sylhet. Troops were at once pushed up to the frontier fort at Badarpur, and, when the enemy approached, they advanced into Cachar and inflicted a severe defeat upon them at Bikrampur. The Burmese then withdrew, but in June it was reported that they were again advancing, and, in spite of the inclement weather, reinforcements were hastily despatched towards the frontier. itself escaped the inconvenience of a raid, but great difficulty was experienced in obtaining transport for the expedition. Boats, which had to be sent up to Badarpur, were manned by 50 persons, most of whom were witnesses who were waiting to give evidence at the cutcherry and had been summarily impressed! "With the greatest difficulty and by subjecting our own subjects to the most dreadful privations and sufferings" 7,000 men were gradually collected, but they charged the guards who were set over them, and broke through every opposition. Apart from their reluctance to accompany the expedition, the Commissioner doubted whether the coolies would be able to carry to Manipur more than the provisions required for their own consumption on the way. The people fled panic stricken from their homes to escape impressment, the fields remained untilled, and the Magistrate was compelled to warn the General in Command that famine might ensue. Stories of the impressment of

the people travelled up to the Khasi Hills, and added to the difficulty of obtaining labour when the road to Assam was being constructed in 1829. The Khasis are, and always have been, an extremely independent people, and the accounts they heard of the way in which coolies had been seized in Sylhet at first rendered them disinclined to do any work for Government.

About the time that Sylhet was freed from the fear of marauding raiders from the north, the wild tribes from the southern hills began to make incursions on the plains.

The first outrage on record occurred in 1826, when a party of wood-cutters was murdered by Kukis. Messengers were sent up into the hills, and ascertained that the cause of the outrage was the failure of the zamindars of Pratapgarh to make their customary presents to the tribesmen. The Kukis took this opportunity of clearly laying their demands before the Government, and detained two of the envoys as hostages, while the third was sent to fetch the ransom of the other two. Government paid the money to obtain the release of its two emissaries, and orders were issued for the exclusion of the Kukis from our markets.

In 1844, Sylhet was the scene of a far more serious outrage. Laru, a Poithu chief of some importance, died, and his son Lal Chokla determined to give him a funeral worthy of his merits. On April 16th, he descended upon the Manipuri colony of Kochabari in Pratapgarh, and in the darkness of the night succeeded in securing twenty heads

and six living captives. Efforts were made to obtain redress through the Raja of Hill Tippera, and when they proved fruitless, an expedition was despatched, under Captain Blackwood, into the hills. He succeeded in arresting Lal Chokla, who was brought down to the plains, tried, and sentenced to transportation for life, in spite of his plea that he did not know that the Manipuris were under British protection, a plea in which very little reliance could be placed.

Three years later the Kukis again descended from their hills, and massacred upwards Raids in 1847 and 1849 followed by Colonel Lister's expedition. 150 persons. After prolonged of investigation, it was ascertained that the scene of the outrage lay outside British territory, and it was left to the Raja of Hill Tippera, in whose country the incident occurred, to take such action as he thought to be desirable. Further raids were, however, made within the boundaries of the district in 1849, and, as even more serious outrages were reported from Cachar, Government determined to send an expedition into the hills. A force was despatched under Colonel Lister which captured one village and then withdrew, as the officer in command did not consider that it was sufficiently strong to justify his advancing further through such difficult country, against so powerful an enemy.

In 1862, Sylhet was raided again, three villages about eight miles from Adampur were plundered by abortive dered and burnt, and a large number of the inhabitants massacred and carried off. Government ordered that a strong force of armed

police should be established somewhere on the Sylhet frontier, and pressure was put upon the Raja of Hill Tippera, as it was thought that his subjects were to some extent responsible for these raids. At the end of 1868, a village near Adampur was again attacked, and as this was only one of several outrages along the southern frontier of the Province, an expedition was despatched into the hills. The climatic conditions were, however, most unfavourable, the central column was detained by seven days' continuous rain which rendered the route impracticable, and the troops were compelled to retire without either rescuing the captives or punishing the guilty tribes.

In January 1871, the village of Kacharipara near the Chargola outpost was burnt, and 20 Raids in 1871. persons killed, and an attack was made on another village immediately opposite to the outpost. Five weeks later a village near the Alinagar outpost was raided; but these were merely incidents in the general outbreak that occurred along the frontier. Such continuous and sanguinary raids called for vigorous repressive measures, and in 1871-72, a strong force was sent into the Lushai Hills, the troops advancing in two columns from Cachar and Chittagong. Since that date the peace of the Sylhet district has been undisturbed, though further out rages on other portions of the Indian Empire rendered the annexation of the Lushai Hills a disagreeable but unavoidable necessity.

The history of the Lushais and their raids will be found in greater detail in the gazetteer of the Lushai Hills, and reference has only here been made to the

comparatively small number of outrages perpetrated in Sylhet.

Towards the latter end of the eighteenth century the district suffered from a succession of heavy floods, which, if implicit reliance can be placed upon the records, produced effects of the most appalling character.

In 1781, the country was desolated by an inundation which is described by Mr. Lindsay in the following terms: \*

"In 1781, and also in the preceding year, there had never been such bountiful crops of rice, insomuch that the granaries could not contain it, and the value of the commodity was so extremely depreciated that it would not pay the expense of carrying it to market. I was, therefore, under the necessity of stating to Government the total inability of the farmers to pay their rents, especially as, in this poor district, they had not the same resources as elsewhere, rice being our only source of revenue. A suspension of rent was in consequence allowed. No sooner was the indulgence granted than one of those dreadful inundations took place to which the country is subject, which in a few weeks involved the whole country in general calamity. The river, from being very low, rose thirty feet perpendicular, overflowing its banks and sweeping everything before it. A more dreadful scene could not be imagined, nor could relief be given to the numerous objects who were seen perishing in the torrent,the cattle and wild animals of every description were observed indiscriminately floating down the stream. The granaries upon the banks, filled with the late superabundant harvest, were all swept into the flood, and thus from a general plenty we were in the course of ten days reduced to a state of famine. All was gone excepting a few partial stores on the high grounds. first thing I did was to despatch express boats in every direc-tion, to bring back the grain we had sent from the Province sometime before, now finding its way to distant markets. In this we succeeded, and part was brought back, but we had a dreadful prospect before us: the greater part of the last year's

<sup>•</sup> Vide Statistical Account of Assam, Vol. II, page 354.

crop was destroyed, and, what was worse, the rice lately planted was so completely laid under water that it could offer no hope of relief.

"My own case was embarrassing, for I had now to give the Supreme Board an account directly opposite to that I had lately furnished. Government, however, immediately assisted us; but at the same time, my story appeared so very improbable that they sent up a confidential person to report to them, from ocular demonstration, the actual state of the country. From the scarcity that prevailed, this gentleman never reached me; but his report of the desolation and misery he saw in the lower country fully corroborated my previous statements, and Government, in consequence, gave much assistance, but I am sorry to say nearly one-third of the population died.

"I must here mention one instance of the industry of the people at this juncture. They sent up and brought rice plants from the seed beds on the high grounds; but, their low lands being under water, they were obliged to plant them in a manner not altogether new, but seldom practised, and to which I was frequently an eye-witness. The work is carried on in canoes. one end of the boat were deposited the rice plants, on the other side a heap of well-tempered tenacious clay; the boatman, holding two or three rice plants in his left hand, attached to each a lump of clay and dropped it into the water; it thus became anchored in eighteen inches of water. Many hundred acres of ground were thus cultivated; and this furnished in due time a considerable resource, so as to save many of the inhabitants from famine. In the situation so described, provided the flood during the periodical rains rises gradualy, the plant will grow to the height of twelve or fourteen feet, always keeping its head above water; but if rapidly overflowed and depressed under water, even for one night only, it never recovers.

"Upon going to Dacca a few months afterwards, I saw many instances of men and women diving from their canoes to tear up from the bottom roots of grass and other vegetables as a miserable food for their famished cattle. Nor were the sufferings of the unfortunate natives yet ended. When the new crop was nearly ready for use, no persuasion could prevent them from satisfying their craving appetites, the frequent consequence of which was immediate death, or diseases which occasioned dropsy and dysentery, which destroyed many."

Three years later there were again complaints of The waters, according to the flood. More floods in 1785. Collector, rose to a height to which they had never before attained within the memory of man, the houses in the town were most of them submerged, and large quantities of cattle and many human beings perished.\* In September, it was said that the country from the banks of the Brahmaputra to Sylhet was like an open sea, dotted over with islands on which the people were living in a pitiable state; that two-thirds of the cattle had died, and that the villagers were endeavouring to save the lives of the remainder by diving to the bottom and scraping up weeds and roots of grass. Early next year, Mr. Lindsay told the Board that over twothirds of the cattle had been swept away and drowned. or starved from want of fodder, and, that one-fourth of the inhabitants of the low lands had perished, either from starvation, or from the diseases that are commonly induced by unwholesome or insufficient food.† In 1787, the Collector again reported a very serious flood,—the low parganas were entirely under water, the greater part of the cattle were drowned, and those that survived were kept on bamboo rafts. "The face of the whole country exhibits an extensive sea, and, where villages formerly stood, may be seen at a distance little mounds rising out of the waters, which on a nearer approach are perceived to be the wrecks of the habitations of the distressed raiyats. It is painful to recall to your recollection the distress of 1784, at the thought of which humanity

Collector's letter No. 46, dated 25th June 1784.

<sup>†</sup> Collector's letter No. 56, dated 13th March 1785.

shudders, but the waters are higher now than they ever were at any period of that year, and the damage is infinitely greater."\* There were heavy floods also in 1793 and again in 1795.

Under native rule the Surma had been protected by a dyke, but this work had been allow-Protective works. ed to fall into disrepair, and in 17.90, Mr. Willes constructed an embankment for a length of about one hundred miles along the side of that river. Six years before, the Supreme Government had sanctioned the expenditure of Rs. 8,000, on the repair of bunds along the Surma, Kusiyara and Manu,† and dykes were also kept in repair by native land-holders at their own expense. In 1814, the idea seems to have gained ground that these bunds were of comparatively little use. They were accordingly allowed to fall into disrepair, and, at the present day, the only one maintained is a dyke along a portion of the Surma river. The annual rainfall is so enormous, the general level of the country is so low, and the whole drainage system is of such a complicated character, that it is extremely difficult to control the action of the rivers. Nullahs and embankments that protect one village may very possibly do damage to another, and the greatest caution has to be exercised when tampering with the drainage of the country.

It is difficult to understand why, at the end of the were these floods been so much more liable to flood than it is at the present day. It is possible that the whole level of the district has been raised during

Collector's letter No. 80, dated 11th July 1787.

<sup>†</sup> No. 38 A. from J. Shore, dated 30th December 1784.

the last hundred years; it is possible that there was a cycle of exceptionally wet years, just as at the end of the nineteenth century, the rainfall throughout India was exceptionally scanty; and lastly it is possible that the floods in reality were not abnormally severe, and that what so impressed the imagination of Mr. Lindsay was little more than the usual condition of the country. At the present day almost the whole of the western portion of the district goes under water in the rains. Fodder for the cattle is brought from the hills, or dragged from the bottom as described by the Collector, and the houses of the villagers are crowded together on small islets of highland, which rise up here and there from out of the waste of waters. It is difficult to obtain reliable information with regard to the condition of the people now, it was almost impossible to do so then, and the estimates of mortality, both of men and cattle, were doubtless much exaggerated. The people had the strongest disinclination to pay land revenue, and clutched at any excuse which would relieve them from the necessity of doing so. Even a strong officer like Robert Lindsay experienced the greatest difficulty in realizing the demand, and he was naturally not disposed to minimise any calamity which would help to explain away the large outstanding balances. On more than one occasion the rainfall may possibly have been severe, but it is to be hoped that the sufferings of the people were not so terrible as was supposed.

That there was some distress and scarcity there seems little doubt. In 1788, Mr. Willes reported that rice was selling at Re. 1-8 per maund, though in former years four maunds could be purchased for one

Such was the general distress that he could not stir from his house without being beset by thousands clamouring for relief.\* It must, however, be added that four maunds for a rupee was an exceptionally low rate. In 1786, when rice sold at four and a half maunds to the rupee, the price was said to be so low as barely to cover the cost of cooly hire to the bazar, and in January 1798, the best rice sold at Sylhet for As. 12 a Owing, no doubt, to difficulties of transport, the grain market at that time was subject to sharp variations. Corners in wheat would have had but a short shrift from the administrators of that day. In 1773, the Collector was authorised to notify by beat of drum, that any merchant who concealed his grain and refused to bring it to the market and sell it at a reasonable price, would not only be deprived of all his stock, but would be placed in confinement till orders had been passed upon his case. As a precaution against scarcity the Government had recourse to public granaries, and more than once the Collector was directed to purchase and store a lakh or two of maunds of grain. सन्यमेव जयते

The efforts made by France to retain some share of
the valuable Indian trade, are illustrated by the action of a certain
M. DeChampigny. This gentleman seems to have come
to Sylhet in 1786, with letters of introduction from
M. Wilton, the French Commissary. Mr. Lindsay informed
the Governor-General that no obstacle would be placed in
M. DeChampigny's way, as long as he conducted himself
as a private trader. At the same time he pointed out that

<sup>·</sup> Collector's No. 19, dated 11th February 1788.

the French had never had a public agent in that portion of Bengal, and that they were naturally of an intriguing disposition; and he hinted pretty plainly that the Frenchman's actions in a turbulent and frontier district, surrounded by savage races who could easily be incited to invade our territory, would always call for careful attention from the Government. M. DeChampigny seems to have lived with Mr. Lindsay, and, during the administration of that vigorous pro-consul, he was wise enough to conceal his real intentions. On the advent of Mr. Willes he ventured to appear in his true colours. He purchased a plot of ground in a very arbitrary manner, the title of the vendor being extremely doubtful. He then began the construction of a fine bungalow, without applying for the consent of Government, as was required by the regulations then in force. When he was in need of stores from the interior, he issued orders on the people under a large seal : and he claimed to be exempted from the rules that applied to all other traders, under which boats carrying merchandise were compelled to attend at the bunder ghat for registration. He is said to have seized, confined, and fined those persons who offended him. On one occasion he arrested a talugdar, and, when ordered by the Collector to release him, his servants impudently denied that their master was in any way subject to the authority of Mr. Willes. But, worst of all, he endeavoured to establish political relations with the Khasis, an arrangement to which there were the strongest possible objections. The Khasi Hills were independent territory, Assam and Cachar were still under native rule, and there was serious risk that the French might establish a protectorate on our frontier, which would be a perpetual

source of danger and annoyance. The records are silent with regard to the ultimate fate of this imperious Frenchman. On the outbreak of war in 1804, he probably had to flee the country; but, for a time at any rate, he was a source of serious annoyance and anxiety to the unhappy Mr. Willes.

In spite of the restrictions imposed on settlers in the interior, there were a considerable number of Europeans in Sylhet a century and more ago. In 1778, Mr. Lindsay despatched two Englishmen, a Frenchman, and a Portuguese to Dacca, 'as no confidence could be placed in them,' and there were still some fourteen Europeans left, who had absconded, apparently from fear that they might share the fate of the other four. In 1799, there were no less than forty-four non-official Europeans in the district. The most important was, of course, the famous M. De Champigny, but numerically the strongest community were the Greeks, no less than thirty-one of whom were engaged in selling salt. They were altogether a distinctly cosmopolitan crew, which, in addition to the Greeks, included three Frenchmen, one Deluc, whose nationality is not specified but who presumably was not English, and a Dutchman who is described as very old and dumb. One cannot help wondering what an old and speechless Dutchman could have been doing in Sylhet a century ago.

In the early days of our administration the revenue of the district was paid in cowries.

As Mr. Lindsay says, it is difficult to understand how they became the circulating medium of a country three hundred miles distant from the

The only explanation he could offer was that sea. the people were so poor, and their rents so small, that a currency of extremely low value was required. The rate of exchange varied at different times, but, in Mr. Lindsay's day, four kahans or 5,120 cowries went to a rupee, and, as the revenue amounted to Rs. 2,50,000, the Collector had to receive nearly 1,300 millions of these little shells. The inconvenience of such a currency was indescribable. The cowries were generally received in baskets, and when they changed hands, the baskets were divided into groups of ten. The payee then counted one basket in each group, and, whatever deficiency was found in that basket, was supposed to run through the remaining nine. They were not received by weight, as the addition of a little sand would at once have turned the scale, nor by measure, as a little shaking made them settle down. They were fragile, and the Government of Bengal found it necessary to import shells, at a cost of more than a lakh of rupees per annum, to replace those lost and broken in the Presidency.\* They were cumbersome to receive, and troublesome alike to store in Sylhet, or to export to Dacca. Efforts were accordingly made by Government to induce the landholders to pay their revenue in rupees, and by 1819, two-thirds of the people had agreed to do so, and only 30,000 kahans of cowries were in store. This result was not attained without much difficulty. The price of cowries was raised by declining to issue them from the treasury, and at one time the Collector had nearly 1,100 millions of

<sup>•</sup> Letter No. 164 A., dated 9th September 1819, from the Board of Revenue to the Collector. The Collectors of Customs at the three seaports reported that 43,000 maunds of cowries were imported every year.

these little shells in the godowns at Sylhet. Arrangements were made to send them to other districts, to distribute them as diet money to prisoners, and to sell them locally; and gradually this medium of circulation, which assuredly must have been one of the very worst on earth, was banished from the district.

It is interesting to trace the development of the excise revenue in the early days of Development of the excise system. British rule, and the small beginnings from which the present system was built up. The consumption of spirituous liquor was naturally regarded with some disfavour by the Muhammadans, a tax of 5 kahans or about two rupees, was imposed on each maund landed at Sylhet, and each retail vendor paid a small registration fee of Re. 1 per annum.\* For some years after our assumption of the administration no attempt seems to have been made to obtain any revenue from excise, ; but in 1793 the Collector, under pressure from the Board of Revenue, issued licenses to four distillers. The fees received only amounted to Rs. 42, whether per mensem or per annum is not quite clear; but the actual incidence of the fees was not of much importance, as shortly after receiving their licenses, all the vendors disappeared. Further enquiries led the Collector to report that liquor was only drunk by the fishermen near Aimiriganj; but in 1798, he complained bitterly of the evil effects of opium. This, he said, was in very common use, or rather abuse, as the consumption of the drug gave rise to consequences of the most disastrous kind. "Opium if taken to excess, which commonly is the case, brings on an insanity which in general terminates either

Collector's letter No. 204, dated 3rd April 1795.

in suicide or murder. Instances of such fatal effects are so numerous and so well authenticated by the records of the Fauzdari Court, as to have attracted the particular attention of the Magistrate." \* Bhang and ganja were not generally used except by natives who had come from Hindustan. It is, however, doubtful whether the opium habit was as prevalent as the Collector thought. In 1814, the total amount of 'koppah' used in the district was said to be some 60 maunds, but, as 'koppah' consists of strips of cloth soaked with poppy juice, the actual weight of the drug was only 40 maunds, which certainly was not a very large amount. 'Koppah' sold for Rs. 6 per seer in Sylhet, and Rs. 4 in the mofussil. The lack of definite knowledge on the subject is well illustrated by the fact that, three years later, the Collector said that only one-third of 'koppah' was actutually opium, and that it sold from Rs. 6 to Rs. 10 per seer. It was subsequently proposed to charge a fee of Rs. 6 per annum for each license for the retail sale of ganja, Rs. 12 for opium, and Rs. 18 for "muddad," presumably madak. Two country spirit shops were settled at a rental of Rs. 17-4 per mensem, a fee that is in marked contrast with that now paid for the Sylhet shop which, in 1904, amounted to Rs. 738 per mensem. Other shops outside the town paid from one-half to onesixth of this very moderate demand. Even these small fees were found to be prohibitive in their effect, and in 1800, not a single license for the preparation and vend of spiritous liquors was taken out. In 1808, the Collector raised the license fee to As. 8 a day. This proposal found no favour with the Magistrate, who thought that, in view

<sup>•</sup> Collector's letter No. 216, dated 3rd June 1798.

of the large illicit trade in drugs and liquor, the fee should be within the reach of the poorest purse, and should not exceed As. 2 per diem. In 1813, the Collector estimated that one-half, or at the lowest calculation one-third of the population of Sylhet town, which, by the way, he calculated to be no less than 30,000 souls, drank spirituous liquor, and complained of the facility with which illicit distillation could be carried on. Two years later the practice was inaugurated of issuing Government opium from the Treasury. The price charged was Rs. 25 a seer, and the amount sold in the first two years was less than two seers. The price was then lowered to Rs. 20, and afterwards to Rs. 10, and a daily tax was imposed upon the vendor. This concession, coupled with a stern repression of the illicit opium traffic, sent up the issues in 1821-22 to over 24 maunds. Sylhet, however. has never been a great opium-eating district, and in 1904. only 16 maunds were issued from the Treasury.

It is sometimes thought that the salary of a Collector in the early days of British rule was small; and that, though there are now fifteen rupees to the sovereign instead of eight, as in Mr. Lindsay's day, the fall in exchange and the withdrawal of the right of trade have been fully counterbalanced by an increase in the scale of pay. This does not seem, however, to have been the case. Mr. Lindsay's salary was fixed at Rs. 1,500 per mensem in 1787, and he was further granted a house allowance of Rs. 150 per mensem.\* Whether he travelled by water or by land he drew a travelling allowance of Re. 1-1 per mile, as com-

<sup>•</sup> Letter No. 70A., dated 12th April 1787, from the Assistant Secretary to the Governor-General.

pared with the four annas and eight annas of the present day, though boat and cooly hire must have been much lower a hundred years ago than they are now. Mr. Lodge's travelling allowance bill for the journey from Calcutta to Sylhet in 1794 was no less than Rs. 1,061.\* Again in 1825, the Collector was allowed an aggregate salary of Rs. 2,510 per mensem, a larger sum than is drawn by any Collector at the present day.

But, if the salaries a hundred years ago were far from small, the expenditure on public Public offices. works was very light. The cutcherry itself was a very modest building. Mr. Ahmuty, at the end of the eighteenth century, reported that he had erected "a pucka godown divided into three apartments wherein the public records of my office have been ever since deposited; independent of which I rent two bungalows, one of which is occupied by the mohurrirs and writers, and the other appropriated to the use of my public cutcherry." The Governor-General desired that a suitable building should be provided for the Collector's office. That officer replied that if a proper building was to be constructed it must be at least equal in size to a common dwelling house, and contain four commodious rooms with verandahs on the north and The cost of such an office if made of the best materials would not be less than Rs. 10,000. The office erected for the Deputy Commissioner, after the earthquake of 1897, had a floor space of 35,000 square feet

<sup>•</sup> Collector's letter, dated 5th March 1794. The distance from Culcutta to Sylhet was said to be 998 miles, and mileage drawn accordingly. The Accounts Department at the present day hold that the distance via the Sundarbans is only 709 miles. It does not appear whether the same rates were allowed for journeys in the district.

including the verandahs, and though built after a plan in which economy is carried to the very verge of meanness, cost Rs. 1,68,000. The estimate sanctioned for the construction of a jail at Sylhet in 1788 amounted to Rs. 2,500, and affords a striking contrast to the Rs. 1,66,000, which have lately been expended on the existing institution. The godowns in which the myriads of cowry shells were stored were erected by the Collector at his own expense, and leased by him to Government. Mr. Lindsay says that they cost him Rs. 8,000, and he charged a rent of Rs. 100 per mensem, which for those days seems moderate enough.

One of the most serious disabilities under which the people of Sylhet labour at the present A Civil Surgeon of the 18th century. day is the want of proper treatment when they succumb to the unsanitary conditions in which their lives are passed, but the Medical Department has fortunately made some advance since the days of Mughal rule. In 1789, Mr. Willes complained that one Mohammad Jaffar was acting as medical adviser to the Nawab at Dacca, in spite of the fact that he held a grant of land worth Rs. 900 per annum, which had been given to his predecessors by the Mughal Government in consideration of their undertaking the duties now assigned to the civil surgeon of Sylhet. Mr. Willes requested that this gentleman might be sent back to the district to which he properly belonged, as the people were in great distress from want of either a Muhammadan or Bengali doctor. The unfortunate civil surgeon was expected to devote fully half of his annual grant to the purchase of medicines; but it is to be presumed that he was allowed to add by private

practice to the modest stipend he received from Government.

In the Friend of India of February 9th, 1837, the following gloomy account is given of the condition of the district. The writer seems to infer misery and deterioration from the fact that the revenue is not easily collected; but the difficulty experienced in realizing the very small Government demand, a difficulty which is experienced; now as then, is due to other causes:—

"In the sitting of the Board of Revenue on the 30th of January last, the present state of the district of Sylhet was brought under consideration. That district during the last forty years has been subject to a gradual deterioration; and has at length, reached that point of wretchedness which naturally produces a reaction. Forty years ago, it was, comparatively speaking, in a flourishing state; now it is a complete pauper warren. In the whole district there are not fifteen landed proprietors possessed of Rs. 5,000 and the condition of the great bulk of zamindars is in the last degree wretched. But it is of late years that the deterioration has taken the most rapid strides. In 1821, the district was in so prosperous a state, that a sale of land for arrears of revenue hardly ever took place. Even as late 1829, there were but sixty-three estates sold by the Collector; in 1834, the number of estates sold rose to about 250; the next year, the number was doubled; and in the past year, it had reached the extent of 1,004. At the close of the last accounts, it was found, that though the assessment of the entire district did not much exceed three lakhs of rupees, two lakhs of this sum remained unpaid, and that it became necessary to advertise 26,250 tenures for sale. But what is to restore comfort and security to the vast population whose sole dependance is on the food raised in a district, in which every estate, with the exception of a small fraction, is put up to sale? To complete the misery of the district, these sales, it appears, are attended by a set of speculators, who bid for the forfeited estates, though not themselves possessing more than the amount of the deposit money; and whose hope of gain in this lottery of desolation, is built on their being able to sell their purchase to advantage, before the settling day arrives."

Sylhet did not escape unscathed from the troubles In December a party of the of 1857. 1857. mutineers Chittagong entered the south of the district, with the evident intention of pushing on through the Surma Valley to Manipur. A detachment of the Sylhet Light Infantry, under their Commanding Officer, the Hon'ble Major Byng, started to Pratapgarh to intercept them, but on arriving there learnt that they had changed the direction of their march, and were then in the neighbourhood of Latu. The troops immediately started for that place, and on reaching it had barely time to form, when the mutineers came into sight, advancing in good order. A smart action took place, and the enemy, though undoubtedly superior in numbers, broke and fled, leaving 26 dead upon the field. Our own loss was small, and consisted of five dead and one severely wounded, but Major Byng was unfortunately amongst the killed. was impossible to follow up the mutineers with any hope of success through the jungle covered hills into which they had fled. Detachments of men were, however, posted so as to intercept their march towards Manipur, and a native officer, who had been sent with sixteen men to attack ten of the enemy who were lurking in the jungle near Latu. succeeded in killing eight of them. On the 23rd of December the mutineers entered Cachar; but the pursuit was still maintained, and they were engaged and defeated on December 23rd, January 12th, January 22nd and January 26th. They were now completely disorganized and dispirited. They were destitute of all supplies, and some were found lying in the jungle, having died of actual starvation, while others were despatched by Kuki scouts, who had been offered a reward for every sepoy killed. It is believed that out of the three companies which left Chittagong not three or four men escaped death or capture.

The district is not rich in archæological remains of Archmological reinterest. Mosques are numerous, especially in North Sylhet, but most of them are still used as places of worship, and are described in the following chapter. Two miles north-east of the Patharkandi police station there are the remains of the Fort of Raja Pratap Sing, a petty local notable who has given his name to the Pratapgarh pargana. Reference has been already made to the ruins in South Sylhet associated with the names of Subid Narayan and Khowai Osman, and in pargana Bhanugach in the same locality there is a fort attributed to Chandra Singh. belonged to the family of the Tippera Rajas and is said to have moved from the hills into the Sylhet plains about the seventh century, A. D.

सन्यमेव जयते

## CHAPTER III.

## THE PROPLE.

Density—Towns and villages—Growth of population—Migration—Sex and marriage—Infirmities—Language—Caste—Brahmans—Sudras—Caste distribution—Muhammadanism—Mosques and tombs—Hinduism—The Shahaj Bhajan—Sacred places—Akhras—Christianity—Occupations—Leading funilies—Marriage customs—Hindu festivals—Amusements.

Sylhet covers an area of 5,435 square miles, and,

though there are parts of it which
would not generally be considered
desirable places of habitation, it supports a much
larger population than any other district in Assam. In 1901, the density was 412 to the square mile.
This was greatly in excess of the figure for the Province
as a whole (109), though considerably below that of
the two Bengal districts which adjoin Sylhet on the west:
Mymensingh, where there was a density of 618 persons

to the square mile, and Tippera, where the density was as high as 848. The statement in the margin shows the Maringani Sipper south Sylhet Habigani Sipper south Sylhet Siber Sipper south Sipper south Sylhet Sipper south Sipper

rain that are precipitated on the southern face of the Assam range, and the heavy local fall convert the plain into a swamp at certain seasons of the year. In the centre of the great depressions, or basins, with which

this locality abounds, the cultivation of hot weather crops is quite impossible, and there is no high land available for village sites. The Dharmapasha thana has a density of only 246, over a total area of 321 square miles, while in the Sunamganj thana, which adjoins it on the east, there are only 262 persons to the square mile. In the Jaintia Parganas which, roughly speaking, are enclosed within the Surma river, the Piyaingong, and the Jaintia Hills, the density (250) is slightly less. Towards the centre of the district population increases, and in the Balagani thana, over a total area of 222 square miles, there is an average density of 640 people to the square mile. The whole of the Habiganj subdivision is very fully peopled, the density ranging from 493 in the Baniyachung thana to 651 in the Madhabpur thana in the south-west corner of the district. Population is also fairly dense in South Sylhet, as the low ranges of hills, which are unfit for the growth of ordinary crops, have been to a great extent cleared and planted out with tea. In Karimgani population begins to fall off, as a large proportion of the surface is covered with the Chhatachura, Pratapgarh. and Pathariya hills; and the upper valleys of the Langai and Singla have not yet been opened out for cultivation. Taking the thana as a unit, it cannot be said that any portion of the district is sparsely peopled, as nowhere is the density less than 246 to the square mile. tion is, however, comparatively sparse in the belt of land lying at the foot of the hills along the northern frontier, is somewhat denser on the eastern frontier. and is positively congested in the central and southwestern portions of the district. The density in each thana in 1901 will be found in Table II.

Sylhet contains five small towns and 8,330 villages.

## Towns and villages. Population 1901. Rythen 1992

Town. 1901.

Sylbes . 18,893

Karimganj . 5,886

Sunamganj . 3,580

Maulavi Bazar . 2,481

The population of these towns at the census of 1901 is shewn in the statement in the margin. Seven-eighths of the villages are reported to be small hamlets with less than 500

inhabitants, and there were only 54 with a population ranging from two to five thousand souls. reliance can, however, be placed upon these figures. villages are not, as in some Provinces of India, clusters of huts which stand out clearly in the centre of the fields tilled by their inhabitants. Rice, the staple crop, is grown in wide plains, dotted over with clumps of bamboos and fruit trees, in which are buried the houses of the cultivators. Except in the flooded tracts, it is groves and not villages that the traveller sees when riding through the more densely populated portions of the district, and not a house can usually be discerned till he has penetrated this jungle of plantains, betelnut trees, and bamboos. It is thus difficult to tell where one village ends and another begins, or to which of the larger clumps of trees should be assigned the smaller clumps which are freely dotted about amongst the rice fields, and the village as a statistical unit is of little value.

The earliest estimate of the population is one made by Mr. John Willes in 1789. He reported that there were altogether 492,945 people in the district; but his figures were evidently very much below the mark, and in 1813 the Collector made a much more reasonable estimate of 1,500,000 persons. In 1853, Mr. Mills calculated that the

population was about 1,393,500, this figure being apparently obtained by multiplying by five the number of houses reported by the police. This estimate was much more plausible than one framed by the Survey Department in 1860, which only amounted to 795,272 souls. In 1866, the Collector stated that, including the Jaintia Parganas, the whole population of the district might be fairly estimated at 1,000,000, or half a million less than the guess made by his predecessor 50 years before. The census taken a few years later in 1872 showed that his estimate was ridiculously low.

The statement in the margin shows the population recorded at each of the four last Percent-Population. age variation. enumerations, with the percentage of + 14·5 + 9·4 + 4·0 increase occurring in each decade. Part of the increase disclosed in 1881 was, no doubt, due to the inaccuracy of the enumeration of 1872. In the next decade there was a fair expansion of the population, but much of this was due to immigration; and the natural growth, i.e., the increase in the number of persons born and censused in the district, only amounted to 5.8 per cent, in the ten years. In South Sylhet, where there was a great development of the tea industry. the gross increase amounted to as much as 16 per cent.. and in Karimganj, where similar causes were in operation. there was an increase of 12 per cent. In Habiganj, on the other hand, the increase was less than 6 per cent. During the next decennial period the gross increase amounted to 4 per cent. This in itself is small enough, but more than half of this was due to immigration, and the number of persons born and censused in the district

only increased by 1.9 per cent. The local variation in the

Distribution of population by Subdivisions.

SUBDIVISION.	Popula- tion 1901.	PERCENTAGE VARIATION.	
oc Boly Island		1891— 1901.	1881- 1891.
Sunamganj North Sylhet Karimganj South Sylhet Habiganj	438,752 463,477 410,460 879,158 555,001	+4.9 -3.9 +6.7 +2.5 +9.9	+ 8.0 + 7.9 +12.0 +16.2 + 5.6

population is thus described in the Report on the census of Assam in 1901.\* "From the statement in the margin it appears that, while in one subdivision there has been an increase of nearly 10 per cent., in another there has been a decrease of nearly 4.

Habiganj has increased by 9.9 per cent., and, though there has been a substantial increase in the number of persons censused on tea gardens, the general population has increased by 7.3 per cent. In Sunamganj also there has been a very fair natural growth of the population, the increase amounting to nearly 5 per cent.; and as this cannot be considered a particularly healthy portion of the district, lying, as it does, at the foot of the Khasi Hills, there is no need to be dissatisfied with the progress made during the decade. The same cannot, however, be said of Karimganj, for, though the increase in the total population amounts to 6.7 per cent., the greater part of this is due to the tea industry, persons censused outside tea gardens having only increased by 2.5 per cent. South Sylhet, the state of affairs is still more unsatisfactory, as the population outside tea gardens has actually decreased by 3.9 per cent. during the last ten years, owing to the ravages of malerial fever; while in North Sylhet the total population is less by 3.9 per cent. than it was ten years ago." The decrease in the sadr subdivision was ascribed to a wave of malarial fever, which

<sup>•</sup> Page 15. ..

was unusually virulent in 1897 and 1898, and there can be little doubt that, in the middle of the nineties, Sylhet, like most of the other districts in Assam, was suffering from abnormally unfavourable conditions.

Sylhet is one of the most important tea districts in the Province, and during the ten years Migration. ending with 1900 over 141,000 coolies were imported to its gardens. But the indigenous population is so large that, at the last census, foreigners, i.e., persons born outside the Province, formed only a little more than 7 per cent. of the total population. proportion is unusually low for Assam. In the Province as a whole, foreigners formed nearly 13 per cent. of the persons censused there in 1901; and in the four other districts in which the tea industry is of considerable importance, i.e., Cachar, Darrang, Sibsagar and Lakhimpur, the rates varied from 24 to 41 per cent, The distribution varies considerably by subdivisions. South Sylhet foreigners formed 16 per cent., and in Karimganj 10 per cent, of the total population; whereas in Sunamganj they were only 4 and in North Sylhet 3 per cent. of the persons censused within the subdivisional boundaries.

The total number of foreign immigrants was 164,895, but a considerable proportion of these persons were not

Immigrants from Mymensingh			15,289	members of the cooly castes.
Hill Tippera district	and Tip	pera	11,690	The statement in the margin
Dacca	 Total		32,407	shows that over 32,000 per-
•				sons had entered Sylhet from

Hill Tippera and the three neighbouring districts of Bengal. No less than 30,000 of these people were

found in the frontier subdivisions of Sunamganj and Habiganj, so that it is not unreasonable to suppose that most of them had only moved across the border—a few miles from their former homes, and thus belonged to a quite different category from that in which the garden cooly must be placed. Sylhet, however, gains nothing by this movement of the population, as the number of persons who were born in Assam, in this case practically Sylhet, and were censused in the four adjoining districts

of Bengal, was over 36,000. Nearly half of these people were found in the neighbouring state of Hill Tippera.

There is plenty of waste land still available here, which the authorities are willing to lease out on easy terms, and which forms a great attraction to the inhabitants of the densely populated subdivision of Habiganj. There is a good deal of inter-marriage between Sylhet and Tippera and Mymensingh, and, as there are no natural frontiers, it is only to be expected that there should be a certain amount of movement across the boundary of the Province. The majority of these people go to Bengal as servants, cooks, priests, and shopkeepers, as the pressure on the soil is as severe there as in their native district.

Turning to the Provinces and divisions from which the coolies come, it appears that the proportion of immigrants from Chota Nagpur (24,627) is comparatively low. This is due to the fact that natives of the United Provinces thrive better in the Surma Valley than in Assam Proper, and are employed by planters in place of the true jungly cooly who is difficult and expensive

to procure. Three-fourths of these Chota Nagpuris were found in the two subdivisions of South Sylhet and Habiganj. 51,068 natives of the United Provinces were censused in the district, most of whom come from Ghazipur and Azamgarh. Nearly one half of these coolies were living in the Karimganj subdivision, and most of the remainder in South Sylhet. 13,144 persons came from the Central Provinces, chiefly from the districts of Bilaspur and Jabalpur; and over 10,000 from Madras. Unlike the Assam Valley, the number of settlers from Nepal is very small.

Sylhet, as is only natural, loses largely by interdistrict migration. Most of this takes place with the neighbouring district of the Cachar Plains, to which Sylhet sent 25,971 persons in 1901, though it received only 4,111 in return. This does not, of course, represent the loss to Sylhet in the single decade 1891-1901. Cachar itself is now fairly densely peopled, and most of these Sylhettis moved into it some years ago. The actual increase at the last census over the figures for 1891 was only 2,259; but, to provide for this increase, and to make good deficiencies caused by death, must have required the emigration of about 8,500 persons from Sylhet to Cachar between 1891 and 1901. It need hardly be said that the district can easily afford to spare these men. In places there is considerable pressure on the soil, and it is hoped that now that the railway has been completed through the North Cachar Hills, some of its teeming thousands may pass across into the fertile plains of the Assam Valley. Details with regard to the proportion of immigrants in each subdivision will be found in Table IV.

The proportion of women in 1901 was fairly high, (964 to 1,000 men) and considerably Sex and marriage. exceeded the proportion for the Pro-This was, however, largely due to the vince as a whole. emigration of men in considerable numbers to Cachar, and to the fact that the proportion of the sexes was not, as in the other tea districts, seriously affected by immigration. If these two factors are eliminated, and the proportion calculated on the natural population, i.e., those born in the district and censused in the Province, it will be found that there were, in 1901, only 958 women to every thousand men, a figure which was 4 below the average for the plains districts as a whole. The ratio between the sexes has shown little tendency to change, and, taking those born and censused in the district, the proportion of women was practically identical at the three last enumerations. things are more obscure than the causes which determine the proportion of the sexes, but one factor which is known to operate adversely on female life, i.e., infant marriage. is unfortunately in existence in Sylhet.

The statement in the margin shows the percentage

Percentage marr widowed amo girls aged	Percentage un- married amongst girls aged.	
0.10	10.15	18:20
Nowgong } 0.2	10.2	40.1
Eylhet Bindus } 8.4	67-7	5·9
Sylhet Muham- madans.	37.6	7-9

of Hindu girls under ten, and between ten and fifteen, who have performed the marriage ceremony; and the proportion of Hindu girls between fifteen and twenty who are still unwed. Similar figures are given for Muhammadans, and for the Hindus of Nowgong, who

are fortunately free from the ideas that in Bengal "have

succeeded, without a shadow of textual authority, in bringing about the monstrous abuse that the girls of the upper classes commence married life at the age of nine years, and become mothers at the very earliest time that it is possible for them to do so."\* The contrast between the figures is very striking. In an equal number of little Hindu girls under ten, there are 17 who have performed the marriage ceremony in Sylhet, for every one who has been hurried into matrimony in Nowgong, and the contrast at the next age period is almost equally pronounced. Over 15 the number of unmarried maidens in Sylhet is very small, and many of them, probably, suffer from some physical disqualification which seriously affects their chances in the marriage market. The effect of contact is also clearly shown. The Muhammadans have, to a great extent, adopted the fashions of their Hindu neighbours, in spite of the obvious disadvantages of union with a little girl, instead of with a full grown young woman; disadvantages which are not minimised in their case by any foolish dictates of tradition.

The future of the district can to some extent be judged by the proportion borne by the reproductive element, which in this case may be fairly taken as married women between the ages of 15 and 40, to the total population. Out of every thousand persons censused in Sylhet in 1901, 161 were potential mothers, a proportion which was slightly higher than that prevailing in the Province as a whole (157). As compared with the Central Provinces and Bengal the district is, however, handicapped in the race for population, as in the former

<sup>\*</sup> Report on the Census of India in 1901, p. 433.

Province there were 169, in the latter 165 potential mothers per mille in 1901.

The abstract in the margin shows, out of 10,000 males, the number afflicted Infirmities. with the four special in-Sylhet. Assam, India. firmities selected for record 10 at the census of 1901. figures for males only have been given, as concealment is more likely to occur in the case of women, and in their case the figures for leprosy seem undoubtedly to be in-The number of persons afflicted with this terricorrect. ble disease is unusually large, and an asylum has been opened at Sylhet for the reception of pauper lepers. The total number of males suffering from this disease in

1901 was 1,728. The number of leprous women was in all probability, not much smaller, though the number

actually returned was only 422.

blindness are also fairly prevalent.

Bengali is the ordinary language of the district and was returned by 92 per cent. of the inhabitants, Hindi by nearly 5 per cent., and Manipuri by 1½ per cent. Tipura is spoken on the southern frontier, and the various cooly languages have their own adherents. In Table III details are given for the principal languages by subdivisions. According to Dr. Grierson, the language spoken by the inhabitants of Eastern Sylhet is not intelligible to the natives of Central or Northern Bengal.\* There are

several peculiarities of pronunciation. K has a guttural

Deaf-mutism

<sup>\*</sup> Linguistic Survey of India, Vol. V., Pt. I, p. 224.

sound like the German ch., ch. is pronounced like s, and there is no difference between ch. and chh. sibilant, as in the case of Assamese, is often replaced by h, and the Sylhetti speaks of haph when referring to a snake, and talks of hakal instead of sakal. But, like a veritable cockney, he is not content with inserting h's where they are not wanted, but frequently omits them when they are. The elephant masquerades as ati, and hatgao, which really should be satgao, is loosely spoken of as atgao. The h is also reduced almost to the vanishing point in ghar, bhari, or in verbs like kahilam. Devanagari character is used amongst low caste Muhammadans, especially in the east of the district. They find it easier to master than Bengali, and Bengali books are printed in this character for their benefit,

The caste system of Sylhet is based on the principles in force in Eastern Bengal, a tract Caste. of country of which it really forms a part; but as is only natural in a frontier district, social restrictions are to some extent relaxed. Baidyas and Kayasthas intermarry, and Kayastha girls are not unfrequently given to men of lower rank. In these cases. the bride, of course, sinks to the status of her husband, but her parents do not lose their caste on account of the misalliance. The Shahas, who are the great trading caste of Sylhet, and have amassed considerable wealth, occupy a good position in society, though Brahmans will not actually take water from their hands; but even this privilege is accorded to the Das who are the great cultivating caste of the district. This concession is not extended to the Das's priest; and though a Kayastha or Baidya will take water brought him by a Das, and a high caste Brahman will allow him to enter his cook house, the Das's priest could not offer a cup of water even to a member of the Nabasakh without receiving a severe re-Sylhet and Cachar are, by the way, the only districts in Assam in which the Nabasakh are found, i.e., the functional castes, by tradition nine in number, from whose hands a Brahman can take water. In Sylhet they include the Baniya, Barui, Gandhabanik, Goala, Kamar, Kumhar, Mayara, Napit, Tanti, and Teli. The typical castes of the district hardly call for special mention. They do not differ from those of Eastern Bengal, and are described at length in Mr. Risley's work on the Tribes and Castes of Bengal. Brief notes on all the castes censused in Assam will also be found in the Report on the census of that Province in 1901.

Some reference should, however, be made to the Brahmans on account of their high Brahmans. rank, and to the Sudras who occupy a somewhat peculiar position in Sylhet. The five Brahmans who were imported by the Raja of Tippera in 642 A. D. are said to have been the first members of that caste who settled in the district. The original immigrants were Vaidiks, but representatives of the Rarhi and Barendra septs are also found. They have, however, been so thoroughly fused by intermarriage, that, in practice, there is hardly any difference between these three divisions. Two valid distinctions exist between the Sampradayiks and the non-Sampradayiks, and between the Gaur Gobindi and other Brahmans. The origin of these Gaur Gobindi Brahmans is obscure, and they

endeavour to merge their identity in that of the whole Brahman caste. Gaur Gobind, the last Hindu king of Sylhet, is said to have raised the position of the Maharas and Dases, and general opinion would suggest that the Brahmans who bear his name are indebted to his kind offices for their high position. The most respectable classes of Brahmans are known as Sampradayiks, and do not often marry outside their own community. They are again sub-divided into four local sections: the eastern, who are the most honourable of all and live in the east of the South Sylhet subdivision, the central, southern. and northern. The customs of the Sylhetti Brahmans do not materially differ from those followed in Bengal, which are described at length in Mr. Risley's Tribes and Castes of Bengal. They observe the rules of the gotra, \* and the usual restrictions which encompass a member of the priestly caste from the day of his birth to the day when he is laid upon the funeral pyre. Brahmans are distributed fairly evenly all over the district but are not very numerous in Sunamganj.

The term Sudra is usually applied to the lowest of the four great divisions of Manu, of which the other three are the Brahmans, Kshattriyas, and Vaisyas, but in Sylhet it has acquired a special meaning. Here it is used of the "Deba Das," the low caste people who are knows as "inghas" and "Bhandaris," and act as servants to Brahmans, Kayasthas, and Baidyas. They

The following are the principal gotras in Sylhet: Sandilya, Eharadhwaja, Kasyapa, Savarna, Ghritakausika, Moudgalya, Parasara, Batsya, Basistha, Jamadaguya, Gautama, Agnibeshma, Krishnatreya, Kusika, Kousika, Katyayana, Saktri, Gargya, Atreya, Gargya Maharshi, Swarna-kousika, Jatukarna and Batsa.

are often allowed to occupy their land rent free, and in return for this are bound to render their masters any assistance that may be necessary. Separate figures have not been given for the Sudras in Table IV. as the Halwa Das dislike the prefix Halwa, and, in 1901, many of them described themselves as Sudra Das or even Sudra. Another curious caste are the Rarh or Kusiari. Their second name is said to be derived either from the Kusiyara river, or from the sugarcane kushiyar which they grow. But neither of these derivations seem appropriate, as they would apply with equal force to thousands of other people. Another tradition says that they are of Tippera or Bodo descent. Kusiaris are cultivators by profession, they are looked down on by the Halwa Das, and numerically they are unimportant. The Haijongs, who are found in the Sunamganj subdivision, seem to have originally come from the Garo Hills. They speak a peculiar dialect of their own, and are, apparently, the result of a union between Garos and low caste people of the plains.

The number of persons returned under each of the main castes in 1901 will be found in Table IV, and it only remains to touch briefly on their local distribution. Kayasthas are specially numerous in Habiganj and North Sylhet, and are comparatively scarce in Karimganj. The Das are found in strong force all over the district, but are particularly numerous in Sunamganj, where they form nearly one-third of the total Hindu population; a proportion about twice as large as that existing in any other subdivision. The Baruis are specially numerous in South Sylhet, where their

pan gardens are to be seen on the banks of the rivers. Habiganj and Sunamganj are the strongholds of the Shahas and Kaibarttas. The latter are hardly found in the three remaining subdivisions, their place being taken by Dom Patnis who are especially numerous in Karimganj. Most of tht Manipuris are settled in Karimganj and South Sylher, though in the latter subdivision they masquerade under the name of Khatris or Kshattriyas. The language test is, under these circumstances, the most reliable, and this shows that in 1901, nearly 29,000 persons were speakers of Manipuri. It is, however, a mistake to suppose that at the present day there is any appreciable immigration from Manipur. This movement westward took place some years ago. Each succeeding census shows a large decrease in the number of persons born in Manipur and censused in Sylhet, and in 1901 there were only 89.\* These Manipuris are a factor with whom the district officer has to reckon. The history of their own State is one of perpetual conflict; wars and rumours of wars. risings and rebellions, usurpers seizing the throne and being in their turns assailed by other usurpers. Manipuris are by nature a turbulent and unruly little respect for the majesty of people, and have the law. In 1857, it was thought that possibly they might give trouble, and recently at Bhanubil they have evinced a tendency to defy not only their own landlord but the representatives of Government itself. They are also suspected of having an inclination for dacoity and other violent forms of crime.

<sup>•</sup> The corresponding figures for 1881 were 3,253 and for 1891, 336.

Ethnical composi-tion of the peoples.

Percentage on total population.

Muhammadans Higher Hindu Castes (Brahmans, Bhats, Baidyas and Knyasthas) The Nabasakh The Nabasakh Respectable Quitivning Coates (Sudra Das, Halwa Das, Das)
Lower functional Castes (Shaha, Snuri, Jugi, Dholis, Sutradhar) ...
Fishing Castes (Kaibartta, Dom Patni, Namasudra, Shuiumalis, Maii) 7 6 13 Naniparis Animistic Tribes (Tipperss Garos, Khasis, Haijongs) .. Other Persons Total .. 100

The abstract in the margin gives some idea of the composition of the ethnical the people. The Muhammadans describe themselves as Sheikhs, but the great majority are no doubt descended from the aboriginal inhabitants of the Surma Valley, and must have been largely recruited from humble Hindu castes, who themselves were very probably of Bodo origin. Both the Naba-

sakh and the lower functional castes have to a great extent abandoned their traditional occupations for agriculture. The fishing castes are very strongly represented, but this is only natural in so watery a district. The bulk of the undistributed nine per cent. are foreigners of various humble castes employed on tea gardens.

Religion Muham-madanism.

Percentage of Mubam-Diadana to total popu-

North Sylliet 67 **55** Bunamusuj Habiganj Karimganj South Sylhet

Classified by religion, the population of Sylhet in 1901 was distributed in the following proportions: Muhammadans 52.7 per cent., Hindus 46.8 per cent., Animists The abstract in the mar-0.5 per cent. gin shows the percentage of the population in each subdivision who profess the faith of Islam. As is only natural,

numerous in North Sylhet, Muhammadans are most the first portion of the district Was possession, and on the western adjoins Bengal. South Sylhet and Karimganj came less under the influence of the Moslem faith, and for many years were probably dominated to some extent by the Hindu Kingdom of Tippera.

During the last decade the increase amongst the Muhammadans amounted to 5 per cent, though the natural growth of the population was less than 2 per cent. is the more remarkable in that nowhere are the Muhammadans more numerous than in North Sylhet, a subdivision in which the last census disclosed a serious decrease in the population. Four Musalman gentlemen, who were consulted by the Deputy Commissioner, were all of opinion that conversion had very little to do with the growth of the Muhammadan population. There is no organised propaganda of the faith, and the few converts made are said to be Hindus of low caste, who have been detected in intrigues with Muhammadans of the opposite The higher rate of increase amongst the Musalascribed to superior fecundity, which mans is said to be due to greater physical vigour and a more nourishing dietary, to the absence of restrictions on widow remarriage, to a less marked disparity between the ages of husband and wife, and, to some extent, to the greater prevalence of polygamy. The absence of restrictions on widow remarriage is probably the most important factor. In 1901, there were only 31,000 Muhammadan widows between 15 and 40, as compared with 60,000 Hindu widows of this age, and the Musalmans had about 30,000 more potential mothers, i. e., married women between 15 and 40, than the followers of the rival religion. A difference such as this is bound produce a sensible effect on the growth of population.

The town of Sylhet is full of memorials of its Muhammadan conquerors. On every Mosques and tombs. side are to be seen mosques, the majority of which are still in excellent repair, and are attended by a concourse of devout worshippers. But, even more numerous than the mosques, are the large brick tombs of the Muhammadan saints, each with a little masonry receptacle for a native lamp, or else with a bamboo lamp post of the most modern pattern, standing at These tombs are to be seen in every quarter of the town. There is hardly a road which has not one or more along it, hardly a hill which has not the bones of saints upon its summit. The religious centre of Sylhet is the shrine of the famous Shah Jalal. situated about a mile north of the cutcherry, some three or four hundred yards west of the road that leads to Companyganj. At the point where the main and branch roads meet are the masonry walls of an old mosque, begun some two and a half centuries ago, but still unfinished. The builder was dilatory, the work was not completed within the stated time, and, as a punishment for his neglect, the Nawab of that day had him summarily put to death. The building is now almost completely hidden by the trees that have succeeded in effecting a lodgment in its walls, but, though the roof was never finished, the massive outer walls suffered little or no damage in the great earthquake of 1897.

Shah Jalal's mosque, which was built in 1531 A. D., is approached through a gateway of solid masonry, much of which was shaken down in 1897, and now lies in huge blocks in picturesque confusion on the ground. On the

left hand side as you enter is a tank with a ruined mosque in front. On the right is an open shed, in which food is cooked for the worshippers on holy days, one huge cauldron alone containing as much as six and a half hundredweight of rice. The building is approached by a flight of steps which terminates in a broad platform. In front is a central hall through which the worshipper passes to the actual tomb. Here there is a small place of prayer, which, together with the gateway, is said to have been erected by Mr. John Willes, one of the earliest of the Collectors of Sylhet. South of the central hall is the mosque in which prayers are usually held, while at the back is a deep well full of fish who come when called to be fed. A grant of Rs. 93 per mensem, which was sanctioned by the Nawabs for the maintenance of this institution, has been confirmed by the British Government. famous mosque is situated near the south-west corner of the Jail compound, and was founded by Shah Abu Turab in 1698 A.D.

Masonry mosques are common even in the villages of North Sylhet, but, where the villagers cannot afford this luxury, service is often held in a small thatched hut. Near the Shahji Bazar railway station, in the south-west corner of the district, is the darga of Shah Fateh Ghazi, one of the companions of Shah Jalal. This darga is maintained from the rents received from a village which was granted to it by the Mughal Government, and has since been exempted from payment of land revenue, and a mela has for many years been held in the vicinity about the middle of January. In this same thana of Madhabpur there are the dargas of other famous Muhammadan saints,

i.e., of Shah Ahmed Ghazi at Fathepur, of Shah Ghyas Saheb at Charabhanga in pargana Ghyasnagar, of Shah Aulia in pargana Kasimnagar, of Shah Ali and Shah near Kasimpur, and of the Panch Pirs Alabakshpur. In Dhargam pargana, in Jaintia, there is the tomb of a great fakir called Patashah, at which offerings are made by those who are anxious to be cured of some disease or to be blessed with children. In the Pratapgarh pargana, to the south of Karimgani, there are several mukams which are said to have been founded by one of the Badshas of Delhi, who turned fakir and settled in that lonely spot. Timber traders, whether Muhammadan or Hindu, still worship at these places, and it is said that tigers in former days used to visit these shrines on Thursday nights, and eat any food left for them, without molesting the persons stopping in the mukam. Thursdays are still observed as holy days by the lumber men in these hills, and timber is neither felled nor dragged on that day of the week. Nearly all the Muhammadans of Sylhet are Sunnis, but there is one important family, that of Moulavi Ali Amjad Khan, which professes the Shiah creed.

Hinduism is divided into three main sects, Saktism,

Sivaitism, and Vaishnavism. At the census of 1901 nearly 30 per cent. of the Hindus returned themselves as Saktists, 5½ per cent. as worshippers of Siva, 53½ per cent. as Vaishnavites, and 11 per cent. failed to specify the particular form of that religion to which they owed allegiance. Saktists worship the reproductive powers of nature as manifested in the female, and Sivaites the male emblem of fertility. The

latter adore Siva, the former his wife Sakti. The Vaishnavites represent a revolt against the haughty of the Brahmens and the degrading pretensions rites of the Tantric worship. Little attention is paid to caste restrictions, the use of animal food and wine is deprecated, and the slaughter of animals in sacrifice forbidden. Krishna the particular is manifestation of the deity selected for special reverence, and sankirtan, or music and songs, is declared to be the most suitable form of worship. The family home of Chaitanya, the great Vaishnavite reformer, who was born in 1484 A.D., was situated at Dhakadakshin, about ten miles south-east of Sylhet town, and most of his followers regard him as the latest incarnation of Vishnu.

A somewhat curious sect is that which is known as the Shahaj or Kishori Bhojan. The Shahal Bholau. was founded by one Kalachand Vidyalanker of the Bikrampur pargana in Dacca, and salvation is said to be obtained by imitating the amorous actions of Krishna at Brindaban. Each devotee has one or more female associates with whom, according to most accounts, he indulges, or endeavours to indulge, in very curious practices. The members of this sect are said to assemble secretly at night and to worship the mistress of their priest, who is supposed to represent Radha, the wife of Krishna. Food is offered to her, and, after she has taken a little, the prasada, or leavings, are distributed amongst the congregation. Songs are sung, ganja is consumed, and a good deal of sexual intercourse is supposed to take place. The female worshippers are

generally young widows, and most of the members of this sect are persons of low caste.

few masonry temples in Sylhet, and religious buildings usually take the Sacred places in Sylhet, form of akhras for the Vaishnavites, and Kali or Durga baris for the worshippers of Sakti. akhra is a religious institution inhabited An Vaishnavite devotees, who are supported by the contributions of their immediate disciples or of devout Hindus in general. There is little of dignity either in the demeanour of the inmates or in the appearance of the buildings in which they dwell. In many of these institutions there are women as well as men, and it would hardly be too much to say that under the specious cloak of religion a large proportion of the devotees live a life of sloth and sensual indulgence. The akhras of Sylhet and Bithangal are described below, but these are two of the finest specimens of their kind, and the ordinary akhra is a place of much less interest and importance. In the Kali or Durga bari too, no less than in the akhra, Hinduism suffers, as it so often does, from the mean and unworthy form in which it is presented to the world. The emotions roused by a contemplation of the image of the goddess are hardly those of reverence or awe, and the building in which it is housed is generally a sorry shanty whose roof of hideous corrugated iron is supported on wooden posts. The unprejudiced observer in Sylhet can hardly fail to be impressed by the extraordinary difference between the outward manifestations of the Muhammadan and Hindu faith. In the one case there is simplicity, severity, cleanliness, and dignity. In the

other there is only too often nothing but grotesqueness, meanness, and squalor, and it is difficult to realize that its adherents include the most advanced and intelligent sections of the population.

The places which are most sacred in Saktist eyes are Phaljor in pargana Bhaurbhag in Saktist Fiths. Jaintia, where there is a stone pillar which is said to be Sati's left leg, and Jainpur, about a mile and half south of Sylhet town, where her neck is said to have fallen when her body was dismembered by Vishnu. The latter pith, as the places consecrated by the fragments of Sati's severed body are called, has only recently been rediscovered. Sati's neck is represented by a piece of flat rock, similar to that found on most of the tilas round Sylhet. Her bhairabi, or guardian left to protect her by Siva, takes the usual form of a small upright pillar of rock shaped like a phallus. There is no temple over these remains, and hardly anything to distinguish them from many similar pieces of stone found in the neighbourhood of Sylhet town. At Barakia and at Chandipur, a village near Dwara Bazar in the Chhatak thana, there are shrines of Chandi, another incarnation of Sakti, which are visited by pilgrims on the Ram Navami day.

The following places are considered by the Sivaites to be particularly sacred: (1) Nirmai in the South Sylhet subdivision, where there is an image of Siva, before which people sometimes shave their hair in the hope of being delivered from disease. (2) Siddheswar's temple

at Badarpur, a few yards beyond the boundary of the district. (3) Rupnath in the Jaintia Hills about a mile and a half beyond the district boundary, and (4) Sarbananda about a mile and a half south of Sylhet town. The last two places are said to be the bhairabis of the neighbouring piths. Fairs are held at each of these shrines on the occasion of the Sivaratri festival. Large lingams, or stone pillars intended to represent the phallus, are situated three miles south of Jaintiapur; at Hatakeswar on the left bank of the Surma in the Karimganj subdivision where it is said to have been worshipped by Gaur Gobind, the last Raja of Sylhet; and at Tungeswar in the Habiganj subdivision.

The places which are held by the Vaishnavites in most respect are the temple of Chaitanya Valshnavite akhras. at Dhakadakshin or Thakurbari, and the temple at Supatala in Panchakhanda. At the latter place there is a stone image of Vishnu, which has a considerable local reputation. There is another image of Vishnu in the Jagannathpur village, in the south-east corner of the Sunamganj subdivision. It is said to have been made by Viswakarma, the god of artificers himself, in the time of the Mughal Emperor Shah Jahan, and on this account is visited by pilgrims from every part of the district. At Bithangal near the Mymensingh boundary there is an akhra under the management of the Jaganmohani sect. At one time there was neither idol nor tulsi plant at this akhra, and cowdung was not-used for cleansing purposes. Strong objection was, however, taken at Brindaban to this disregard of what the ordinary Hindu holds sacred, and a more orthodox ritual is now observed. Ram Krishna, the founder of this place, is held in the greatest veneration, and offerings are made at his shrine by men who desire offspring or the increase of their herds. This section of the Vaishnavites at one time tried to worship an abstract god without shape or form, but this proved to be beyond the spiritual capacities of their disciples, and they sing the praises of Hari, Krishna, Rama and even Chaitanya. Bithangal has completely eclipsed the akhra at Masulia near Habiganj, which contains the tomb of Jaganmohan, the founder of the sect. It is the wealthiest and most prosperous akhra in Sylhet, and is said to receive as much Rs. 40,000 per annum in the form of offerings from its disciples. The buildings are of considerable size, and are of masonry, and several of the rooms are paved with marble.

Other famous akhras are situated at Jugaltila in Sylhet, where the mahunta is invariably a Brahman; at Panisail in the Indeswar pargana in South Sylhet; and at Nayagaon in Sunamganj. The last named akhra has recently been started in honour of Adwaita, one Chaitanya's followers, who is said to have been an incarnation of Siva. The akhra of Jugaltila is said to have been founded some 200 years ago by one Jugal Kiscre mahunta, who is supposed to have been an incarnation of the deity. It is endowed with landed property which brings in from one thousand to fifteen hundred rupees a year, and has some seven or eight hundred disciples, each of whom contributes on the average about As. 12 per mensem towards its mainten-It is situated on a low hill, approached by a flight of masonry steps, and the idol is placed in an open shed

consisting of a corrugated iron roof supported on wooden posts. There are quarters for some thirty resident disciples, but all of the buildings are mean and squalid, and the place is in no way comparable with the more important sattras in Assam.

There are other places revered by all Hindus alike, irrespective of their sect. A certain Other sacred places. portion of the Panatirtha river, near the village Ghagtia becomes as sacred as the Ganges on the occasion of the Baruni, and pilgrims flock in numbers to bathe in the holy waters. In the south-west corner of the Habiganj subdivision, there is a temple at Krishnapur, at which pilgrims worship after they have bathed in the sacred pool of Brahmakunda. which is situated just across the boundary of Hill Tippera. Another sacred pool is known as Tamptakunda and is situated in pargana Panchbhag in Jaintia. pool is said to become quite warm on the occasion of the Baruni, and it is possible that the water has in reality some mineral properties. Special sanctity is also said to attach to the place where the Manu and the Kusiyara meet. The absence of any Hindu temples of importance is quite intelligible. Sylhet came under the influence of the Muhammadans at an early date, and, prior to its conquest, there were no local notables of sufficient wealth and power, to erect masonry buildings of any size or permanence. The country seems to have been split up into a number of petty principalities, and these small lordlings of a jungly frontier tract had not the means, even if they had the inclination, of raising temples to the glorification of god's name and the commemoration of their own. The statement appended to this chapter shows in a consolidated form the various sacred places in the district. Some of these shrines are surmounted by a brick built temple, but in many cases the deity is hidden in a rough unhewn piece of stone, protected from the sun and rain by a miserable hut of bamboo and thatch.

The statement in the margin shows the number of persons returned under the different Minor Religions. 141 · religions which had a comparatively small number of adherents in the dis-The animistic tribes are found at the foot trict in 1901. of the hills along the northern and southern boundary, and are Khasis and Garos in the north, and Tipperas in the south. A considerable proportion of the followers of this religion were, however, jungly coolies, Oraons, Santals, and people of that class. The Jains are the Marwari merchants from Rajputana, and the Brahmos are recruited from the ranks of the more thoughtful and educated amongst the Hindus, and are not unnaturally found living in the towns.

The total number of Christians (744) is small, and the number of native Christians (394) smaller still. Sylhet is too civilized to allow of conversion proceeding rapidly, and in the twenty years ending with 1901 the number of native Christians only increased by 130. Members of the Welsh Mission are stationed at Sylhet, Maulavi Bazar, and Karimganj, but they have only met with a small measure of success, and in 1901 they had but 80 followers. This is

not due to any personal hostility towards the preachers of the gospel. A well-known missionary, the Reverend Mr. Pryse, was universally esteemed, and, on his death, the Hindus of the town defrayed the cost of the erection of his tombstone, and founded a library to commemorate his name. On social grounds there are, however, the strongest objections to a change of faith. The neophyte, whether he embraces Christianity or Muhammadanism, has to abjure too much, and there are at present no signs of any general movement towards the adoption of the western creed. The native Christians are distributed fairly impartially over most of the principal sects. In 1901, there were 52 Anglicans, 48 Baptists, 85 members of minor denominations, most of whom failed to specify their sect, and 126 Roman Catholics.

The bulk of the Roman Catholic community live at the village of Bandasil, on the left bank of the Barak, a mile below Badarpur. Their forefathers are said to have been settled there at the beginning of the 18th century by a Muhammadan Nawab, who came from Meerut with a party of Musalmans and Native Christians; the latter, according to the village traditions, being employed to serve his guns. Where the Nawab recruited these men history does not relate, but they are said to have built a fort in Bandasil and to have settled round it. After the Burmese war the Nawab was rewarded for his loyalty by a grant of land in Baniyachung, the proceeds of which enabled the Roman Catholics of Bandasil to live in idleness. Quarrels broke out in the small community, their land was gradually sold to the surrounding villagers, and most of the people now earn their living by domestic

service. Since 1891, there has been a resident Roman Catholic priest at Bandasil.

Sylhet like the rest of Assam is a rural area, but the percentage of the population supported Occupation. by agriculture (81.5), though high, is lower than in any other district in the plains except Kamrup. The explanation lies in the fact that occupation is somewhat more specialized than in Assam. functional castes exist, and to some extent follow their traditional occupations, and the spiritual needs of the people have ample provision made for them. statement in the Number of persons to each. Sylhet. Darrang. shows the number of persons 3,666 Washerman Priest 2,656 1,629 in the district for each person actually employed as a barber, washerman, or priest in Sylhet, and in Darrang which is a purely rural The number of priests is particularly large in Habiganj, and, with real discretion, they avoid the marshy country lying to the north of this subdivision. fishing industry is of considerable importance in the flooded tracts to the west, where a trade is carried on in cured as well as in dried fish. In North Sylhet the fishermen are not so numerous, and they are comparatively scarce in South Sylhet and Karimganj, where the level of the country rises, and the area of submerged land is not so large. The greater portion of Sylhet is permanently settled, but settlement was made direct with the actual cultivators, and the number of estates is unusually large. According to the census returns, which have, however, in a matter of this kind to be accepted with a certain degree of caution, nearly one-third of the

total agricultural population were cultivating their own land. In North Sylhet, the number of persons holding direct from Government was almost equal to the number of tenants, but the subdivision includes the Jaintia Parganas which are temporarily settled. In Karimganj also, the number of landholders is about two-thirds of that of the tenants, but in the three remaining subdivisions the tenants are in a very large majority. The only occupations in addition to those mentioned, which in 1901 supported more than one per cent. of the total population, were garden labour, general labour, and begging. Women do not, as a rule, work in the fields in Sylhet, and the proportion of actual workers is thus considerably lower than in Assam proper. In 1901, the workers only formed 38 per cent. of the whole, as compared with 67 per cent. in a district like Lakhimpur. Further details with regard to the occupations of the people will be found in Table IV.

The wealthiest family of Sylhet is that of Maulavi Ali Amjad Khan of Langla. The founder of the family was one Maulavi Muhammad Rabi, who was tutor to the sons of the Nawab of Murshidabad, and in 1735 A.D. received as a reward a large jaghir of land near his house at Langla. His son Maulavi Muhammad Ali Khan was appointed Kazi of Sylhet in 1773 A.D., and his estates were assessed to revenue in 1819 A.D. He was succeeded by his son Gous Ali Khan, who was accused of having supplied rations to the mutineers in 1857, but was acquitted of the charge, and was the grandfather of the present zamindar.

One of the most respected, though not one of the wealthiest families in Sylhet, are the The Mauzumdar Mauzumdars. The founder of the family was Surwar Khan, who, in 1464 A.D., reduced to order the revolting Zamindars of Ita and Pratapgarh. His son, Mir Khan, was appointed Kanungo of Sylhet, and this office remained in the family till it was finally abolished at the time of the permanent settlement. Several places in the district take their names from different members of this family. Thus Jahanpur is called after Jahan, son of Lodi Khan, who subdued Khoja Osman Khan, the zamindar of Bhanugach. Keshwar Khan, who held office in the time of Aurangzeb, dug a canal which is still called Keshwar Khal, and Mahtab Khan, his son, founded a bazar which bears his name. The present representative of the family, Khan Majid Bakht Bahadur, was for some time a Deputy Magistrate in Bengal and an Extra Assistant Commissioner in Assam. His father Saived Bakht resided for several years in Mecca, and was made a member of the Sherif's Council and decorated with the Star of the Meiidhi. he and his son, Hamid Bakht, were exempted from attendance in the civil courts, a privilege which is at the present moment (1904) accorded to only one individual in the Province, the gosain of the Dakhinpat. sattra in Sibsagar.

The Dastidars are said to be descended from the same stock as the Mauzumdars, though the latter family were converted to the faith of Islam in the 15th century, while the Dastidars have remained faithful to the Hinduism of their forefathers.

The founder of the family, Kabiballabh, was appointed Dastidar of Sylhet, and in that capacity had charge of the royal seal. Hare Krishna, who in 1722 was appointed Amil of Sylhet, is perhaps the best known member of the family, which at the present day has lost most of its former wealth.

The Dewan family was founded by a native of the Hooghli district, who settled in Sylhet The Dewan family. in the middle of the 16th century. One of his descendants, named Manik Chandra, was appointed Dewan, and his son, Murari Chand, was, in his time, one of the most conspicuous figures in the society The present head of the family, Raja of the district. Giris Chandra Roy, is the grandson of this gentleman, and has established a college in the town in honour of his memory. In 1898, the title of Raja was conferred upon him, but his estate has been considerably reduced by his numerous benevolences and generous and hospitable style of living. There is another Dewan family at Baniyachung descended from the Gobind Singh referred to in the second chapter (p. 25.)

The great bulk of the Hindus marry in the orthomarriage customs.

dox way, by what is known as the prajapatya form, which corresponds to the hompura of the Assam Valley. The ordinary marriage ceremony is much as follows, but the style in which it is carried out depends upon the resources of the contracting parties.

The first thing to be done after a match has been agreed upon is to fix the date for the ceremony. The bridegroom's representatives proceed to the house of the

bride with fish, sweetmeats, curds, and betelnuts, and, on their arrival, the Brahmans of the village are summoned and asked to select an auspicious day. The next stage is known as Panakhili, and consists of the offering of betelnuts and leaves, with two small pieces of gold and silver, to the family idol, or to the idol of a neighbour, if neither of the families possesses an idol of its own. Two nights before the wedding day the bridegroom and the bride are solemnly bathed, and on the following morning the general merry-making begins. A party of drummers is called in, who, with short intervals of rest, keep up their unmelodious music day and night; the children of the two families are decked out in their best; the bride and the groom are solemnly bathed; and friends and relatives assemble from all sides. At night a theatrical performance is given in the bridegroom's house, and a party is despatched to fetch the bride, for in the Surma Valley the actual ceremony generally takes place in the house of the groom. On this night, also, the contracting parties are once more solemnly bathed. the next morning a priest sprinkles water over them from a mango leaf, and places a daub of an oleaginous black ointment, called adibash, upon their foreheads. During the day the bridegroom, and some male relatives on behalf of the bride, offer oblations to the spirits of their ancestors, and a feast is given to the Brahmans and the assembled guests. In the evening, the contracting parties are again solemnly bathed and attired in their best clothes, and, pending the advent of the bride, who arrives in the middle of the night attended by most unmusical musicians, the groom is allowed to witness the theatrical performance that is going on.

When the time for the actual ceremony has come, he is anointed with sandalwood, a crown of pith and flowers is placed upon his head, and he is escorted to the front of the main house, where a maid or married woman presents him with a ring, a pair of cloths, and some curds. Both parties then enter a small enclosure in the courtyard which has been fenced in with split bamboos and plantain trees, the groom is seated on a stool, and the bride marches round him seven times, throwing flowers and red powder over him as she completes each circuit. The next stage is called sampradan, and is the really binding part of the ceremony, when the girl and her dowry are formally handed over to her husband. fire is then lighted, flowers, rice, and ghi are thrown upon it, and the priest utters the appropriate mantras. By this time the young pair are thoroughly worn out, and gladly avail themselves of the permission to seek what rest they can for the remainder of the night. On the following day they are again solemnly bathed, and are conducted round four bamboos in the courtyard. and a feast is given to the assembled guests. This ceremony is repeated on the fourth day, as on the intervening day the bride and groom are not allowed to see one another, and the marriage is then said to be complete.

Except among the higher ranks of Hindu society,

ti is the general practice in Sylhet for a man to purchase his wife. The usual price amongst the lower castes ranges from Rs. 40 to Rs. 50, though a girl can sometimes be obtained for a ten rupee note, a price which could not be thought excessive by even the poorest cultivator. Shahas, on

the other hand, when marrying into a good family, have been known to salve the conscience of the father by the gift of as much as fifty times that sum. That, after all, is not too much for a wealthy parvenu to pay for the privilege of being allowed to call a respectable Kayastha father-in-law. The other expenses incidental to a marriage are incurred on Brahmans, who expect their customary fee, on musicians, palki-bearers, and other hangers on, and on fireworks, clothes, presents, and quantities of food. On this an ordinary cultivator will expend some Rs. 30 or 40, but a rich man's wedding may cost anything up to Rs. 1,000. Widow re-marriage is regarded with growing disfavour, even amongst the lowest castes, with the natural result that there is an increasing difficulty in obtaining wives. Even if every Hindu woman were pressed into the service, some thousands of men would still remain unwed. Under these circumstances it seems a lamentable waste of good material to leave some 60,000 Hindu widows, none younger than fifteen and none as much as forty, to lead a depressing life of dreary solitude. In the Habiganj subdivision, the Bengal custom of paying for the bridegroom is gradually gaining ground amongst the upper classes, and the father of the girl is expected, not only to defray the expenses of the wedding, but to pay for the education of his son-in-law as well.

Amongst the Tipperas the familiar form of marriage by service is in vogue, and the man is expected to live some time in the house of his father-in-law and work for him in his *jhums*. The only trace of this custom amongst the Hindus of Sylhet, who differ in this particular from the Assamese, is to be found in the ghor jamai, who is permanently absorbed into the family of his father-in-law. The Manipuris, like the Assamese, sometimes evade the demands of a too avaricious parent by the simple process of carrying off the girl, who offers only a nominal resistance to her abduction. Having obtained possession of her person it is a comparatively easy matter to come to terms, and no social obloquy attaches to the young couple.

As far as the feasting and general merry-making is concerned the Muhammadan marriage does not differ materially from the Hindu, but it has, of course, no religious side. The essential parts are the formal assent to the contract given by the bridegroom and the bride, and the execution of the kabin.

The following are the principal festivals of the Hindus:—

A clay image of the Goddess of Learning is procured, offerings of flower, leaves, and eatables are made to it, and the worshippers abstain from book and pen. This puja is usually confined to the higher classes of society. The Suryapuja is held in the month of Magh (middle of January, to the middle of February) in honor of the Sun God. A plantain tree is set up in the courtyard and decorated with flowers, and offerings of leaves, eatables, and flowers are made, the women singing all the while in honor of the Sun God. In February or March comes the Sivarati, during which the worshippers fast during the day and sit up at night to worship Siva's lingum and eat bhang and ganja.

About a fortnight later there is the Doljatra. On this occasion the image of Vishnu is worshipped, anointed with red powder, and then swung to and fro, while the people pelt one another with red powder in memory of the amorous contests of Krishna with the milkmaids of Towards the end of March there is the Brindaban. Barunisnan, when ablutions are offered to the spirit of the departed ancestors, and the villagers feast on curds, parched grain, and molasses. The Rath Jatra takes place in June or July, when an image of Vishnu or Jagannath is dragged about on a car. On the last day of Sraban (middle of August) there is the Bishahari or Manasa puja in honour of the goddess of snakes. puja is very popular in Sylhet, and is observed by all Hindus, high and low, rich and poor alike. Flowers, leaves, and eatables are offered to a clay image of the goddess, and goats, ducks, and pigeons are sacrificed. few days later the Vaishnavite section of the community, and more specially the Vaishnavite ascetics, or Bairagis as they are called, celebrate the Jhulan festival. Images of Krishna and Radhika are worshipped and swung to and fro. There is much singing on this occasion at night. In the same month, or in the month following, there is the Janmastami in honour of the birth of Krishna. The main feature of this festival, which is observed by every devout Hindu, is abstinence from food and drink. In September or October there is the Durga puja which is a time for general merry-making. New clothes are given to the children, members of the family who are away return home, and there is general feasting and iollification.

The rich purchase clay images of Durga, Lakshmi, Saraswati, Kartik and Ganesh. Poorer people make their offerings to plantain trees or earthen jars filled with water. The puja lasts for four days. Goats are usually sacrificed on each of the first three days and on the third day those who can afford to do so kill a buffalo. On the last day the goddess is worshipped with flowers, leaves, and eatables and then thrown into water amidst singing and beating of cymbals.

Four days after the Durga puja comes the Lakshmi puja, and in the last quarter of the year there are the Kali, Kartik, Jagadhatri and Rash pujas. The last named festival is only observed by the Vaishnavites and is especially popular with the Manipuris.

A special form of religious ceremony is known as the noaka, or boat puja, and is performed by a wealthy man in satisfaction of a vow, who generally spends from Rs. 300 to Rs. 500 on the ceremony. A shed is built, at the end of which is a boat painted and gilt, from which rise, tier upon tier, the images of various gods, amongst whom Bishahari is generally the most prominent. For several days sacrifices are offered to the deities, and Brahmans, who are well paid and feasted for their services, offer up their prayers. At the end of this time the house and its contents are abandoned and allowed to fall to pieces. Every Hindu has a guru, or religious teacher, to whom he makes an annual offering varying from 2 annas to 5 rupees according to his means.

The Pous or Uttarayan Sankranti, held about the middle of January, has no religious associations and corre-

sponds to the Magh bihu of the Assam valley. The villagers light bonfires in the rice fields, at which they warm themselves after the morning bath, and devote the day to merry-making.

In the north and west of the district, where, in the rains, much of the country goes com-Amusements. pletely under water, boat races are a source of great amusement. The khel naos, as they are called, are long narrow canoes, with a peaked stern and prow, which are carved, and painted with the brightest colours. They often carry a crew of forty men, who sit in pairs and paddle with the utmost vigour, while a corybantic individual dances in the centre of the boat, and shrieks out a weird song to the accompaniment of a pair of clashing The course is generally a fairly short one, but, as soon as one race is decided, the boat-men paddle slowly back to the starting point, and at once set off again upon their wild career, and the process is repeated time after time till all the competitors are thoroughly exhausted. सत्यमेव जयते

Tigers are found near the foot of the Khasi Hills and are netted by the villagers. Directly a kill takes place the tiger is followed by the bravest and most expert shikari and is marked down to his lair. The villagers then turn out armed with spears, daos, and guns, and keep up a terrific din till the place has been surrounded by a strong net fastened to bamboo posts. The space enclosed is generally covered with jungle, in which the unfortunate animal lies hidden, but a heavy log with ropes attached is slipped underneath the net, and dragged

backwards and forwards till the grass is beaten down. Furious at this disturbance the tiger charges the net, but it is driven back with spears and sharp bamboos. goes on the animal becomes exhausted from weariness and thirst. A split bambco is then thrust through the net, and water is poured down it into the huge beast's mouth to revive its flagging energies. During the night, large fires are lighted all around the net, and the people amuse themselves with songs and music. tiger is sometimes teased and worried for a week or more and no one is allowed to attempt to kill it, till a majority of the whole crowd assembled have decided that the proper time has come. The first shot is then offered to the man of highest rank who happens to be present. Heavy fines are imposed by the village community on any persons who fail to attend on receiving information of the kill, who leave their posts before they are relieved, or who break any of the other rules laid down by the community. In the same portion of the district wild pigs are shot, and, sometimes, speared by men mounted on tame buffaloes. The pig does not notice the man on the buffalo's back, and he is thus enabled to approach sufficiently near to deal a blow which generally proves fatal. Occasionally, also, pigs are speared from trees, but this form of hunting is only crowned with success when the animal breaks cover in exactly the desired direction. namganj subdivision, the villagers often race their ponies in the haors, the Pous Sankranti being the season of the year which is specially set apart for these local Derbys. Boys and young men play cricket and football, and native games akin to prisoner's base and tip-cheese. Song and music, of course, are popular, and theatrical performances are given at weddings and on feast days. A special form of dance is known as the ghatu's nautch. The ghatu is a young Nat boy who is hired by the villagers, often at a considerable salary, to dance to them in the evening. This form of amusement is very popular, but it is doubtful whether it has a very elevating effect upon the moral character of the people, as the ghatu is generally treated as a pet by the younger members of the community.



				rist of femples.		·
·	Place or pargana in which situated.	Name of temple.		Name of founder and date of foundation.	Special god to whom the temple is sacred.	Brief description of building.
				NORTH SYLHET.		
-	Dbakadakahin—Vil- lage Dattarail.	Mahaprabhu	:	Mahaprabhu Jagannath Misra and others of Chaitanya and The masonry building was bis family, about 1700 A. D. Nityananda. of 1897. The idol is now in a cutcha house,	Chaitanya and Nityananda.	The masonry building was destroyed by the earthquake of 1897. The idol is now in a cutcha house,
	Nijpat-Jaintiapuri	Jaintesvari	4-11	Not known	Kali.	
	Do.	Siva Mandir	<b>T</b> a (	Do	Siva	Masoury.
<b>-</b> 22	Sylbet town	Sridargabari	नयत	Lala Gour Hari Singh, about Sridurga 1780 A. D.		Corrugated iron roof and maseoury walls.
	Do. (Kalighat) Kalibari		:	Lala Har Chandra Singh, Kali about 1800 A. D	Kali	. Do do.
	Do. (Lamabazar)	Бавоаші	:	About 1750 A. D	Kalbhairab	Masonry.
14	Mandalibogh, parga- Kalibari na Chhatak.		:	SUNAMGANJ.  Hindu zamindare of Baniya. Kali chung, about 1300 A. D.	Kali	Do.

		List of Temples-contd.	ntd.	
Flace or pargana in which situated.	Name of temple.	Name of founder and date of foundation.	Special god to whom the temple is sacred.	Briof description of huilding.
		SUNAMGANJ—contd.		
Tatikona, pargana Chhatak.	pargana Kalibari	Tilak Nandi, about 1800 A. D.	Kali	Masonry.
Town Sunamganj	Do.	Besidents of Sunamganj in 1882 A. D.	Do	Cutcha.
	यमे	HABIGANJ.	600	
Amirkhani, pargana Baniyachung.	о О	Keshab Misra	Kali, Mahadev and Vishnu.	Masonry building.
Віндвог, Raja's cut-	Rajarbazar Kali- bari.	Reja Ram Ganga Manikya Bahadur of Hill Tippere.	Kali	Cutcha.
Town Babiganj	Gabiganj Kali- bari.	About 1700 A.D. The temple was first located at Laskerpur, but in 1882 was transferred to Habiganj.	Kali, Mahadev and Vishnu.	Masonry.
-		SOUTH SYLBET.		
Gayghar, pargana Ita Uma-Maheevar	Uma-Mahesvar	Hridayananda Datta of Gay-gbar 1757 A. D.	Mahesvar and his consort Ums	Cutcha.

		<del></del>					<del></del>
Do.	Do.	Мавовгу.	Cutcha.	Do.	Do.	Do.	4 brick building on a small hill, a fair is held here annually during the Ulta Rath.
:	(Siva)	wn sa	:	i	•	į	:
Kali	Bauesvar (Sivo)	Bhabani Presad Chaudhuri, Kuli known as about 1700 A. D. Rajyeswari and Siva.	Kali	Do.	Siva	Kali	Basudev
son in		dburi,		about	EAST PIN		:
Rejarem Dae of Penchgeon in Kali 1728 A. D.	Jay Gobinda Sarma, about the middle of the nineteenth century.	ad Chau D.	Raghudeb Bhattacharja of Pancingson in 1704 A. D.	Gaugaram Biromani, about Do. 1800 A. D.	irmai and Barmai two un- married ladies of the Tippers Royal family in 1454 A. D.	Sarma in 1881	KARIMGANJ.
b Das of	hinds Sa of t y.	shabani Prasad about 1700 A. D.	eb Bh gaon in	kin Bir A. D.	and Hadies		K A R I M W u
Rajaram Dae 1728 A. D.	Jay Gobinda iniddle of century.	Bhaban about	Raghud Panch	Gaugare 1800 4	Nirmei marrie Royal	Bezer Servananda A. D.	KA Not known
:	:	Siver-	:	:	rerbari	Bezar	:
Kalitari	Вапевчаг	pargans Kali and Siver- bari.	Kalibari	Š	Nirmai Si	Manlavi Kalibari	Basudev
pargana 18gar.	balilpur, pargana Banesvar Bauli Setrasati.	pargans ar.	pargana Kalibari	pargana sati.	pargane	80	pargann ndakala.
Kadambata, pargana Kalibari Shamshernagar.	Kbalilpor, Rauli Setre	Maskandi, pe Sbaistanager.	Panchgaon, Ita,	Sadbuhati, pargana Hauli Sarasati,	Sankareena, pargana Nirmai Siverbari Nirmai and Hurmai two un- Balisira.  Royal family in 1454 A. D.	Sultapur, parga Chaitanyanagar.	Serutola, pargana Basudev Pancuaklandakala.
	_			32	wa	44	v) I

Place or pargana in which situated.	Name of Akhra.	Name of founder and date of foundation.	Special god to whom the Akhra is sacred.	Brief description of building.
		NORTH SYLHET.		
		BRAHMAN MAHUNTAS.		
Balaganj	Madanmohan	Madanmohan Residents of Balaganj bazar in Madanmohan	Madanmohan	Masonry.
Bhatirkhola village	Goyalpara	About 1750 A. D.	Jagannath	Do.
Кијадарј	Rajaganj	) interest	Brindaban Chan-	Do.
Sadipur	Sadipur	Murari Chand about 1850.		
Sankhi village	Lalabazar	Jagannath Nazir about 1800 A. D.	Mahaprahhu Krishna Chan- dra.	Do.
Tengra village	Tengra	About 1750 A. D.	Mahaprabhu Cutcha.	Cutcha.
Town Sylhet (Dharma- Taltola pasha.)	Taltola	About 1780 A. D	Gobindajee	Masonry.
Do. (Gopal-tila.)	(Gopal- Gopaltila	About 1750 A. D.	Gopaljee	Do

Do.	Do.	Do.	Do.	Cutcha.	Мавопгу.	Cutcha.	Do.		Cutcha.	Masoury.
ab	:	:	÷	:	•	i	÷		:	:
Radha Madb	Jagannathjee	Narsingjee	Baladebjee	Syamsundar Cutcha.	Gobindajes	Do.	Jagannath		Basudeb	Jagannath
Jugal Kisore about 1700 A. D.   Radha Madhab	(Kalighat) Jagannathjee About 1800 A. D	A Sanyasi about 1750 A. D Narsingjee	Madan Munshi of Raynagar Baladebjee about 1750 A. D.	(Nach ir Syamsundar About 1850 A. D	Jagannath Nazir of Bagher- Gobindajee khola about 1850 A. D.	Jasobanta Singh about 1800 A. D.	Hara Krishna Gosain, about Jagaunath 1750 A. D.	SUNAMGANJ.	Basudeberbari In the 15th century A. D	Sunamdi an ex-soldier about Jagannath 1800 A. D.
:	- :	•	:	:	:	:	:			:
(Kazal Jugaltila Haor)	Jagannathjee	Narsingjee	(Mira-Baladebjee bazar.)	Syameundar	(Noya Gobindajee Sarak.)	Do.	Jagannath			Akhra
(Kazal)	(Kalighat)	do.	(Mira- bazar.)	(Nachir Alli.)	(Noya Sarak.)	(Zinda-bazar.)	do.		hpur	:
D0.	Do.	Do.	Do.	D <b>9.</b>	Do.	Do.	Do.		Jagannathpur	Town Sunanganj

# List of Akhras-contd.

Place or pargana in which situated.	Name of Akhra.	Name of founder and date of foundation.	Special god to whom the Akhra is sacred.	Brief description of building.
		MAHUNTAS OF OTHER CASTES.		
Chhatak, Bazar		The shop-keepers of Chuatak Chaitanya about 1800 A. D.	Chaitanya	Masoury.
Jagannathpur	स	The Jagannathpur Chaudhuries Jagannath about 1800 A. D.		Cutcha.
Patharia	यमेव उ	Janaki Dasi Baishnabi in Radhamadhab Gutcha house. 1890 A. D.	Radhamadhab	Cutcha house.
Puran Laur, pargana Laur	नयत <u>े</u>	Golak Chandra'Das Purkayss. Advaits tha in 1898 A. D.	Advaita	Do.
lailkona, pargana Chhaiak	:	Jaganuath Chaudhuri about Chaitanya 1800 A. D.	Chaitanya	Masoury.
		HABIGANJ.		
Gbatis	Mahalprabbur Akhra.	Brahman Mahuntas.  Rem Nersyan and Rej Neisyan Geuranga Maha-Sualia.	Gauranga Maha- prabbu.	Мавопгу.

la- Do.	da Do.	Do.	Cutcha.	Masoury.	tm Do.	ъ Do.	na Do.	Do.	Gutcha.	na Masoury.
Jagannath Bala- ram and Subha- dra	Radha Gobinda	Gobindajee	Giridhari	Mehaprabhu	Tomb of Ram Krishna Gossin	Gauranga Maha- prabbu.	Rum Krishna Gosain.	Ġ	Jagahandhu	Baisnab shout Ram Krishna Goesin.
Hars Sundari Chaudhurani   Jagennath Bala- ram and Subha- dra	Krishna Chandra Gossin	Kriehna Das Namayat	•	Lal Singh Chaudhuri of Rarisal Mahaprabhu	MAHUNTAS OF OTHER CASTES. Ram Krishda Gossin, date uncertaid.	Bidura Nanda Gosain, about 1840 A. D.			A Raja of Hill Tippera, date Jagahandlu	Ananta Dae 1820 A. D.
Narsingh "	Bara "	Gobindajee "	Giridhari "	Mahaprabbu,	Bithangal large Akhra.	Mabaprabhu "	Rum k r i 9 b n a Gussin Akhra.	Krishna Gossin Akbra.	Jagabandhu Akbra.	Bithangal new Akhra.
Kamrapur	Murakari	Nabiganj Bazar	Noagaon	Rarieal	Bithangal	lkram	Jangal Rauta	Krishnapur	Baki	Srimangal

List of Akhras—concld.

# CHAPTER IV.

# AGRICULTURE AND FORESTS.

Agriculture—Rice—Mustard and Pulse—Linseed and Til—Sugarcane—Jute—Cotton—Garden Crops—Agricultural Implements—Storage and Threshing of Grain—Causes affecting productiveness of land—Yield and Value of Crops—General Remarks—Live Stock—Floods—Development of Tea Industry—Labourers employed—Soil required—Varieties of Plant—System of Cultivation and Manufacture—Green Tea—Outturn and Prices—Forests.

The principal crops grown in the district are rice. which is the staple food grain, tea, Agriculture. mustard, pulse, linseed, sesamum or til. sugar cane, jute and cotton; but, as the greater part of Sylhet is permanently settled and has not been cadastrally surveyed, there are no reliable data to show the area planted out with each of these different staples. In this, as in other matters, the historian of Sylhet labours under special difficulties, due to Mr. Willes' decennial settlement. It is impossible to trace the extension of cultivation, it is impossible to say, even at the present day, what proportion of the district is under crop, what proportion fallow, and what proportion waste, it is impossible to mark the rise or fall of any staple in the estimation of the peasants. Offensive though this doubtless is to the precise mind of the statistician, it is doubtful whether the practical loss is in reality very great. Although we cannot express the fact in percentages worked out to several places of decimals, we still can feel assured that Sylhet is densely peopled, that the proportion of good waste land available for cultivation is very small, and that during the last century there was

a great extension of the area under the plough. We know that the staple food grain is rice, that in normal years the district produces much more than it can possibly consume,\* and that the chance of anything even approaching scarcity is very small. The direct intervention of Government is so seldom necessary, that we can acquiesce, with some show of grace, in general knowledge, as distinguished from the particular information available for other districts. In the following paragraphs some account is given of the system followed for the cultivation of the various crops.

Rice, as has already been said, is the staple food crop, and probably covers two million acres of land. It falls into four main divisions, sail, which is transplanted on higher land, and aman, which is sown broadcast or transplanted on lower land, and, like sail, is reaped in winter; and aus and boro, both of which belong to the category of summer rice.

Sail is first sown broadcast in little beds or nurseries. The land is broken up in April or May, is ploughed five or six times till it is reduced to a fine puddle of mud, and is not unfrequently manured with cowdung and sweepings. The size of the nursery varies with the are to be planted out, but generally stands to the rice fields in

o In 1850 Dr. Hooker wrote as follows: "The Silcharrice is of admirable quality, and much is imported to Sylhet, the jheels not producing grain enough for the consumption of the people. Though Silchar grows enough for ten times its population, there was actually a famine six weeks before our arrival, the demand from Sylhet being so great."—Himalayan Journals, Vol. II., p. 319. Sylhet has always been in normal years a great rice exporting district, and it is difficult to believe that it at any time drew its food supplies from Cachar. At the present day of course rice goes from Sylhet to Cachar.

the proportion of from 1 to 14 to 1 to 18. The seed, which has been selected from the largest ears of the previous year's crop, is sown broadcast over the bed, and at the beginning of summer these patches of the brightest green herbage are a striking feature in the rural landscape. In the meanwhile the fields are being got ready for the The husbandman reception of the seedlings. ploughing as soon as the soil is softened by the spring rain, and repeats the process from four to six times, till he has reduced the land to a rich puddle. After the third ploughing the field is harrowed, and the little embankments, a few inches high, intended to retain the water, are repaired. When the seedlings are about seven or eight weeks old, they are taken from the nursery bed and carried in large bundles to the field. Here they are planted out in handfuls (qusi), each of which contains four or five The distance at which these are planted from one another depends upon the fertility of the soil, but the handfuls are generally placed about 9 inches apart. It is not unfrequently the practice to steep the young plants in water before they are planted out, and, if they seem too luxuriant, the tops are cut off when they are removed from the nursery. Transplanting goes on from the beginning of July to the middle of September. The work is of a most arduous description, as it involves stooping for hours in a field of liquid mud, under the rays of a burning tropical sun. Before the end of the rains the crop is fully grown though the ears are still empty; but about the beginning of October they begin to fill, and the field to turn to a rich yellow. From the middle of November to the middle of January harvesting is going on. The reapers grasp a handful of the ears and cut them off about eight inches below the head. These handfuls (hatta) are tied up with a piece of straw, and made up into bundles, which are affixed to either end of the bamboos which the villagers carry across their shoulders. The principal kinds of sail are terab-uli, which ripens early about the beginning of December and has a large yellow grain, balam which has a large reddish grain, khai which has a large yellowish grain, and thakur bhog which has a fine grain and is extremely palatable. Sail is often grown on land from which a crop of aus has been already taken.

Aman is sown broadcast about the middle of April, the field having been previously prepared by four or five ploughings. It is grown in flooded tracts, and the embankments made between the fields are smaller than in the case of sail, and are often dispensed with altogether. are three principal varieties. Bhogdhan is grown on higher land, is sown earlier, and ripens in November. Parisok and badal thrive in deeper water and are not harvested till December. Other varieties reported are lengri, hiraman, gutakh, hater mura, paricha, goyai, kalakura, dudbal, naliuri, jari, longmur betair, and birun. Of these goyai, kalakura, and hiraman have a long stem and so are generally grown in low lying tracts. Badal, paricha, lengri, and gutakh grow to a medium height and are sown on land which is neither very high nor very low. The other kinds grow on moderately high lands. Dudbal, naliuri, jari, and longmur are generally sown on land which lies near the hills.

Aus is generally grown near village sites, on the edge of haors, and on the banks of the A11#. rivers, which are usually above the level of the surrounding country. Ploughing usually begins when the ground has been softened by the rains of March, and is repeated some five or six times. seed is sown broadcast in April and May, and the plant grows with such rapidity that it is ready for the sickle in June or July. Aus is sometimes transplanted, and is generally followed by a crop of sail. This kind of rice is usually cut off close by the ground, as, at the season of the year when it is reaped, the straw is in much request for fodder. The principal varieties of aus are dumahi which ripens in 21 months, chengri which takes 3 months to mature, and murali which is sown on low lying land and is ready in about 4 months. Hati is so called because in theory it takes 60 days to ripen, though in practice it generally requires from two to four weeks more. The yield varies with the length of time the crop is in the ground, and the outturn of dumahi or hati is considerably less than that of the slower growing varieties. In spite of the rapidity with which aus ripens it can be seen in some part of the district at most seasons of the year. Low land aus is sometimes sown at the beginning of February, and in places the harvesting is still in progress in the middle of October.

Boro is an early rice which is grown in haors, and more especially in the Sunamganj subdivision, before the floods rise. It is sown on high land near bils and streams, on low land which is under water at the time of transplantation

but dries up shortly afterwards, and on land which lies so low that it can dispense with what is required by the first two kinds of land, i.e., artificial irrigation. further advantage appertains to this low land in that no ploughing is required, but the crop is very liable to be destroyed by flood, and the outturn for boro is comparatively small. Boro rice is, however, generally grown on the sides of haors, after the floods subside, and is irrigated from the water which remains at the bottom of the basin, and is prevented from escaping by dams which also serve to raise its level. A simple form of water-lift is employed to raise the water from this central reservoir on to the fields. The trunk of a tree is hollowed out and an opening is left all along the upper surface. This trunk is placed at the edge of the reservoir, and the end that projects above the water is fastened by a rope to a stout bamboo that is fixed at right-angles to a bamboo upright. To the further end of this bamboo a heavy weight is affixed, which raises the opposite end and the hollow trunk attached to it, well above the water. When a man wishes to work the lift he stands on the further end of the hollow trunk and presses it below the water, which promptly runs in through the slit. He then steps off, the weight of the stone comes in to play, and the water is tilted up and runs into a channel just above the reservoir. The slope of the haors is very gradual, and by means of a series of these kunds, as they are called, the water is raised from the reservoir in the centre and distributed upwards from terrace to terrace. Towards the end of October, the fields are cleared of the aquatic plants that have taken root there in the rains, and the nursery beds are

prepared for the reception of the seed. The seed itself is soaked in water for four hours, then kept in a cool place for thirty-six hours, washed again, and left uncovered till the grain begins to shoot. It is then sown broadcast on the nursery and left to grow there for about two The young plants are then pulled up, kept for months. two days in a muddy place to allow the roots to develop, and finally planted out in the fields in January and February. The crop takes about three months to ripen, and, if it is submerged by an early flood, the villagers try to gather all they can by diving to the bottom, or by pulling it up with bamboo hooks. The cultivation of boro rice gives rise to a good deal of quarrelling. The owners of low land sometimes protect their crop by building dams which injure the fields of others, water is occasionally stolen, and the necessity for co-operation in the construction of dams and irrigation channels is a source of friction. This kind of rice is divided into two classes: Sailboro, and boro. principal varieties of the former are sail, tepi, banajira, pankait, bashful, atuatopa, rata, chandana, naluatopa, gharmura, saulpani, barsail, harnarata, and of the latter, boro, kali boro, khaiya boro, lara boro, dhali boro and guabhir boro.

Mustard is grown on low lying land in the Jaintia

Parganas, which, in its natural state, is covered with high grass and reeds, on high land near the homestead from which a crop of seedlings has been already taken, and in haors. The total area under this plant is estimated at some 37,000 acres.

In Jaintia, the jungle is burnt at the beginning of the cold weather, and the ashes serve the purpose of manure. The seed is sown at the beginning of November after a single ploughing, and even this is occasionally dispensed with. In haors more ploughing is required, and the harvest is extremely insecure, as heavy rain in early spring may ruin the whole crop. High land near the homestead is ploughed some seven or eight times till reduced to dust, and is generally manured. The plants when ripe are pulled up, and the seed is trodden out by bullocks or threshed out with sticks. The area under pulse is comparatively small; the commonest varieties are arhar (cajanus indicus) and maskalai (phaseolus mungo radiatus).

Linseed, like mustard, is grown on high land near the village site as well as in the haors.

The ground is ploughed up twice or thrice in December, the seed is sown, and the crop is ready for harvest towards the end of March. The plants are then pulled up and dried, the seed is trodden out by cattle or threshed out with a stick, and finally sifted and winnowed. Heavy rain in March is injurious to the crop, and pigs near the Khasi Hills often do damage.

Til (sesamum indicum) is generally grown near the village site, and is almost a garden crop. The land is ploughed five or six times till reduced to a fine tilth, and is divided into little blocks about five feet square, by trenches three inches deep and nine inches broad. When the plants are about six inches high they are carefully weeded and hoed, and earth is spread over their roots. The seed ripeus in May, and the plants are dried and treated in the same way as linseed. Linseed is said to cover some sixty-nine or seventy thousand acres, whereas til is not grown on more than three or four thousand acres.

The area under sugar cane is said to be declining, ลล the profits obtained are Sugar Cane. sidered hardly commensurate with the It is sometimes planted on high labour that it entails. land near the homestead, but the bulk of the area under cane is situated in the hills to the south of the Karimgani and South Sylhet subdivisions, where it is grown by ex-garden coolies. The following are the principal varieties cultivated in the district. The dhol or dhali stands about seven feet high, and is generally grown near homesteads, the khagra is a hard and thin variety of the dhali, and the bombai is of a purple colour and is juicier than either of the other two. The land is hoed up till it is reduced to a fine tilth, and the tops planted in trenches between April and June. The patch is fenced with split bamboo, and there is usually a stout hedge of arhar dal (cajanus indicus), but constant watching is required to scare away jackals and other animals, and an empty oil tin with a clapper is generally to be seen suspended over each field. While the crop is growing it is continually hoed and weeded, and about August the leaves should be tied up round each cluster of canes, which is a troublesome proceeding. The earth from the ridges is heaped about the roots to strengthen their hold upon the soil, and this process is continued until the relative positions of

ridge and trench are reversed, and the canes stand upon ridges with the trenches in between.

The native form of mill consists of two wooden rollers, fixed side by side in a trough Preparation of molasses. hollowed out of a heavy block of The tops of the two rollers pass through a wood. beam, supported by uprights let through the lower block of wood into the ground, and are cut into the form of screws which fit into one another. To the larger of the two is affixed a pole, which is driven round in a circle, and thus causes the rollers to revolve. The motive power is usually supplied by the villagers themselves, but buffaloes are occasionally used for the work. Of recent years the wooden mill has been largely displaced by the iron mill which is easier to work. The cane is placed between the rollers, and crushed as it is slowly forced through. The juice trickles from the trough into an earthen vessel, and is then transferred to a small boat scooped out of a log. When twelve or fifteen gallons have been collected boiling begins. The furnace is hollowed out of the ground, and has four circular openings to receive the cauldrons, which are made of the most durable kinds of potter's clay. Two of these vessels are placed about 9 feet from the furnace mouth, and only serve to heat the juice before it is transferred to the other vessels When the juice has been reduced to the to be boiled. proper condition it is ladled into a wooden vessel shaped like a small dug out, and is stirred for half an hour. the stirring continues the liquid loses its dark brown colour, and assumes the consistency and hue of yellow It is then stored in earthen pots and the process mud.

is complete. Pargana Taraf in the Habiganj subdivision is especially noted for the excellence of the molasses manufactured there.

has not yet attained to any great dimensions, and in 1903-04 the total estimated area under this crop was only 9,200 acres. The plant is grown on high land near the village, and on the banks of the Kusiyara and the Manu in the North and South Sylhet subdivisions. The land is ploughed, and ploughed deeply, some eight or ten times. The seeds are sown in March or April, and when the plants are from some ten to fifteen inches high, a harrow (bindha), with teeth nearly one foot in length, is dragged over the field, and loosens the soil at the same time that it removes the weeds. When the plant is sown near the homestead the ground is liberally manured with cow-dung.

The plants are cut in August and September, stripped of their leaves, tied in bundles, and left to rot in pools of water from seven to twelve days. When they are ready a handful of stems is taken up, broken in the middle, and beaten to and fro in the water, till the inner part drops out and only the fibre remains. The bundles of fibre are then dried and are ready for transport to the market. The leaves of the jute plant are eaten fresh as a vegetable, and when dried are thought to possess medicinal properties. Small patches of rhea (boehmeria nivea) are grown in the gardens of the fishing castes, where it is heavily manured. The skin is stripped off from the stem and the fibre separated from the outer covering. The

thread obtained is exceptionally strong and durable, but the difficulty of decortication has hitherto prevented the growth of rhea on a commercial scale.

Cotton is grown by Tipperas on the hills in the south of the district. The fibre is stiff and has a short staple, but the percentage of fibre to seed is unusually high.

One of the commonest of garden trees is the plantain (musa sapientum), of which there are Garden crops several varieties. The best fruit is obtained from the chenichampa, which has a small well flavoured fruit, the kulapati and safari, large trees which yield large plantains, and the dingamanik, which has a soft trunk and long fruits, which are generally gathered and sold while still quite green, as if kept when ripe they soon develop a saline taste. There are two kinds of athia known as ghi and bhim. Both are valued for their soft leaves and the coolness of the pulp, but the former is preferred as The kachakala has the same shape as it has fewer seeds. the athia, but has a sharper taste and is generally used as a vegetable. Other varieties of the plantain are the sail or gopi, the bartaban, and gerasunder. The betelnut (areca catechu) is very common in the eastern part of the district, where groves of these graceful palms add much to the beauty of the landscape. The tree does not thrive if the roots are covered with water, and it is seldom seen in the submerged tracts in the western portion of Sylhet. Of recent years it has been attacked by an insect pest which makes it gradually shrivel up and die. The pan vine (piper betel) is occasionally trained up the stem of

the areca palm, but is generally grown by Baruis in carefully fenced gardens along the banks of the Kusiyara or Manu, or in the hilly-country to the south. Other common fruit trees are the jack fruit and the mango, but the fruit of the latter tree is generally spoilt by worms. The vegetables which are most in evidence are gourds, pumpkins, cucumbers, beans, different kinds of arums (kachu), some of which attain an enormous size, radishes, and brinjals.

The agricultural implements in use are of a very simple character. The plough is usually made of the mango or jack fruit tree, or some other hard wood.

It consists of three parts-the handle and body which are usually all in one piece, the pole which joins the plough at the junction of the handle and the body, and the yoke, which is merely a piece of bamboo fastened by rope at right angles to the pole, with pegs affixed to it to keep it from sliding from the necks of the bullocks. The front portion of the body is sharpened to a point which is shod The whole instrument is suited to the with iron. wretched class of animal required to draw it. It weighs as a rule about 20lbs., and, when cattle are used, the yoke seldom stands as much as 36 inches from the ground. When buffaloes are employed the whole plough is constructed on a larger scale. It is obvious that such an implement can only penetrate from three to four inches into the soil, but the wretched quality of the plough cattle prohibits the use of a more effective instrument. Ploughs in Sylhet are nearly always purchased, and not made at home as in the Assam Valley, and cost from As. 12 to Re. 1.

The harrow (moi) is generally a bumboo ladder, about eight feet in length, on which a man Other implements. stands as it is drawn across the field. It is used to crush the clods turned up by the plough before mustard or summer rice is sown, and to reduce the fields required for wet rice to puddle. Its place is sometimes taken by a plain log of wood. It is prepared by the cultivator himself from the bamboos growing in his garden. Hoes (kodalis) are used to trim the embankments (ails) which help to retain the water. The head is bought in the bazar and costs from As. 12 to Re. 1-4, and is fitted with a shaft by the farmer himself. with which the rice is reaped, have also to be purchased, and cost from two to four annas. The sugarcane mill has been already described in the paragraph dealing with the preparation of molasses. The ordinary implement used for husking grain is the dheki, a long beam with a pestle affixed at the end, which is supported by two posts at about two-thirds of the length from the head. The shorter end is depressed by the foot, and the pestle is thus raised into the air; the weight is then removed and the pestle falls into a small hole in which the grain is placed. When only a small quantity of grain is to be husked a mortar (gyle) and pestle (sekait or chhia) are employed. All of these implements are usually made by carpenters and purchased by the cultivator.

The grain is threshed as soon as it is brought from the field, and stored either in a separate granary (bhararghor), or, more usually, in a part of one of the cultivator's houses which has been set apart for the purpose. It is

threshed by driving cattle round and round over the heap of grain and straw, till the ears have been finally separated from the stalk. The grain is next passed through a sieve, and placed in a flat bamboo tray called kula. It is then jerked into the air and allowed to drop back into the tray, or held aloft and allowed to fall slowly to the ground till gradually the chaff is carried off.

The character of the rice crop depends more upon suitable supply of water than Causes affecting productiveness of land. upon the chemical constituents of the soil on which it is grown, and of water in Sylhet there is very seldom any scarcity. It is however, flood, not drought, that is the farmer's enemy. and the harvest often suffers from excessive and unseasonable rain. The different soils of the district have never been carefully examined, but the following kinds are recognised by the cultivator. Domarua or domativa is composed of clay with a slight admixture of sand, and is well suited to the growth of double crops. Athalu is a heavy clayey soil on which aman is generally grown, while chegua contains a large proportion of decayed vegetable matter, and is found in low swampy ground. Rice planted on this soil at first does well but tends to produce more leaf than grain. Balua, a sandy soil found near the rivers which issue the northern hills, is far from fertile, and bhurburia, a clay soil much broken up by worms, is thought to be more suitable for vegetables than for rice.

Serious damage is sometimes done to the growing crop by the insects which are called Insect pests. khatra, loai, poka, and monu (leptocorisa acuta). The monu is a small bug which injures the rice plant by feeding on the stems and sucking all the sap from the young grains. It is most prevalent in July and August, and is particularly in evidence during a spell of hot dry weather. High wind and rains drive it back into the jungles, and good results are obtained by lighting fires, of vegetable refuse to wind-The best remedy of all is to collect the insects by smearing a winnowing fan with some glutinous substance and brushing it over the ears of grain, when many of the bugs will be found adhering to the fan. remedy should be tried in the morning or late afternoon, as the insects do not feed in the heat of the day. The khatra appears in April and May, the loai in May and June and the poka in November and December. Rain is wanted when sail is sown and is transplanted. but is not needed for the sowing of aus and aman. During every stage of its growth the plant is benefited by moderate showers, but rain is absolutely essential at the time when the ears are first appearing. Hail storms in December sometimes lay the crop and add materially to the cost of reaping, but fortunately are very local in their action.

The outturn of different crops varies according to the character of the season, and also to a great extent according to the character and level of the soil on which they are grown.

		lbs.	The statement in the margin shows
Sail Ans	••	1,000	the normal yield per acre laid down
Aman Boro Mustard	::	950 1,050 450	by the Agricultural Department after
Molasses	::	2,400	a long series of experiments. These
foures	only	repres	ent a general mean, and, even in a normal

figures only represent a general mean, and, even in a ne year, there are many fields whose outturn varies largely from the average. The yield of rice, it may be premised, is expressed in terms of husked grain. Like the outturn, the cash value of the crop can only be approximately The prices obtained by the raiyats vary to ascertained. some extent in different parts of the district, but probably average from Re. 1-4-0 to Re. 1-12-0 per maund of unhusked grain. Assuming that unhusked paddy yields 62 per cent. of clean rice, it would appear that the value of the harvest from an acre of sail, boro, or aman is roughly from 25 to 35 rupees, and from an acre of aus from 20 to 30 rupees. For mustard the villagers generally get from Rs. 2-12 to Rs. 4 a maund, so that the yield from one acre is worth from 15 to 22 rupees. of molasses varies considerably from time to time and from place to place, and ranges from Rs. 4 to Rs. 6 per maund. The value of the yield of an acre of cane ranges accordingly from Rs. 120 to Rs. 180.

There is very little, as yet, in the shape of intensive cultivation, the villagers do little or nothing to improve the character of the crop beyond selecting the best grain for seed, and manure is seldom used. Cowdung is scattered over the seedling beds and jute fields, and applied to garden crops, but large quantities of this excellent fertilizer are

allowed to go to waste. Sugarcane is often treated with oil cake, and, in parts of the district, the stubble and sods turned up by the plough are burned, and the ashes help to fertilize the soil. Mustard land also is enriched with the ashes of the jungle growing on it. As a general rule the peasant trusts to the heavy rainfall and to deposits of silt to do all that is required. and does not adopt either new methods or new staples. The cultivation of jute is, however, spreading, and in Madhabpur onions and potatoes are coming into favour. The majority of the farmers are small men, who have neither the means nor the knowledge which are requisite in the pioneer; and little improvement can be looked for, unless Government or some of the larger zamindars are prepared to show the way. The system of giving advances on the standing crop is not much in vogue. An exception must be made in the case jute, but the total area under this fibre is not large. Karimganj small advances are sometimes given for mustard, linsced, cotton, and molasses, which are then sold to the creditor at a price a little below that ruling in the open market, but only a small share of the profits of the farmer are diverted by this channel into the pockets of the capitalist.

There are three varieties of buffalo in Sylhet, the

Live stock.

Manipuri which comes from the state
of that name, the Bangar which is
imported from other parts of India, and a hybrid formed
by crossing the other two. The Bangar, though a much
more satisfactory animal than the cow or bullock of

Sylhet, is inferior both in size and appearance to the hybrid, which again is not as fine an animal as a pure bred Manipuri.

Professional graziers are not so numerous as in the Assam Valley, the scarcity of pasture in the rains being no doubt a serious difficulty. There are some ten herds of buffaloes in the Dharmapasha thans on the extreme west of the Sunamganj subdivision, four in Fenchuganj, Maulavi Bazar, and Rajnagar, one or two in Matiganj and Karimganj, and fifteen or sixteen in the Hakaluki haor. Elsewhere the number of professional graziers is very small.

A cow is said to remain in milk for about ten months and yields at the beginning from two to four seers every day. The amount gradually decreases till a month or so before the next calf comes, when it ceases altogether. The milk is very white and rich in fatty matters, and consequently yields a large proportion of ghi. The cows are said to begin breeding when three years old, and to continue doing so for fifteen years, during which time they give birth on the average to about ten calves. normal life of a buffalo is from 25 to 30 years. judged by the incisor teeth, and a buffalo is not aged till it is twelve years old. Male buffaloes vary in price from Rs. 20 to Rs. 100, and cows from Rs. 30 to Rs. 120. The Bangar buffaloes are cheaper than the hybrids, and much less costly than the fine animals of Manipuri breed. The prices paid in the Jaintia Parganas are considerably higher than those prevailing in the west and south of the district.

The cattle of Sylhet are some of the sorriest of their kind, and are undersized, half starved, Onttle. and not unfrequently diseased. Everything is left to that stern stepmother, Nature, from the time when the most active, and probably therefore the youngest, bull in the herd has succeeded in covering a cow, to the time when the progeny, worn out by semi-starvation and over work lies down to die. No attention is paid to breeding, cows and bulls alike exercise their reproductive powers at the earliest possible moment, and continue to do so without intermission. The parents of the calf are often close relations, and no attempt is ever made to effect any improvements in the stock. In cases of sickness remedies are seldom thought of, and the infected animal is allowed to mingle with the herd. The natural result is the production of a breed of undersized, weak, and miserable animals which are hardly strong enough to drag even the small native plough. Bullocks and cows alike are said to cost from Rs, 10 to Rs. 50, but it is very seldom that the higher price is paid. Rs. 15 to Rs. 20 is the more usual figure and the animals are generally dear at that.

In the Sunamganj subdivision, there is excellent grazing to be obtained in the cold weather when the floods drain off from the marshes, but during the rains the condition of the live stock is far from satisfactory. Nearly the whole of the country goes under water, and the cattle have to be kept in the immediate neighbourhood of the homestead and are fed on reeds and coarse grass, brought in boats from the higher ground at the foot of the hills, or on

aquatic plants and grass pulled from the bottom of the jhils. Rice straw, it is said, is not very rally used, partly because the floods come on very soon after the reaping of the boro crop, partly because the straw decomposes very rapidly. In the Habiganj subdivision, the people graze their cattle on the Raghunandan and Satgaon hills, but the area available has been considerably decreased of recent years by the opening of tea gardens. In the north and west, there are marshes which afford excellent fodder in the dry season, but this part of the district is very densely peopled and the villagers are said to experience difficulty in obtaining food for their cattle in the rains. Grass and rice straw are stored against this time of scarcity, but the supply not unfrequently runs short, and thefts of fodder are said to be fairly common. The conditions in North Sylhet are very similar. In Karimganj there is a considerable area of high land on which the cattle can be grazed during the rains, and in the dry season the most excellent pasture can be obtained in the Hakaluki haor. and in other places, such as the Anair and Hanra Kuri haors and the Chapra and Medal bils. Rice Straw, as in other parts of the district, is stored for use in the rainy season, but at its best it is unsatisfactory fodder, and it is, perhaps, partly responsible for the poor condition of the Sylhetti cattle.

The most common forms of cattle disease prevalent in the district are, foot and mouth Cattle disease. disease, rinderpest (quti), a disease called kachua, the principal symptoms of are flatulence and diarrhoa, diarrhoa (marki), cholera,

matikhoa, the first symptom of which is, as the name implies, the eating of earth followed by dysentery, and sukuna when the animal refuses to eat and dies after ten days or in a fortnight.

The goats are almost as degenerate as the cattle. Goats, sheep and ponies. They yield but little milk, the whole of which is taken by the kids, and are only kept for food or sacrifice. At night they are usually shut up in a small out house with a raised floor, which is approached by a slanting board or sloping bamboo platform, as a protection against jackals. There is no indigenous breed of sheep, and the animals imported The total number in the district is exdo not thrive. tremely small. The country ponies are, if anything, even more miserable specimens than the cattle. Few of them are as much as twelve hands in height, and they possess neither pace, stamina, or endurance. They have not in fact a single redeeming feature, and it is a matter for congratulation that their numbers are so small. European residents in Sylhet are compelled to obtain all their horse flesh from Calcutta.

which agriculture is confronted, but they are of so regular and general a character that they are treated by the husbandman as part of the established course of nature. In the chapter on the history of the district reference has been already made to the destructive inundations at the end of the eighteenth century, to the attempts made to control these deluges by a system of embankments, and to the conclusion to which

the authorities were ultimately forced that they were engaged upon an absolutely hopeless enterprise. the rains the north and west of Sunamganj is over-flowed by the waters of the various rivers that come down from the hills such as the Panatirtha, Maheskhali, Someshwari, l'ainda, Kangsa, Surma, Kalni, Khasimara, Mugai and Piyain. The north and west of Habiganj are submerged by the floods of the Dhaleswari, Sutang, Balabhadra, and Khowai; and in Jaintia, the Lain, Goyain, Peein, Lubha and other streams inundate the low lying tracts. however, only the fringe of marshy country which on three sides surrounds the higher and more fertile portions Though it must be admitted that floods of the district. occasionally do damage, it is obvious that the harm done in the more elevated tracts cannot be very serious or the district would not be able to support over 2,000,000 persons in a condition of comparative comfort. During the past twenty years, the floods of 1883, 1885, 1893, and 1897 have been unusually high, but no measures of relief were necessary.

Reference must now be made to one of the most important crops of the district, a crop which has attracted a considerable number of Europeans\* to Sylhet, and has led to a large local expenditure of British capital. Tea is said to have been first discovered growing wild in the Assam Valley in 1823, and the first garden was opened, in Lakhimpur, in 1835. In 1855, wild tea was discovered in the Surma Valley, and the first garden was opened in Sylhet at

The number of European planters in 1903 was: North Sylhet 15, Habiganj 26, South Sylhet 102, and Karimganj 5).

Malnichara in 1857. The progress of the industry was at first extremely slow, and the merits of Sylhet as a tea producing district were not recognised till comparatively The earliest figures available are those for 1868. In that year the area under tea cultivation returned at 2,050 acres, and the outturn at 251,000 Even in 1884 the outturn was only 5,561,000 lbs, which was less than half the crop obtained in Cachar, Sibsagar, or Lakhimpur. A great change then took place, and both the area under cultivation and the outturn increased with remarkable rapidity. By 1893 the yield amounted to 20,627,000 lbs. which nearly equalled that of Sibsagar, the largest tea producing district in Assam. The upward tendency was maintained, and in 1900, there were 71,490 acres under plant, which yielded 35,042,000 lbs. of manufactured tea, which was more than 4,000,000 lbs. in excess of that produced in any other district in the Province.

Statistics for later years will be found in Table VI.

which shows the number of gardens
in each subdivision, the area under
tea, the outturn, and the labour force.

Such local labour as is available for employment is generally unsatisfactory, and the coolies required for working the plantations have to be brought from other parts of India. In the ten years ending with 1890, the total number so imported was 71,950, and during the next decade it was nearly doubled and amounted to 141,650. The largest numbers imported in any given year were 26,450 in 1895 and 27,080 in 1896.

The following statement shows the locality from which the majority of these persons come. The climate of Sylhet is not unsuited to the natives of the United Provinces and planters are thus enabled to work their gardens with labourers who in Assam would quickly sicken and die. The coolies who are most difficult to procure, and who cannot, as a rule, be imported to Assam for less than a hundred rupees a head, are Sonthals and other jungly tribes from the Chota Nagpur plateau. Of them there are comparatively few, and one of the most important assets in the planter's favour in Sylhet is the fact that he can obtain his own labour at fairly moderate rates.

1901.			Number	Percentage.
Total	•••	141	144,876	***
Chota Nagpur	•••		22,745	16
Other parts of Bengal		(cine) (ce//	22,067	15
United Provinces		सद्यमेन ज	युने 41,169	28
Central Provinces	•••	•••	12,681	9
Madras	•••	•••	10,079	7

The gross cost of importation is, however, large and few people would be willing to expend considerable sums of money in bringing up coolies to the district, without some guarantee that for a time, at any rate, they would be able to retain their services. This guarantee is afforded by Act XIII of 1859, which empowers a magistrate to order a man who has taken an advance of money on

account of work to be done by him, to complete his contract, and to punish him with imprisonment if he declines to carry out this order. The number of cases in which the coolie is actually confined is, however, small, and in 1903 only 13 deserters were punished with imprisonment, or less than one in every 10,000 of the labour It has already been remarked that the gardens of Sylhet are fairly healthy on the whole. Unfortunately the mortality is occasionally high on newly opened gardens, and amongst batches of new coolies, who often come up in a poor state of health, especially in times of famine, which is the very time when recruiting is most The average mortality amongst adult labourers in the ten years 1880-89 was 35 per mille, and in the next decade the rate was 37. During the pist three years, (1900-03) it has not exceeded 25 per mille. 1897 was the most unhealthy year, with a deatht rate of 51 per But this, after all, was no higher than the recorded mortality for the Province as a whole, which, thanks to the extremely defective agency for registration, was undoubtedly much below the mortality which actually occurred.

A friable red loam is thet soil that proves most suitable for tea. The plant requires a well distributed and heavy rainfall, but anything in the shape of water-logging is most prejudicial to its growth, ando gardens should only be planted out on land which can be well drained. Land which in its natural state is covered with tree forest, is usually considered the most q suitable, as the absence of timber generally shows either that the place is liable to flood, or that the soil is sandy, or that the rainfall is

deficient, but excellent results have been obtained in Sylhet from reclaimed marsh land. Most of these bil gardens are situated in the Langai valley, but they are also found in the valleys of the Juri or Sonai. taken to select a piece of marsh land which is above flood level, and it is then thoroughly drained. This is a very expensive operation, and the mere drainage of a bil garden costs nearly as much as the complete opening out of an estate on higher land. The main drain is from 12 to 15 feet deep and as many wide, and every twelve yards it is joined by lateral drains. The yield is, however, unusually large, and these gardens have proved to be a very good investment in spite of the heavy initial expen-The first bil garden was opened at diture entailed. Adamtila in 1878, and the largest gardens of this kind in Sylhet are Siphinjuri, Patni, Piplagul, Champabari, Tilbura, Chandkhira, Langai, and Sonakhira, all of which are situated in the Langai valley.

Assam indigenous, which has a leaf from 6 to 72 inches in length by 23 to 23 inches in width, Manipur or Burma indigenous with a larger, darker, and coarser leaf than the preceding variety, Lushai or Cachar indigenous, whose mature leaf is from 12 to 14 inches long, and from 6 to 7½ inches wide, and the Naga indigenous which has a long and narrow leaf. In addition to these four varieties there is the China plant, and different kinds of hybrids. The China tea is a squat and bushy shrub with small leaves, which gives a lower yield per acre than the other kinds. It is many years since China seed was planted out in new clearances.

and considerable areas covered by this plant have been In its natural state the indigenous plant abandoned. attains to the dimensions of a tree, varying from 20 to 50 feet in height, though its girth seldom exceeds two feet. It has a vigorous growth and yields a large outturn of fine flavoured tea, but is delicate when young. Of the hybrid variety there are many qualities, ranging from nearly pure indigenous to nearly pure China. A plant with a very small admixture of China is usually preferred, as this imparts the hardiness the want of which is the one defect in the indigenous variety. The best seed grown in Sylhet is obtained from the Lakatura garden. The price varies largely in accordance with the demand. and, of recent years, has ranged from Rs. 150 a maund prior to 1898 to Rs. 15 to 35 a maund in 1903.

The seed is planted in nursery beds in December and January, and kept under shade System of Cultivation. till the young plants are three or four inches above the ground. Transplanting goes on between April and July, whenever there is rain, the plants being usually placed from four to five feet apart. During the first two years of their life little more is required than to keep the plantation clear of weeds. time the plants are from two to four feet high, and at the end of the rains they are pruned down to fifteen inches or a foot, to encourage lateral growth. In the third year the plant can be lightly plucked over but the yield of leaf is small. Pruning is continued every year. Only about two inches are left of the wood formed since the previous pruning and any unhealthy or stunted branches are removed. During the rains, the garden is hoed over several times, in order to render the soil permeable both to rain water and the roots of the bush. At the end of the rains the ground is hoed up to the depth of 8 or 9 inches. object of this is to protect the land from drought as the hoed up soil prevents the evaporation of water from the lower strata. It, also, adds to the fertility of the land by exposing it to air, light, and changes of temperature. Manure has hitherto been little used. Oil cake and cowdung are, however, sometimes spread about the plants. and exhausted land is not unfrequently top dressed with rich soil from a neighbouring marsh. The cost of these operations is considerable and they are not invariably successful from the pecuniary point of view. Matikalai (phaseolus mungo radiatus) is sometimes sown among the bushes and afterwards hoed in as a green manure.

Plucking begins in April and is continued till the beginning of December. The bud and the two top leaves are taken from each shoot, but fresh leaves soon appear, and in about five weeks time the shoot is ready to be plucked again. This throwing out of new leaves is termed a flush, and there are usually six or seven full flushes in a season, though each bush is picked over every ten days or so, as the twigs develop at different times. The plucking is usually done by women and children, while the men are engaged in hoeing up the ground around the plants.

The plant is liable to be attacked by a large number of pests, the best known being the tea mosquito or blight, the green fly, and the red spider. A full account of these pests will be found in "The pests and blights of the tea plant" by Watt and Mann, Calcutta, 1903.

When the leaf has been taken to the factory, it is spread out in thin layers on trays System of Manu-facture. and allowed to wither. Īn weather the process takes about 18 hours, but if it is cold and wet it may be 30 hours before the leaf is ready. When the leaf has been properly withered it is placed in the rolling machines. The object of rolling is to break up the cellular matter and liberate the juices, and to give a twist to the leaf. Rolling taken about 40 minutes, and after this the leaf is spread in a cool room for from 3 to 5 hours to ferment. It is then placed on trays in the firing machines, through which hot air is driven, until the last trace of moisture has been expelled, and the tea is crisp to the touch. The leaf is then passed through sieves of varying degrees of fineness, and the tea sorted into different grades. The best and most expensive quality is called broken orange pekoe and is made from the bud or tip, which contains all the good qualities of tea in a more concentrated form than any of the other leaves, is stronger, and has a The other grades, which are more delicate flavour. differentiated by the size of the mesh through which they pass, are orange pekoe, broken pekoe, pekoe, souchong, and fannings. After the tea has been sorted it is fired once more to remove any moisture it may have absorbed from the surrounding atmosphere, and is packed in lead lined boxes while it is still warm. Tea loses largely in weight during the process of manufacture, and about

four pounds of green leaf are required to produce one pound of the finished article.

Of recent years an attempt has been made to introduce the manufacture of green tea Green Tea. in order to meet the demands of the American market. In 1902, the Indian Tea Association offered a bounty of 11 annas on every pound of green tea manufactured. The following year this bounty was reduced by half, and over a million pounds of green tea were exported from Sylhet. The principal difference between the manufacture of green and black tea is that the former article is not fermented. As soon as the leaf comes in it is steamed in a drum for about half a minute, a process which turns it a bright green colour, and effectually stops all fermentation. Excess moisture is removed by a hydro-extractor or centrifugal machine, and it is then rolled, fired, and sorted into the following different grades, pinhead gunpowder, gunpowder, young hyson, hyson No. 1, hyson No. 2, twanky, and dust. The infused leaf should be of a bright green colour, and the liquor of a very pale yellow shade. Most of this tea is sent to North America, but a small quantity is sold in the midland counties of England.

The average yield per acre varies largely in different years and on different gardens, but Outturn and Prices. may usually be taken as at about 500 lbs. per acre. Since 1897, the lowest average was 412 lbs, in 1898, the highest 536 lbs. in the following year. Prices, of recent years, have been on the downward grade. In 1868, the Commissioners appointed to enquire into the state and prospects of tea cultivation in Assam, Cachar, and Sylhet, reported that tea must fetch at lease two shillings a pound if the industry was to be a profitable one. In 1887, the first year for which returns are available, Surma Valley teas fetched about As. 8 per lb. The price fluctuates considerably and in 1894 was as high as 8 annas 8 pie. It then began to fall, and in 1898 was only 5 annas, while in 1902, it was 4 annas 3 pie; but in the following year it was nearly an anna higher. The fall in price has, however, been accompanied by a great decrease in the cost of production, which is largely due, amongst other causes, to the increase in the average output. In 1872, the highest yield from any garden was 315 lbs per acre-thirty it was probably four times as large. years later Most of the tea gardens are situated on the low hills in the south of the Habigani, South Sylhet, and Karimgani subdivisions. In South Sylhet they reach almost up to the Kusiyara river, some distance to the north of Maulavi Bazar. In Appendix A will be found a table showing for each tea garden in the district, its gross area and the area under plant, the labour force, the names of the owners, and the distance from the garden to the nearest subdivisional head-quarters station.

In the Fifth Report submitted to Parliament in

1812 A. D. by the Select Committee
on the affairs of the East India Company it is said that Sylhet is chiefly productive in rice
and cotton, but is of more importance from the natural
growth of timber which is largely used for boat building.
It is probable that, even at that time, Sylhet timber, like

Sylhet lime, was actually brought from places which were beyond the borders of the district, and, at the present day, though considerable quantities of forest produce pass from Sylhet into Bengal, most of it was grown in Cachar, Manipur and the Lushai and Tippera Hills.

The Sylhet state forests fall into two main classes, the reserved forests, which cover an Area of reserves and unclassed state forests. area of 103 square miles, and the unclassed state forests, which, in 1902-03, covered an area of 179 square miles. Unclassed state forest is neither more nor less than 'waste land at the disposal of Government, and does not of necessity possess the very smallest silvan characteristics. may be a large swamp which goes under water in the rains and is totally destitute of trees, it may be a small piece of arable land, which has been resigned by its former owner and has not yet been settled with any other person, or it may be, as its name suggests actual tree In the case of Sylhet, the proportion of unclassed state forest which falls in the latter category is probably not large. Most of this unsettled Government waste is situated in the Jaintia Parganas, or in swamps and hills in the south of the district.

The management of the Government forests is generally entrusted System of management. Assistant Conservator who sanctioned staff of 4 deputy rangers, 3 foresters, 17 head guards and 42 forest guards. Settlement holders in the Jaintia and Pratapgarh Parganas and the Langai-

Singla valleys are allowed to remove from unclassed state forests forest produce, other than reserved trees, free of charge, provided that it is for their own consumption and not for sale. Permits are also issued to traders for timber and other forest produce. On this a royalty is paid, the rates charged varying from one to four annas for every cubic foot of timber in the rough, or for every hundred bamboos. If the timber is situated in a reserve, the tree must not be felled till it has been marked by a forest officer deputed for the purpose. Timber or other forest produce is almost invariably removed by water, and ultimately reaches one or other of the revenue stations of the district.\* Here it is measured up and assessed to royalty, which may be sent by postal order to the nearest treasury. On receipt of the treasury voucher, a pass is issued, and the owner is allowed to remove his property. Forest produce coming from private land is also stopped at these stations, but, on the production of a certificate of origin signed by the owner or his agent, a pass is issued for its removal. सन्यमेव जयने

The most valuable timber trees found in the district, which are largely used in the con-Trees and trade in forest produce. struction of houses and boats, are iarul or ajhar (lagerstræmia reginæ), sam (artocarpus chaplasha), gundroi (cinnamomum glanduliferum), kurta

<sup>\*</sup> The following are the revenue stations in Sylhet :-

<sup>1.</sup> Patharkandi on the river Langai. 7. Chhatak on the river Surma.

<sup>8.</sup> Sunamganj "
9. Laurergar " 2. Langai 3. Silua " Panatirtha or Jui. 17 72

<sup>4.</sup> Maulavi Bazar ,, ,, Manu, 5. Manumukh ,, ,, Kusiyara 10. Muchikandi ,, 6. Kasairghat ,, ,, Surms. 11. Dinarpur ,, Jadukata. "Khowai.

<sup>&</sup>quot; Gopla.

(isonandra polyantha), rata (dysoxylum binectariferum) and poma (cedrela toona). Simul (bombax malabaricum), am (magnifera), kadam (anthocephalus cadamba) and harish (albizzia stipulata) are converted into tea boxes. The trees are felled, sawn into logs about fifteen feet in length, and dragged by elephants to the nearest stream, down which they are floated to their destination. principal centres of the timber trade are Patharkandi in the Langai valley, Karimganj, Sylhet, Moulavi Bazar. Habiganj, Bhanga, Ajmiriganj and Lakhai. The industry is not confined to any particular section of the community. but in North Sylhet most of the saw pits are the property of Muhammadans. From the figures given in Table VIII it will be seen that nearly all the fuel, and fully half the timber extracted from Government forests in Sylhet, is obtained from unclassed state forest. Minor products from which revenue is realized are bamboos, thatching grass. and grazing. Fees are levied on all animals grazed by professional herdsmen in the Hakaluki haor, and the exclusive right to cut bamboos and thatching grass in the more inaccessible portions of the district is put up to auction.

The Langai forest, which is situated at the southern end of the Langai valley, between the Pratapgarh and Pathariya hills, was originally constituted a reserve by notification No. 57, dated 17th September 1886. A portion of it was subsequently disforested, and revised boundaries, which include an area of some 80 square miles, were gazetted in notification No.

The number affected is not very large. In 1902-03 fees were levied on 1,485 buffaloes, 1,146 cattle and 48 other animals.

3341 R., dated 13th September 1901. The greater part of this area consists of hilly country which slopes towards the river, interspersed with stretches of level land covered with high grass. The soil is a deep sandy loam which is rich in vegetable mould, and in addition to the trees already mentioned the following are found: Shundi (mechelin sp.), ping (cynometra polyandra), (dipterocarpus sp), (albizzia procera), karal (alstonia scholaris) and sitarjat (echinocarpus tiliaceus). Timber can be extracted without much difficulty, and floated down the Langai to the Kusiyara, whence it can be distributed to every part of the district. The average annual receipts from this forest in the three years ending with 1902-03 were about Rs. 13,000. The Singla reserve adjoins the Langai on the east and resembles it in its gene-It covers an area of 23 square miles, ral characteristics. according to the boundaries laid down in Notification No. 3341 R., dated 13th September 1901. Timber felled in this reserve is floated down the Sonai, to the Kusiyara, but from Table VII it appears that the average annual receipts, since the forest was formed into a separate reserve, have only been about Rs. 1,200.

## CHAPTER V.

## INDUSTRIES.

Lime-Pottery-Brass and Bell-metal-Weaving-Boat building-Workers in wood-Carving and children's toys-Cane work-Other manufactures-Fishing-Lac.

The following is a list of the manufactures of Sylhet apart from tea: Slaked lime, pottery, brass and bell-metal utensils, cotton and silk cloths, boats, wooden articles and palanquins, children's toys, chessmen, jewellery, shell bracelets and inlaid iron work, iron and stone work, fire-works, hookhas and tikiyas, mats, leaf umbrellas and fans, cane furniture, attar of agar, various kinds of oil, cane and bamboo baskets, cheese, ghi, and molasses.

Lime is brought from the quarries in the Khasi Hills and is burnt on either side of the Lime. Surma river from Chhatak to some distance below Sunamganj. A full account of the history of the industry will be found in the Gazetteer of the Khasi and Jaintia Hills. The process of manufacture is extremely simple. Big holes of the shape of an inverted cone and about ten feet deep are dug near the bank of the river. They are filled with stone which is piled up till the structure rises about five feet above the surface of the ground, and the upper portion is then covered with straw and plastered over with mud. A hole is left at the bottom facing the river, and a fire is built right underneath the centre of the pile of rock and continuously fed with reeds for some twelve to fourteen days, till the stone is thoroughly calcined. A little water is then sprinkled over it and the lime is ready for the market. The importance of the industry may be judged from the fact that over two million maunds of lime and stone were exported from Sylhet in 1902-1903. The following figures give some idea of the cost of the different stages by which limestone cliffs in the Khasi Hills are converted into slaked lime at Calcutta.

The approximate charges for laying down 1,000 maunds of stone at Chhatak are—Quarrying Rs. 30; dynamite Rs. 2; trollying to river's bank Rs. 10; boating from Therria Ghat to Chhatak Rs. 50; and Government royalty Rs. 20.

One thousand maunds of stone at Chhatak fetch from Rs. 125 to Rs. 130, and the cost of burning is from Rs. 120 to Rs. 150. A Chhatak maund of stone weighs 102 lbs. and yields one phera, or about 92 lbs. of slaked lime. The cost of 1,000 nominal maunds of slaked lime at Chhatak is thus from Rs. 245 to Rs. 280, and the price is said to vary from Rs. 290 to Rs. 400. Freight to Calcutta is from Rs. 200 to Rs. 230 per 1,000 maunds.

Potters are either Hindus of the Kumar caste, or

Muhammadans called Khuskis who are
regarded with some contempt by the
main body of their co-religionists. The earth used is
generally a glutinous clay, which is well moistened with
water and freed from all extraneous substances. If it is
too stiff, some clean coarse sand is worked up with it,

and a well kneaded lump of the material is then placed on the wheel, which is fixed horizontally and made to rotate rapidly. As the wheel revolves the potter works the clay with his fingers and gives it the desired The vessel is then sun-dried, placed in a mould, and beaten into final shape with a mallet, a piece of hard earth called balia being held the while against the inner surface. It is again sun-dried, the surface is polished. and it is ready for the kiln. The collection of the clay and firewood, the shaping of the utensils on the wheel, and the stacking of them in the kilu, form the men's portion of the work, while the final polishing is entrusted to the women, who sometimes mould small pots with their hands without employing the wheel. The instruments employed are the wheel (chak), which is about three feet in diameter and rotates on a piece of hard pointed wood fixed firmly in the ground, the mould (athal) a hollow basin about 16 inches long by 31 inches deep, the mallet (boila) and the polisher (chaki). The principal articles manufactured are water jars (kalash or kalsi, ghat or sarai), cooking pots (kachli, kurai or patil), larger vessels such as hari, matka, or jula, smaller vessels such as sara, kai, and kalki, cups, plates, and lamps. The potters also make clay images of the various deities which are painted in bright colours and worshipped at the various festivals, and small models of elephants and other animals which are used as children's toys. This branch of their art is said to be distinctly lucrative. A few villages in Habiganj are famous for large, strong, earthen vessels which are used for storing molasses, and the cooking pots of Bengaduba in pargana Bejura, and of Lukra in pargana Richi are in some request. The profits

of the business are said to be small, and the local pottery is being gradually ousted by a superior quality of goods imported from Bengal, and by metal utensils which are coming extensively into use. Rough glazed earthen ware caps of European manufacture and plates and dishes of enamelled iron are also taking the place of the Sylhet pots and vessels.

The brass and bell-metal industry is not of much importance. Its principal centres are Brass and bellat the district and sub-divisional headmetal. quarters towns, and at Badarpur, Nandanpur, Madhabpur, Akhailkura and Srimangal, but only about a thousand persons are supported by this trade. Bell-metal utensils are cast in moulds, but brass vessels are made out of thin sheets of that metal which are beaten out and pieced together. The implements of the trade consist of anvils of different sizes (nehai, thammua, and amti), hammers, pincers and chisels. The furnace is simply a hollow in the floor of the hut and the bellows are made of goats' skin. When it is desired to join two sheets of brass together, nicks are cut in one edge, into which the other edge is fitted, and the two are then beaten flat. A rough paste made of borax and pain, a substance which consists of three parts of sheet brass with one part of solder, is then smeared over the join. The metal is heated, the pain melts, and the union is complete. The principal articles manufactured out of brass are small flattish bowls often used as drinking cups (lota, bati), jars for holding water (kalsi), basins (dabar, tagar, tasla), and spoons (hata). From bellmetal are made lime boxes (chunati), cooking vessels (batlai), and cymbals (kartal).

Weaving is not practised as a home industry in Sylhet as it is in the Assam Valley, Weaving. and the great mass of the rural population dressed in the eheap fabrics are of Manchester and not in home made cloth. Jugi caste is strongly represented, but few of them now touch the loom, and such clothing as is produced is for the most part woven by Manipuris. In 1891, there were only 6,768 persons in the Surma Valley entirely supported by the weaving of cotton cloth, as distinguished from those who combined that occupation with agriculture, and, in 1901, there were only 5,009 persons in Sylhet whose principal means of maintenance was the loom. The whole question of weaving in this Province has been dealt with at great length in a monograph on the Cotton Fabrics of Assam published at Calcutta by the Superintendent of Government Printing, 1897. system followed in the Assam Valley is described on pages 30 to 51, and this is the system adopted by the Jugis on such occasions as they think fit to return to their traditional occupation, and occasionally also by the Manipuris. An alternative Manipuri process is described on pages 77 and 78. In the absence of elaborate plans and diagrams, descriptions of mechanical processes of this character are extremely difficult to follow, and those curious in the matter should refer to the monograph in question. Any one who really wishes to understand the way in which the work is done would, however, be well advised to study the subject in person and on the spot. The following is a brief description of the more important local products of the loom. The than or gilap is a large stout cloth made of white cotton thread, and used in the cold weather as a warm wrap. The ordinary size is 9 feet by 4 feet 6 inches, but it is sometimes 18 feet and even 36 feet in length and is worn double. The price ranges from As. 8 to Rs. 3. Other articles turned out are chadars or wrappers, dhotis or waist cloths, handkerchiefs, and napkins. The fanek is a garment worn by Manipuri women, which is fastened under the arms above the bust, and reaches to a little below the knee. It is made of green or dark blue thread with red and yellow stripes, and is sometimes embroidered with flowers in cotton or silk. The price varies from Rs. 2-8 to Rs. 7. The khesh is a thick cloth either plain or striped, used as a coverlet for a bed, as a wrapper by men, and as a petticoat by women. Kheshes are generally from 5 feet to 9 feet in length by 3 feet to 6 feet in breadth, and cost from As. 8 to Rs. 3. The Manipuris also weave cheap mosquito curtains which are sold for from As. 8 to Rs. 1-4-0 a set. Imported cotton thread is generally used, but the fact that the last census 2,383 persons in Sylhet were shown as upon spinning for their maintenance. dependent indicates that the cotton grown in the hills is not neglected. Nearly all of these spinners, it need hardly be said, were women.

The eri silk worm is reared by Assamese immigrants
who have settled at the foot of the
Khasi and Jaintia Hills, and by a few
poor Namasudra widows, but the cloth produced is
generally intended for home wear and very little comes to
market. The worm (attacus ricini) derives its name from
the eri or castor-oil plant (ricinus communis) on which
it is usually fed. From 5 to 6 broods are usually

reared in the year, those which spin their cocoons in November, February, and May yielding most silk. When the female moths emerge they are tied to pieces of reed, and are visited by the males who are left at liberty. The eggs are hatched in the house and take from a week to 15 days to mature. As soon as the worms appear they are placed on a tray, which is suspended in a place of safety, and fed on the leaves of the castor oil plant. When fully grown, they are about 31 inches long and of a dirty white or green colour. After the final moulting, the worms are transferred from the tray to forked twigs suspended across a piece of reed. and, when they are ready to spin, are placed on a bundle of dried plantain leaves or withered branches which are hung from the roof of the hut. The matrix of the cocoon is very gummy, and the silk, which is of a dirty white colour, has to be spun, not reeled off. Before this is done the cocoons are softened by boiling them in water and a solution of alkali. Empty cocoons yield about threequarters of their weight in thread.

Boat building has always been an important industry in Sylhet. Mr. Lindsay, who was Collector there in 1780, built one ship of 400 tons burden, which drew 17 feet of water when fully loaded; and experienced considerable difficulty in navigating her to the sea. He also built a fleet of 20 ships, and sent them to Madras loaded with rice, on the occasion of a scarcity in that Presidency. The following account of boat building in Sylhet is taken from an account submitted by Mr. Luttman Johnson in his General Administration Report for 1880-81: "The subdivision of Habiganj possesses at least two kinds of boats not

found elsewhere, the Lakhai Palwar and the Khawai The Khawai boat is, however, only a flat-bottomed "saranga," the simplest development of the dug-out The bed of the saranga is simply a curved dugout, on which the sides of the boat are built up. more elaborate boats are built on the lines of an imaginary keel, the two ends or "Galais" of which are propped up at the beginning, in the places they will occupy when the boat is finished. Great quantities of keels and half finished boats of Jarul (lagerstræmia reginæ) wood are made at Habiganj for sale at Phandauk Bazar in the Tippera district, where there is a great mart for timber. The "Barki" boat of Panduah, which plies in the river from Chhatak to Therriaghat, at the foot of the Khási Hills, is also peculiar to the district." It is. however, nothing more than a flat bottomed canoe, of very shallow draught, which is used for transporting limestone over the rapids in the hills. The boats built in the Balaganj quarter of the district are more spacious, as they are much wider than the Habiganj boats, though not so long. सरामेव जगने

The following account of the carpentry of Sylhet is taken from the same source: "Wood sawing is carried on in many parts of the district, specially at Bhanga, a place on the eastern border of the district, at the town of Sylhet, and at Habiganj. The sawyers generally come from the Habiganj subdivision. From the wood thus prepared, beams, rafts, and posts of houses are made, as well as platforms, bedsteads, benches, stools, wardrobes, desks, almirahs, chairs, tables, &c. Some of these are made after Calcutta

models. The wages of a carpenter vary from As. 8 to As. 12 a day. The carpenters also make agricultural implements, namely, the clodcrusher, the plough, and the yoke. The Manipuris make the wooden shoes, which are so universally worn by natives, and the baulas or pegs, which pass between the great toe and the toe next to it to prevent the sandal from slipping off the foot. These shoes and pegs are exported to some extent. Dhakadakshin, a pargana in the east of the district, is famous for the wooden plates, khanchas or barkoses, and vessels, charis or tagaris, made there." Palanquins are made at Lashkarpur, Rajnagar, Langla, and Chapghat.

The best carpenters are Manipuris, and they often Capving and child-pen's toys. turn out with a little carving Carving in ivory used also at one time to be a speciality of Sylhet town, but the art has unfortunately become extinct. Excellent children's toys are made from common wood. A wooden spindle, called dokan, is supported on two uprights, and is encircled by a piece of leather whose two ends are alternately pulled and relaxed by one of the carpenters, so that the spindle rotates with great rapidity. A rough hewn piece of wood is inserted in the hole at one end of the spindle, and the second man applies his gouge or chisel, which is supported on a rest called pholi. As the wood revolves he deftly and quickly fashions a peg, bowl, cup, top, or similar toy, and when the article is shaped applies the colour. This is imported from Dacca or Calcutta, the colouring matter being mixed with resin or lac, and the whole being of the consistency of a stiff putty. It is applied in bands as the toy revolves on the spindle, and polished with a dry leaf. This colour does not come off when moistened, a property which is most useful in the case of children's toys. The best kind of paint costs Rs. 6 per seer, but a cheaper and much inferior quality can be obtained for Rs. 3. Chisels and gouges which are made locally cost from As. 10 to Re. 1. The price of a set of 25 toys is Rs. 1-4, and the makers are able to live in quite as good a style as that of the ordinary cultivator.

The cane and bamboo furniture of Sylhet is cheap and of a good quality, a serviceable Cane work. chair costing as little as As. 6. Really good cane baskets are also to be obtained in the bazar, and the leaf umbrellas of Sylhet are quite a speciality. They are made of what is known as chatta putti (licuala peltata) on a frame work of bamboo, but, though they only cost about three annas each, they are being ousted by the imported article which is more convenient, in that it can be closed, and lasts much longer. Mats are of several kinds, the best quality being the famous sitalpati, which is made from the murta reed (maranta dichotoma), and is valued for its coolness and smooth texture. The finest quality of sitalpati is manufactured in pargana Chaualis and commands a fancy price. The neuli mats, which are made of split bamboo, are almost as fine as a coarse sitalpati, and last a good deal The best varieties of this mat are manufactured in pargana Chapghat, but bamboo mats are usually made of a much coarser quality. Mats are also made from nal (phragmites roxburghii), a high reed

which grows in marshy country; the fine kinds, which are called *chatis* or *maluas*, are used to sit or sleep on, the coarser varieties, known as *dhara*, *katia* or *chas*, are used for partition walls in houses, and are sometimes laid upon the cow shed floor. There is a considerable export trade in mats, and nearly 140,000 maunds weight of these useful articles are said to have been sent out of the district in 1902-03.

Tikiyas are made of powdered charcoal and cowdung by poor widows and are used in Other manufac-tures. hookah smoking. Short wooden hookah stems are manufactured in Sylhet, and so also is the flexible variety which is adorned with silver thread. Sola pith is made up into artificial flowers, ornaments. and crowns, and the red powder, abir or fagua; which is used at the Doljatra festival, is prepared in pargana Taraf. Oil is expressed from mustard, linseed, sesamum or til, radish, and the castor oil plant. Linseed oil is used to mix with paint, and til is generally taken medicinally. Radish when intended to be used for oil is sown very thickly, there is hardly any root, and the oil is expressed from the seed. It resembles mustard oil with which it is always mixed. Castor oil is used as food and also as a medicine for the itch. Oil is also extracted from the coal near the bed of the Panatirtha in the Sunamganj subdivision and is used as a remedy for skin diseases. Patas or stone pestles, and slabs used for pounding curry are made in Jaintia. and daos inlaid with gold at Rajnagar in the South Sylhet subdivision. Ghi and cheese are manufactured in Sunamgani and Nabigani. Gold and silver ware is

manufactured, but the articles produced have no conspicuous merit. Many of the goldsmiths are Manipuris, but there are a certain number of Sylhettis, up-country men, and natives of Dacca, the last named being the most expert of all. There is one saw mill in the district at Bhanga Bazar, a station intermediate between Karimganj and Badarpur. In 1903, this mill gave employment to some 50 persons.

The fishing industry is of considerable importance in Sylhet and is a source of no little The fishing industry. revenue to Government. In 1902-03 under this head amounted to the total receipts Rs. 66,900, and were distributed as follows: Sunamgani Rs. 5,500; North Sylhet Rs. 26,600; Karimganj Rs. 20,100; South Sylhet Rs. 2,100; and Habigan Rs. 12,600. Though the receipts from Sunamgani are comparatively small, it is the most important centre of the industry, as there are valuable fisheries in the permanently settled estates. The Subdivisional Officer estimates that as much as 500,000 maunds of dried fish are exported annually from this portion of the district. The fish are cut open, the viscera removed, and the flesh exposed to the sun on bamboo platforms. When dry fish oil is poured over them, and they are buried near the homestead till the time has come for despatching them to market. There is also a large trade in live fish, which, according to the Subdivisional Officer, amounts to some 100,000 maunds. They are carried to their destination in boats, the bottoms of which are filled with water which has to be changed every twelve Fish\* oil, which is used as an illuminant in lamps.

is obtained by frying the viscera, and soaking the head and flesh in water, when the oil rises to the surface. There is not much export trade in fish from the other subdivisions except from the Son bil near Karimganj, whence fish is exported to Hailakandi; and from the Hakaluki haor, whence it is sent by rail to the North Cachar Hills. The castes who are engaged in the industry are the Mahimals, Namasudras or Chandals, Dom Patnis, Kaibarttas and Bhuinmalis. Members of the higher castes catch fish for their own consumption but not for sale.

Public fisheries are sold at auction to a middleman who makes the actual fishermen pay, either System of a fixed sum for each fishing house or village, or, more generally, a fixed sum for every net or trap employed. Typical rates are Rs. 30 for each uthar jal, Rs. 6 for a jhaki or loya jal, Rs. 4 to Ks. 6 for a kheo jal, Re. 1 for a pelain, and As. 4 for a polo, hagra, or other bamboo trap. In the Hakaluki haor Government levies a certain charge for each net or basket used, but in the channels leading to this and other haors there are regular fixed fisheries called kheos. which are openings cut in the jungle at right angles to the stream, in which a stake net can be placed. In the Jaintia Parganas many of the Government fisheries put up to auction are bils or swamps; elsewhere they are generally sections of the numerous rivers with which the country is intersected. The most valuable fishery is the Hakaluki haor which brings in a revenue to Government of from ten to eleven thousand rupees a year. In Habiganj fishing rights in 51 miles of the Kalni river, from the Bibisana river to the Kusiyara, fetch as much as Rs. 3,500 per annum, while a section of the Bibisana, 2½ miles in length, was sold for Rs. 1,700. The Chatla bil in Karimganj fetches about Rs. 1,000. Most of the Government fishery revenue in North Sylhet is derived from the Jaintia Parganas. The best eating fish are hilsa (clupea ilisha), roe (labeo rohita), butchua (eutropichthys vacha), pufta (callichrous bimaculatus), magur (clarias magur), kai (anabas scandens), katal (catla buchanani) and chital, soul and prawns.

Bhar Jal.—Cost Rs. 16. A square net each side of which is about 24 feet in length. The two corners at one end are fastened a little above the water to two posts driven into the bed of the fishery 24 feet apart. The other end, to which ropes are attached, is allowed to sink in the water and is then drawn up with any fish that may have chanced to be swimming over the net at the time.

Dal Jal.—Cost Rs. 80 to Rs. 100. A stake net which is used to enclose a piece of water to which the fishes have been attracted by artificial cover formed from the boughs of trees.

Galfa or Ghona or Ber.—Cost Rs. 30 to Rs. 40. A net about 100 feet long and 10 feet deep which is allowed to float in a vertical position down stream, the top edge being buoyed by hollow bamboos. The fish, which swim faster than the net is floating, are caught in the meshes as they try to force their way through.

Ghatghati Jal.—Gost Rs. 10. This net is used by two men, each of whom takes one of the top corners in his left hand and ties the corresponding lower corner to his left foot. They walk out into the fishery till the net is in the form of a semi-circle, while their friends beat the water in the neighbourhood to drive the fish into the space enclosed. The men then meet and the fish are unable to escape.

Hefa Jal.—Cost Rs. 3 to Rs. 5. A triangle of bamboos filled with netting and fitted with a handle. It is used much as a shrimping net. The pelain is a smaller variety of this net and costs Re. 1. The heka jal is a net of the same kind used in rivers, and the jhinti jal one which is also used in bils.

Hera.—Cost Rs. 2 or Rs. 3. A rope which is used to catch the ghagal fish which always remains close to the bottom of the river or bil. The rope is dragged along the bottom, and the fish, when it feels it, retires before it and thus is guided towards the bank.

Hura Jal.—Cost Rs. 6 to Rs. 10. A long net, one end of which is tied to a post in a bil and the other held by the fisherman. He takes it out to its utmost limit and encloses a piece of water, catching all the fish which are inside.

Jhaki.—A flat circular piece of netting with a cord attached to the centre. The circumference is weighted with lead and the edge is turned up so as to form a series of deep pockets. The net is thrown so as to fall flat on the surface of the water, the weights pull the outer circle

down and together, and any fish inside are entangled in the pockets.

Khati.—A species of net or screen made of split bamboo and twine. A piece of water is enclosed by this net, which is then brought gradually towards the bank.

Kheo Jal or Shitkar.—Cost Rs. 4 to Rs. 8. A square net, the opposite corners of which are fastened together with pieces of bamboo. The net thus hangs like a sack from the pole to which it is attached, and is lowered into the water and raised again.

Maha Jal.—Cost Rs. 300 to Rs. 500. This net is something like the galfa, but instead of being allowed to drift down stream, it is arranged parallel to the bank and drawn towards it.

Sakubel—Cost Rs. 20. A triangular net the two sides of which are fastened to two bamboos joined at the apex. A little above their junction the bamboos are fastened to two stout posts on which they work on a pivot, and the base of the net is allowed to sink into the water. Pressure is then applied to the apex and the net and its contents are raised into the air. The sakubel is a large net the two sides being about 48 feet long and the base some 24 feet.

Sanga.—Cost Rs. 2. A net like a large pocket, about 24 feet across. The mouth of the pocket is fitted with two bamboos to which cords are attached, and the net is sunk in the stream facing the current. As soon as a fish enters the pocket the man slackens the cord attached to the upper edge of the mouth and pulls the lower edge

upwards so that the pocket is closed. Smaller nets of the same shape are the loya jal and the ilish jal. They are kept nearer the surface of the water than the sanga.

Uthar Jal—Cost Rs. 80 to 125. A large kind of jhaki which is too big to throw and is gradually laid out from two boats. This net is made in meshes of different sizes, the largest size mesh is called reg, the next size saphaya, while the smallest of all is known as bachaoi.

Fish are also caught in traps made of split bamboo, the doors of which open inwards so that the fish can shove them open from without, but cannot pull them open from within. They are of different shapes and are known as kuin, bair, or dari, gui, paran and runga. The hagra is a cone shaped wicker work basket open at one end only, and filled with brushword in which small fish take shelter. It is sunk in the bed of the river and pulled up every twelve hours or so. chunga is simply a hollow bamboo with holes in it, and is used in the same way as a hagra. Another device is the datia which is a split bamboo, the two ends of which are fastened in an insect and tied together with a piece of twine. The fish swallows the insect and the twine, the two ends of the bamboo spring apart, and the fish is unable to close its mouth. Another method of catching fish is to spear them at night with a trident called attar, when they are dazzled by the glare of a torch in the front of the boat. The ordinary fish spear is called kucha, but when the head is fastened by a piece of cord to the shaft and remains in the body

of the fish, it is known as jhagar. Small fry are caught in the polo, a species of conical basket which the fisher dabs down before him as he walks along the bil. If he feels a fish inside he puts his hand in through the top and removes it. A long tube shaped basket used to catch the kai fish and worked on the same principle as the polo is called jhupri.

About 25 years ago lac was produced in considerable quantities, but the industry is now in a very languishing condition. The insect is reared on the banian (ficus indica), but, for reasons which the cultivators have not yet succeeded in discovering, it no longer thrives upon this tree. The only places in which it is now produced are parganas Bhaterah, Baramchal, Langla and Kanaihati in the South Sylhet subdivision. Two crops are generally obtained in the year, the first being collected in May and June, the second in October and November. The first crop is largely used for seed.

सत्यमेव जयते

## CHAPTER VI.

## ECONOMIC CONDITION OF THE PEOPLE—COMMUNICATIONS—TRADE—TOWNS AND LOCAL BOARDS.

Subtenancy—Rates of rent—Rent law—Subtenancy in Jaintia—Subletting in the ilam estates—Wages—Prices—Food and dress--Houses and
furniture—Economic condition of people—Social restrictions—Railway—
Navigable rivers—Boat traffic—Roads—Post and Telegraph—Trade—Towns—Local Boards.

There are no statistics of subtenancy available for the permanently settled portion of Subtenancy. Percentage of ordi-nary cultivating classes who were— Sylhet, but the figures in the margin, which are taken from the Census 1901. 1891. Landholders .. Reports of 1891 and 1901, suggest Tenants Cultivators that more than half of the total unspecified .. | 1 area of the district is sublet. The bulk of the estates created at the time of the permanent settlement were so small that there has been no room for the growth of the intermediate tenures which are so common in Bengal. Many of the actual settlementholders drive the plough themselves, while the others let their land direct to the cultivator, and from the rent he pays them satisfy the Government demand.

In spite of the density of the population rents as a rule are fairly low, the ordinary rates charged ranging from As. 12 to Rs. 6 per acre; though good land in Habiganj and the most densely settled portions of the district will fetch as much as Rs. 12 or Rs. 15 per acre. The great majority of the landlords are small men, and have not the resources

or influence which would enable them to coerce refractory tenants; and, though there is considerable pressure on the land, the difficulty of realizing the demand acts as an effectual check upon any tendency to rack renting.

The tenants are protected by Act VIII (B. C.) of 1869. which confers a right of occupancy The rent law. upon any person who has held his land for a period of twelve years. The rent of such land is then not liable to enhancement, except on the ground that it is below the rate prevailing for similar land in the vicinity, that the value of the produce or the productive powers of the land have been increased otherwise than by the agency or at the expense of the raivat, or that he holds a larger area than that for which he has hitherto been paying. The relations between landlord and tenant are said to be fairly satisfactory. The average number of suits annually instituted in Sylhet under the rent law during the four years ending with 1902 was 4,057, but the immense majority were for sums that did not exceed Rs. 50.

In the Jaintia Parganas, for which more accurate statistics are available, most of the cultivators hold direct from Government. At the settlement which took effect in 1896, it was found that out of a total settled area of 215,000 acres only a little more than 7 per cent. was held by subtenants, who formed a little less than 7 per cent. of the total population. These tenants fell into four classes. The majority paid rent in cash at rates which varied from Rs. 7-8 to As. 6 per acre of cultivated land. The

former rate is fairly high but from the small proportion of land sublet it seems fairly clear that the higher figure must be quite exceptional. Of the 8,104 subtenants only 268 paid rent in kind, the amount given to the landlord being usually less than one-third of the total produce. Other villagers, though the number is probably but small, hold their land either on a service tenure, or discharge their obligations partly in cash partly in labour.

The proportion of land sublet in the Ilam estates,

the bulk of which are found in the South Sylhet and Karimganj subdivisions, is considerably higher. Out of a total area of 35,500 acres cultivated with ordinary crops nearly 42 per cent. is sublet, at rates varying from Rs. 8 to As. 6 per acre of rice land. Both of these are, however, exceptional rates, and the ordinary rent taken ranges from Rs. 2 to Rs. 3 per acre.

The labouring classes are for the most part recruited from the ranks of the humbler Hindu castes such as the Dom-Patnis, Malos, Namasudras, Malis, and Jugis, and the poorer Muhammadans, but even members of the Halwa Das caste will consent to act as ploughmen. Four annas a day appears to be the usual labourer's wage. The minimum is reached in Sunamganj, where men can sometimes be hired for 2½ annas, but, in all parts of the district, reapers at harvest time, house-builders, and load carriers are occasionally paid as much as As. 8 a day. In parts of the district there is a prejudice against carrying loads or

palkis for hire, and men who will plough and reap or help to build a house, object to being employed as beasts of burthen, in spite of the fact that for centuries all goods taken by land have been carried in this manner. There is a still stronger prejudice against working on the roads, and most of the repair work has to be entrusted to Nuniva coolies from Bengal. Servants are paid from Rs. 2-8 to Rs. 4 a month with board and clothing, and if they feed themselves generally receive from Rs. 6 to Rs. 8 per mensem. Difficulty is said to be experienced in obtaining both servants and daily labourers, but, in comparison with the Assam Valley, Sylhet is well supplied with people ready and willing to work for hire. The proportion of the population of the district supported by general labour is, however, only 1 per cent. as compared with 7 per cent. in the neighbouring Province of Bengal.

Rice is the staple food crop of the district, but the price at which it sells is largely affected by the condition of the harvest in Bengal. In the early years of British rule, the market was liable to violent fluctuations. This was not due to the want of proper means of communication, as the waterways of Sylhet and Eastern Bengal were as good then as they are at the present day. But the same facilities did not exist for a foreign export trade or for the despatch of grain up-country, and, when there was a bumper harvest in Sylhet, there was doubtless little or no demand for rice in those districts of Bengal which were accessible by water. The lowest price recorded was in 1786, when rice was selling at the rate of four and a half maunds

to the rupee, a price which hardly paid the cost of bringing it to market. Two years later it was up to Re. 1-8 a maund, but the normal price at the end of the eighteenth century seems to have been from 10 to 12 annas a maund for husked rice, and 5 to 6 annas for unhusked rice or paddy.

The last forty years have witnessed a steady rise in price, the average amount of com-Rise in price dur-ing past 40 years' but progress very irregular. mon rice obtainable at Sylhet for a rupee during each of the four decades between 1863 and 1902 being 25 seers, 21 seers, 16 seers, and 13 seers. But though the general tendency has been upwards, the chart, like that of the thermometer at Quetta, shows the most violent oscillations. the market rate was 31 seers, but two years later it had risen to 13. In 1872, it was back to 38 seers, but in 1879 it had jumped up to 11, only to fall again three years later to 37 seers for the rupee. Only once since 1882 has the price been less than Rs. 2 a maund, and this The highest rate on record was in 1897 was in 1888. when only 9 seers could be purchased for the rupee; the lowest in the last fifteen years was 1899 when the same sum brought in nearly 20 seers.

Communications on the whole are good, and the price of grain is fairly uniform through-Prices fairly uni-The general tenout the district. dency is for it to be highest in the South Sylhet and Karimganj subdivisions, where there is a considerable garden population, but this is merely a tendency and not an economic law, and rice is sometimes cheaper there than in Habiganj or North Sylhet. In May 1899, the price was recorded at twenty-four bazars in different parts of the district. The average was Rs. 2-2-1 a maund, and fifteen out of the twenty-four bazars were within two annas of this mean. The two extremes were Rs. 2-10-0 per maund at Durlabchara Bazar in Karimganj, and Rs. 1-11-6 per maund at Munshi Bazar in South Sylhet. Salt does not vary much in price from year to year. In the ten years ending with 1880, 8.7 seers were on the average procurable for one rupee. From 1882 to 1887, salt was cheap and the average for that decade was 11 seers; but the average for the next ten years dropped to 10.1. 1902, 10.4 seers were procurable for a rupee. Pulse also does not vary very much in price, and since 1900 has kept fairly steady at 13 seers for the rupee.

The price of rice, salt, and pulse in 1900 and subsequent years will be found in Table IX.

The ordinary food of the villager is hoiled rice, seasoned with spices or mixed with dal, or fish, or vegetable curry. Pigeons and ducks are occasionally eaten by the well-to-do, and in the west of the district rams are sometimes fattened for the table. The Muhammadans take fowl and, when they can afford it, beef. Cheese is sometimes eaten by the upper classes, and curds (doi) and fresh milk which has been coagulated by the addition of a little tamarind juice (chhana) are thought a dainty dish. Sweetmeats are made of flour or powdered rice mixed with ghi or oil, and sugar. Tea is comparatively seldom taken.

The clothing of an ordinary villager consists of a dhoti or waistcloth which costs 12 annas, and of which he will probably use four in the year, and two sheets which cost a rupee each. He also sometimes wears a small cotton coat which costs about 12 annas. A winter wrap costs Rs. 4 and lasts about two years, so that a man expends some seven or eight rupees each year upon his wardrobe. A woman wears a single garment—the sari, a long piece of cloth which is wrapped round the waist to form a petticoat and then thrown over the bust. It costs about 12 annas, and three or four are wanted every year. Amongst the upper classes chemises and bodices are coming into use, but the wife of a clerk can still dress on about eight rupees a year.

The cottage of the ordinary cultivator is built on a mud plinth, and the floor, though cool, Houses and furni-ture. is damp. The roof is of thatch, the walls of reeds plastered with mud, or of split bamboo, the frame-work of the house of bamboo. There are no windows, and the interior of the hut, which in itself is small enough, is rendered additionally dark and stuffy by partition walls. The houses of the middle classes differ in quantity and quality but not in kind from those of the ordinary villager. While a poor peasant will content himself with a single hut his wealthier landlord will have five or six. They are larger and better built. timber posts are sometimes used in place of bamboo, and corrugated iron instead of thatch, but the principle remains the same. Masonry houses are extremely rare. The furniture of the villager consists of a wooden bed. a stool or two, and, if the man is fairly well-to-do, of some wooden boxes and perhaps a chair. For bedding he has a dirty quilt made of old clothes, and his wardrobe is not distinguished either for the abundance or the excellence of his garments. Rough earthenware crockery of European manufacture and plates and dishes of enamelled metal are in common use. The poorer people sleep on a mat on the floor, but there are few houses in which a mosquito curtain is not to be found. Of actual poverty there is very little. The clothing of the cultivators though simple is all that is required at most seasons of the year, and there are probably few natives of the district who ever go in want of food. For the insanitary character of their homesteads the occupants are themselves chiefly to blame, and though there are few signs of wealth there is an equal absence of any evidence of grinding poverty.

The economic condition of the people is obviously a subject of much interest and im-Economic condi-tion of the people. Indebtedness and rate of interest. portance, but it is one with regard to which it is extremely difficult to obtain information on which reliance can be placed. The peasant in Sylhet has no desire to minimise his obligations, or to pose as a prosperous and wealthy person, and the reports that are received largely reflect the personal idiosyncracies of the individuals consulted. Indebtedness is said to be extremely common. are few areas in which less than one-fourth of the total population are said to be involved, and ir the west of Habiganj, in the Baniyachung, Lakhai, and Madhabpur thanas, and in parts of Karimganj, practically all the people are described as being in debt. On the other hand

Muchikandi, adjoining Madhabpur, the proportion is reported to be as low as 25 per cent. It is true that this locality is less exposed to flood than Madhabpur, but it seems unlikely that there should be so marked a variation in the condition of the people inhabiting contiguous thanas, and there can be little doubt that these estimates of indebtedness must be received with a considerable degree of caution. In view of the high rate of wages paid for manual labour and the small proportion of labourers in Sylhet, it is not easy to believe that there is really much of genuine poverty. The rate of interest ranges from 18 to 75 per cent., the lower rates being charged on loans of considerable sums. paddy is borrowed, the debtor undertakes to return double the amount or half as much again after the next crop has been harvested; and, as the loan is generally made for but a short period, the rate of interest is very high. Marriage, sradh ceremonies, litigation, and the purchase of cattle are the causes which generally drive the peasant to the money-lender.

It must be admitted that in the north-western corner of the district the conditions are not altogether favourable. Almost the whole of the country goes under water in the rains, there are no tea gardens, and little demand for labour except in connection with the lime industry. The Superintendent of one of the largest zamindaries in Tahirpur describes the people of that quarter as being "the most miserable lot of wretches on God's earth." On this the native Magistrate remarks, that had this gentleman, who is a native of the extremely

सत्यामेव जयते

prosperous district of Backerganj, been acquainted with the condition of the peasantry in parts of Madras, Bihar or the Central Provinces, or, indeed, it may be added, in many parts of the world outside India, he would probably have couched his opinion in more moderate terms. The floods are so high in this portion of the district that the majority of the people depend on one rice crop, the boro, which is reaped before they rise. When the country is submerged a large portion of their time is devoted to the collection of fodder for their cattle which sometimes has to be brought from a considerable distance; but, apart from this, they have little or nothing to do for a great portion of the year, and there can hardly be much prosperity where there is very little work.

The officer in charge of the Sunamganj police station states that it is unsafe to conclude that, because the lower orders decline to undertake menial work, they are necessarily well off. He draws a somewhat gloomy picture of their condition and describes them as " in need of almost all the necessaries of life, ill-fed, ill-clothed, and badly housed. They cannot stand against a single drought or failure of crop, and cannot undertake any work requiring even a small outlay, without applying for a loan. Yet their habitual laziness and race pride precludes them from doing work by which the people of other parts are raising their status before their eyes. They practically have no margin to enable them to struggle with success against even one season of scarcity, can perform no marriage or sradh without a loan, and cannot even purchase a pair of bullocks without going to the usurer." This picture also would seem to be painted in too gloomy colours. Deficiency of food is practically unknown, their clothing though poor is not unsuited to the climate, and their dietary, though unattractive to the European palate, is what they apparently prefer.

In the Fenchuganj thana, it is said that the standard of comfort is higher than it was.

The peat of the district more prosments are worn in place of lac and brass, carpet bags have come into use, and the leaf umbrella has been displaced by the product of the European factory. In South Sylhet and Karimganj, the great majority of the villagers are said to be in debt, but it is difficult to believe that the condition of the people is really quite as unsatisfactory as is alleged.

Little light is thrown on this important subject by the settlement reports. With regard to indebtedness in the Jaintia Parganas the Settlement Officer quotes Babu Prakash Chandra Datta who writes as follows:—

"The tales of indebtedness and living from hand to mouth in the statements recorded are common, but in most cases these are false and exaggerated, as strict enquiries have elicited, and are due to the peculiar fondness of Jaintia people to abstain as much they can from giving accurate information on matters in which they are interested. Of course, instances of real indebtedness are not wanting, as can be naturally expected, but the loans are generally contracted for marriages, religious ceremonies, for litigation, and rarely to buy cattle and to pay revenue. The majority of the real borrowers, it will be seen from the evidence recorded, are those who own larger areas

of land than are needed for their requirements or than they can cultivate, which they will not throw up, although obtaining no profit therefrom, because their forefathers held such an amount of land, and they will'lose their prestige if they are to abandon it now; or those who from a consideration of their social rank think it derogatory to work for hire when in need."

At the last resettlement of Ilam lands the Settlement Officer collected information with regard to the indebtedness of certain villages in the neighbourhood of Patharkandi. Here out of 393 householders 208 owed on the average Rs. 100 each, while in another village there were 81 debtors who owed altogether nearly Rs. 14,000 between them. Patharkandi is, however, situated in one of the less prosperous portions of the district, and it is difficult to believe that indebtedness is quite so prevalent or so serious in every part of the district as these figures would suggest, though the general impression of the native officers consulted is that it is very common.

As compared with the parts of India that are liable

General condition fairly satisfactory, though in some respects the Sylbettis are less fortunate than the Assamese.

to famine the people of Sylhet are undoubtedly well off. The rainfall never fails, and, though a heavy flood occasionally does damage, the harvest is

usually abundant and secure. Their surplus produce is sold direct to traders from Bengal, who can penetrate in their boats into almost every corner of the district, and there is no middleman to absorb a large share of the producer's profit. The villagers generally take three meals a day of cooked rice, and fish can be obtained without difficulty at all seasons of the year. They decline to work on tea gardens or on the roads, and actual poverty seems to be extremely rare. In some

respects, however, they compare unfavourably with the Assamese of Sibsagar and Lakhimpur. Their houses are better built, but owing partly to the scarcity of materials, partly to a dearth of land suitable for building sites, they have less room space per family than the Silk, which is so common in Assam, is hardly Assamese. ever worn by the cultivators in Sylhet, and such ornaments as they possess are in no way comparable to the costly lockets and ear-rings of Jorhat. The houses are generally crowded together in uncomfortable proximity, and in the flooded thanas on the west fruit trees and garden produce are unknown. In the central portion of the district bamboos are plentiful, and there may be a mango or jack fruit tree and a few plantains, but there are no dense groves of betel nut, and vegetables, tobacco, and such like crops are not generally grown. Further south and east, the garden land improves, and the areca palms of Karimganj must be a source of considerable profit to their owners. Several causes operate prejudicially against the villager. In parts of the district there is a certain amount of pressure upon the land, and the people would be more prosperous were it possible for them to extend the area under cultivation. In Assam, the womenfolk of the ordinary peasant do most of the transplanting of the paddy, and help in the harvesting of the rice, and in their leisure moments fish, or weave on the loom enough clothing to satisfy the family requirements. In Sylhet, the women are not allowed to go abroad, and weaving as a domestic industry is practically unknown. The peasant's clothes have to be purchased with hard cash and are not as warm or durable as those worn in the valley of the Brahmaputra. There are few restrictions on trade other than those imposed by the great law of caste.

Dom-Patnis, Kaibarttas, Namasudras, Mirdhas, and Mahimals alone sell fish;\*

Sunris alone sell wine; Jugis alone weave cloth; Kumhars alone make pottery and so forth. In the Dharmapasha thana, in Sunamgani, Saturdays and Tuesdays are considered unlucky days for a first ploughing or for sowing seed, bamboos must not be cut on Sundays or cattle sold on Monday. On the other hand, further east in the Sunamganj thana, Tuesdays and Saturdays are said to be the best days for sowing boro seed, while Sundays, Wednesdays, Thursdays, and Fridays are set aside for aman. Bamboos must not be cut on Sundays or Thursdays. houses built on Sundays, or money and paddy lent on the days of the new and full moon and the following days. In Baniyachung, people will not sell rice on Wednesdays and Sundays; and the former day is considered by Muhammadans in most parts of the district to be unfavourable for any undertaking. All over district, the last day of the month and the day of the new moon are considered inauspicious. In Jaintia. the villagers will not begin ploughing on Sundays or sowing on Mondays, or cut bamboos on Thursdays and Sundays, but in the eastern portion of the district less regard seems to be paid to inauspicious days.

There are four means by which goods are generally transported in Sylhet; the railway, the steamer, the country boat, and the

In Madhabpur thana the Tiyars are the only caste who will sell abything less than whole fishes.

cooly. The cooly seems an anachronism as a beast of burthen, for the district has for the last twenty years been possessed of several hundred miles of excellent unmetalled roads, but, though the roads are there, the people have not yet realised the utility of carts. The Assam-Bengal Railway enters pargana Kasimnagar in the southwest corner of the district at mile 135 from Chittagong. and leaves it at Badarpur at mile 253. It skirts the Raghunandan hills, crosses the low ranges of Satgaon and Balisira, passes, like the river Manu, between the Rajkandi and Ita hills, and runs near the western base of the Langla and Pathariya hills northwards to Karimganj. From this point it keeps fairly close to the left bank of the Kusiyara river till it reaches Badarpur, where the main line crosses the river, here known as the Barak, by a magnificent bridge, and turns north through the Assam Range into the Brahmaputra Valley. A branch line continues along the left bank of the river as far as Silchar. Work was begun on the railway in 1892 and the line was declared to be open for traffic as far as Silchar in The names of the stations going from west to 1899. east are Chandura at mile 137, Mantala at mile 142, Itakhola at mile 147, Shahji Bazar at mile 155, Saistaganj at mile 160, Daragaon at mile 166, Rasidpur at mile 168, Satgaon at mile 175, Srimangal at mile 179, Alinagar at mile 187, Shamshernagar at mile 191, Tilagoan at mile 197, Kulaura at mile 205, Juri at mile 212, Dakhinbhag at mile 216, Barlekha at mile 222, Latu at mile 229, Langai at mile 238, Karimganj at mile 239, Chargola at mile 243, Bhanga at mile 247, and Badarpur at mile 252. The railway passes near many of the tea gardens and carries

a considerable proportion of the tea crop of the district. The stations from which the largest quantities are booked are Srimangal, Shamshernagar, Langai, and Chargola.

It has already been explained that the principal river of the district is the Barak, with its two Navigable rivers. main branches—the Surma and the Kusiyara—the latter of which is again subdivided into the Bibiyana or Kalni and the Barak. The Kusiyara arm is the route by which through traffic goes up the Surma Valley from Calcutta to Silchar, but the extent to which this river can be used depends upon the season of the year and the amount of water in the channel. During the rains big steamers come up from Calcutta and call at the following stations: - Ajmiriganj, Markhali, Enathganj, Sherpur, Manumukh for Maulavi Bazar, Balagani, Fenchuganj, which is the company's headquarters in Sylhet, Nahair Ghat, Bairagi, Sheolamukh, Lakhi Bazar, Karimgani, Bhanga Bazar, and Badarpur. Small steamers run up the Surma from Markhali past Sunamganj and Chhatak to Sylhet town. In the cold weather, the big steamers go right up to Chhatak, but beyond that point there is not enough water in the Surma for steamer traffic during the dry season. Through traffic continues to go from Markhali to Silchar but small feeder steamers have to be employed. During the rains small steamers also run up the Manu to Chatlapur, up its tributary the Doloi to Kurma, and up the Langai from Karimganj to Langai Ghat.\*

These steamers are owned and managed by the India General Steam Navigation Co., whose managing agents are Mesers. Kilburn and Co., 4, Fairlie Place, Calcutta, and the Rivers Steam Navigation Co., whose agents are Mesers. McNeill and Co., 2-1, Clive Ghat Street, Calcutts.

In a district like Sylhet, where the fall is very slight and the current sluggish, it is inevitable that the rivers should silt up their beds. This process is apparently going on with greater rapidity in the Surma than the Kusiyara. In 1872, a large shool formed a little below Sylhet and for the next ten years the attention of the local authorities was directed towards the question of improving the through water communications of the district. The Deputy Commissioner, Mr. Luttman-Johnson, made two trips up the Surma in a small steamer, and after a careful examination came to the conclusion that the river to open out was the Kusiyara and not the Surma. The cost of clearing the latter stream would have been very heavy, and it was not the direct route for the through traffic to Cachar. \*

The greater part of the trade of the district is, however, carried not by steamer but by country Boat traffic. boat. During the rains the haors and channels are filled with water, and these lumbering vessels with their light draught are able to leave the regular rivers and take shorter and more expeditious routes across the country. From Lakhai they go straight to Habiganj and then turn north-east through the Gungijuri haor between the Barak and the Satgaon hills. At the northern end of this haor the traffic divides, and boats for Balaganj, the Manu, Karimganj, and Cachar, join the Barak just below Bahadurpur. From here to Balaganj the boats keep to the river, but between Balaganj and Karimganj there are numerous short cuts.

<sup>&</sup>quot; Vide Deputy Commissioner's General Administration Report for 1880-81.

Boats going towards Sylhet leave the Gungijuri haor at Nabiganj, and travel due north to Enathganj and Haripur Bazars. From there they go by the Itakhola and Babna rivers, past Biswanath Bazar and Lala Bazar to Tuker Bazar, where they enter the Surma a little below Sylhet. The down traffic keeps of course more close to the rivers to get the benefit of the current, but the up traffic not only has the advantage of the short cuts outlined above, but generally also has the wind behind it.

In addition to the various navigable rivers, details for which are given in the statement appended to this chapter, there are two important channels which connect or nearly connect the Surma and the Kusiyara. Except when the river is at its lowest, travellers from Cachar to Sylhet can avoid the Kanairghat loop of the Surma by proceeding down the Kusiyara to a place about fifteen miles below Karimganj, which is connected by a navigable channel with the Surma. During the rainy season, too, it is possible to boat from Fenchuganj via the Korkuchi khal, the Hailka Barna haor, the Khesab khal, the Basudeb khal, and the Tola khal to a point about two miles south of Sylhet town.

Under native rule there was not a single high road in Sylhet, and the district depended on its numerous waterways for the transport of internal trade, and for communication with the outside world. Mr. Lodge reported in 1794 that the only roads in the districts were those in Sylhet town, which had been made by his predecessor at his own

expense, and were kept in repair at Mr. Lodge's own. cost. Since that date the condition of affairs has been completely altered and the district is now well supplied with highways, though during the rainy season journeys are generally made by boat. At the present day there are 120 miles of road maintained by the Public Works Department, and nearly 1,200 miles of main and secondary roads kept up by the Local Boards, details for which are shown in the following statement:-

Name of Loc Board.	cal	Mileage of main roads.	Mileage of secondary roads.	Cold weather tracks, ~o.	Total.
North Sylbet	•••	143	35	238	416
Sunamganj	<b>50</b> -	29	16		45
Habiganj	•••	121	86	114	271
South Sylhet	***	155	118		273
Karimganj	•••	121	51		172
Total	<b></b> .	569	256	352	1,177

None of the main roads are metalled, but they are raised well above flood level, and as there is very little cart traffic, they are not much cut up even in the rainy season. The smaller rivers and streams are crossed by bridges, which are generally of a permanent or semi-permanent nature; though bamboo structures are still occasionally to be found and are always used on the cold weather roads. The larger rivers have to be crossed in ferry boats.

One of the principal thoroughfares is the road from Sylhet to Cachar which runs close to North Sylhet the left bank of the river Surma as far as Ramda, where it turns south to Karimgani and leaves the district at Badarpur forty miles from Sylhet. This is, however, a new alignment and the old road, which is still kept in repair, kept close to the bank of the Surma the whole way from Churkhai to the junction of that river with the Kusiyara. Both the old and the new road are fit for wheeled traffic throughout the year, and there are inspection bungalows at Golapganj, Ramda, and Sheolamukh at the 11th, 18th, and 23rd mile from Sylhet, and dak bungalows at Karimganj and Badarpur. Most of the bridges are of a permanent or semi-permanent character, but even in the dry season are four ferries to be crossed—over Surma at Sylhet, over the Kusiyara at Sheolamukh and Karimganj, and again over the Surma at Katagang. Westward this road is continued to Sunamgani, a It is fit for wheeled traffic distance of 41 miles. during the cold weather as far as Govindganj, but in the rainy season goods and passengers alike go by the Surma river and local pedestrians alone are likely to use the highway. Inspection bungalows are maintained along this section of the road at Govindganj, Pagla, and Kaitak, which are situated on the 14th, 22nd, and 30th mile from Sylhet respectively.

North of the town, a cart road runs 17 miles to Companyganj, crossing ferries at Salu-Other roads in North Sylhet. tiker, and at Companyganj where there is an inspection bungalow. Prior to the earthquake, a small railway ran from Companyganj to Therriaghat at the foot of the Khasi Hills; but this line was wrecked by that terrible convulsion of nature, and there is now only a bridle path which is hardly fit for use during the At this season of the year, travellers from Cherrapunji generally go by boat from Therriaghat to Chhatak, and thence by steamer to Sylhet. road runs north-west from Sylhet to Jaintiapur. As far as Haripur, where there is an inspection bungalow, 14 miles from Sylhet town, the road is drivable throughout the year, but here the level sinks, and for a length of about four miles the road goes under water in the The total distance to Jaintiapur, where there is an inspection bungalow, is 26 miles, and from here there is a bridle path through Jowai to Shillong, a distance of 64 miles. From Jaintiapur a road runs past Kanairghat. where there is an inspection bungalow, till it meets the old Cachar road 29 miles from Sylhet. The total length of this road is 21 miles, and, at the fifth mile from Jaintiapur, another road runs eastward to the boundary of the district at Natwanpur and connects with a bridle path from Silchar. A driving road also runs from Sylhet, a distance of 23 miles, to Sherpur steamer station, in the southwest corner of the sadr subdivision. It was intended that this road should be met by a road to be constructed from Habiganj by the Local Board of that subdivision, but only four miles of the projected road are as yet completed. There is an inspection bungalow at Tajpur, 15 miles from Sylhet, and also at Sherpur. Another inspection bungalow is situated at Dhakadakshin or Thakurbari, the home of Chaitanya's father, which is connected by a short branch road with the Sylhet-Cachar road at Golapganj.

A second main thoroughfare, 79 miles long, runs from Sylhet to Habiganj, through Fenchuganj, South Sylhet Kajaldhara, Srimangal, and There is a dak bungalow at Fenchugani, where the road crosses the Surma river, and inspection bungalows at Srimangal and Mirpur. The subdivisional headquarters station at Maulavi Bazar is connected with this highway by a road running past Rajnagar to Kajaldhara, and thence past Hingajiya thana to the old Faticoolie guard in the hills: and by two other roads to Shamshernagar and Srimangal, at both of which places there are stations on the Assam-Bengal Railway. These two roads are connected by a third which runs across the Balisira hills, and at Naraingani, on the Maulavi Bazar-Shamshernagar road, another road turns south to Adampur. There is an inspection bungalow on this road a little to the south of the point where it crosses the Sylhet-Habiganj thoroughfare. Various minor roads run from the Maulavi Bazar-Kajaldhara road to the tea gardens in the Ita hills. also runs from Maulavi Bazar to Manumukh steamer station on the Kusiyara river, where there is a dak bungalow. It is 91 miles long, but as the distance by river is very little longer, the latter route is generally preferred for journeys down stream.

important road in the Habigani sub-The most division is the one that runs from Habigani roads. Habiganj to the railway station at Saistaganj, the first section of which is part of the great semi-circular road from Habiganj to Sylhet. This road is continued from Saistaganj up the valley of the Khowai past Muchikandi, to Assampara 231 miles from Habigani, From Mirpur, which is situated on the Sylhet-Habigani road, a little to the east of Saistaganj, a road runs past that place, Shahji Bazar, and Jagadishpur to Chakerghat in the extreme south-west corner of the district. From Jagadishpur a road runs west to Madhabpur, and from Surma a road runs east which joins the Muchikandi road a little north of that place, but part of it goes over private land. Another important road runs from Shahji Bazar past Lalchand to Laskarpur garden; and there are roads from Habiganj to the steamer station at Madna on the Dhaleswari river, and northwards to Baniyachung, but the two last are only open for traffic in the winter. From Mirpur a road runs past the Satgaon hills to Putijuri. a distance of 8 miles. There is a dak bungalow at Habiganj, and inspection bungalows at Mirpur, Shahji Bazar, Jagadishpur, Putijuri, Saistaganj railway station, Madna, Chunarughat, and Baniyachung.

The only regular road in the Sunamganj subdivision is the one to which reference has been already made which connects it with Sylhet, but in the cold weather there are tracks to Dharmapasha and Mullapara, with inspection bungalows at Sachna on the former and Mullapara on the latter route.

Apart from the old and the new alignment of the Sylhet Cachar road, the principal roads Karimgani. in Karimgani are those to Hingajiya due south from and Oliviachara. The latter runs Karimganj up the valley of the Langai past Nilambazar to Patharkandi. Here it crosses the Pratapgarh hills into the valley of the Sonai, or Chargola valley, as it is generally called, up which it runs to Oliviachara, 41 miles from Karimganj. There are inspection bungalows at Nilambazar on the 10th mile, at Patharkandi 10 miles further on, and at Dullabchara on the 34th mile. There are ferries at the 1st, 3rd, and 34th miles, but the rest of the road is furnished with substantial bridges. At Fakirhat a little to the west of Karimganj, a road branches off from the Sylhet-Cachar road and runs along the west of the Pathariya and Langla hills, past Latu, Shabazpur, Barlekha, Dakhinbhag, Kulaura, and Hingajiya to Duttgram, which is situated at the point where the Tippera boundary and the Manu meet. There are inspection bungalows at Barlekha on the 15th mile, and at Kulaura in the South Sylhet subdivision. This road is connected with the Langai valley road by roads that run across the Pathariya hills from Barlekha to Patharkandi. distance of 134 miles and from Shabazpur to Nilambazar, a distance of 8 miles. A little to the south of Shabazpur, a road runs 5 miles west to Jaldhub, and thence 7 miles north to the Bairagi Bazar steamer station on the Kusiyara. All of these roads, with the exception of the sections already mentioned, are raised above flood level and are open to wheeled traffic throughout the year.

The following statement shows what an enormous development of postal business there has been since 1861:—

Number of Post Offices in 1908-04,	post o	r of lette ards o nds deliv	mitting	ings B	of Save ank ac- ats in	dit of	e at ore- the de- tors,
	1861-62	1870-71	1903-04	1871-72	1308-04	1871-72 Ks.	1908-04 148.
115	88	82	<b>2,3</b> 09	89	4,711	18,000	5,92,000

A list of post and telegraph offices will be found in the Appendix.

There is a considerable difference between the machinery of trade in Sylhet and in the Commerce & Trade : Brahmaputra Valley. The Assamese have no commercial aptitude, and almost the whole of the trade of their country has passed into the hands of natives of Rajputana or Ajmer-Merwara. These enterprising merchants buy up the products of the valley and the adjacent hills, and despatch them by steamer to Calcutta. and by the same route they obtain the salt, oil, piecegoods, and other commodities which they retail to the villager or garden cooly. Trade is centralized in the hands of a single community, many of whose members are possessed of considerable influence and wealth, and are substantial merchants and not mere petty shop-keepers. The trade of Sylhet has been to a great extent retained in the hands of the natives of the district, and its profits are more widely distributed than in Assam. Traders from Bengal come up the rivers in the rains, and buy direct from the cultivators, either at the bazars, which are generally situated on the river's bank, or in the villages themselves. There are of course merchants at the principal centres, many of whom amass considerable fortunes, but they do not carry on their operations on such an extensive scale as do their confréres in the Assam Valley. Their shops are small and mean in comparison with the large masonry buildings in the bazars of Gauhati and Dibrugarh, and they lean more to the retail than the wholesale side of commerce.

The trade of the district is carried on with Cachar, pirection of Trade. the Khasi Hills, Hill Tippera, and Bengal. No attempt is made to register the trade with the first two districts, and that with Cachar is probably not large. From the Khasi Hills come potatoes, oranges, limestone, pan, bay leaves and cotton, which are carried down by coolies, who return with rice, dried fish, and oil. But the great bulk of these imports from the Khasi Hills, merely pass through the district of Sylhet and their ultimate destination is Calcutta.

The principal bazars are situated at the foot of the hills at Mulagul, Jaintiapur, Jaflang, Lakhat, and Bholaganj. At the two latter places market dues are levied by the Khasi Siems of Cherra and Khyrim.

The population of the Surma Valley was slightly larger than that of the Brahmaputra Valley in 1901, but it contained only 525 natives of Rajputana and Ajmer-Merwara as compared with 8.681 in the northern valley.

Trade from Hill Tippera comes down the Langai, Singla, Juri, Manu,  $\mathbf{and}$ Khowai Trade with Hill Tippera. rivers, and is registered at Muchikandi in the Habiganj subdivision and at Nowakhali in South Sylhet.

The principal imports are timber, bamboos, and canes, raw cotton, and til. The state-Imports. ment in the margin shows the average annual value of each of these articles Bamboos during the three years ending with 1903-04. The chief exports are dried

Canes

fish worth some Rs. 20,000, cotton yarn and piece-goods. and tobacco, but the exports are small in comparison with the imports. This is only natural as Sylhet exports raw material and it is manufactured products that Hill Tippera The trade is to some extent hampered by the requires. heavy export duties charged by the Tippera authorities. Cleaned cotton has to pay as much as Rs. 4 per maund, til Rs. 1-6-0 per maund, and mustard As. 9 per maund. Duties are also levied on timber and other forest produce.

Sylhet exports to Bengal little but raw materials the principal exports consisting of un-Trade with Bengal. husked rice, tea, oil seeds, hides, bam. boos and mats; and lime, oranges, and potatoes which come in the first place from the Khasi Hills. The chief imports are cotton piece-goods, salt, tobacco, sugar, and The following statement shows the average weight of the principal imports and exports during the five years ending with March 31st, 1903.

Statement showing the Imports and Exports in maunds and numbers (thousands omitted).

Articles of import.		Average for 5 years ending Sist March 1903.	Articles of Export.		Average for a years ending 31st March 1903.
_		Md∎			Mds
Coal and coke	•••	219	Bamboos	No.	7,423
Docoanuta	No.	1,181	Coal and coke	•••	10 (a)
Gram and pulse	•••	189	Cotton	•••	11
Metals	•••	87	Hides and skins	•••	17
Oils	•••	211	Jute	•••	24
Potatoes	•••	35	Mats	•••	138
Rice not in the husk	•••	268	Oil seeds		106
Salt		284	Oranges	No.	15,474
Spices	•••	159	Provisions		´ 93
Sugar	•••	240	Rice in the husk		1,670
Fobacco	•••	89	Rice not in the husk		200
Flour	•••	30(b)	Spices		28
Piece goods	•••	42	Stone and lime		1,847
-		100,000	Wood	•••	11 (b)

(a) Figure for 1908.

(b) Average for 3 years.

Statistics of the weight of goods carried by railway and steamer are obtained from the companies concerned and can be accepted as correct. Boat traffic is registered at Bhairab Bazar, and it is only probable that the cargoes of boats that pass at night, or on days when the current is running strong and there is a fresh breeze blowing, are omitted from the registers. The recorded volume of trade is thus in all probability smaller than the actual quantity.

The great bulk of the trade is still carried by water, and in 1902-03 only 18 per cent. of the imports and 9 per cent. of the exports went by rail. A large proportion of the river borne trade is carried in country boats, which, though slow, are comparatively cheap. A

195

list of the principal rivers used for traffic is appended to this chapter.

The principal centres of trade in Sylhet are the district and subdivisional headquar-The district basars. Ajmiriganj, Balaganj, ters. Chhatak. Most of the business of the district is transacted at bazars which are generally situated on the banks of rivers. The villagers assemble at these places once or twice a week and exchange the products of their farms, and there are generally a few permanent shops which are kept open throughout the year. A list of these bazars will be found in Statement C. in the Appendix. Sylhet town, which is fairly typical of the larger centres, has two distinct bazars. The streets of the Bunder Bazar are not unlike some of the less important thoroughfares of Calcutta. There are rows of small mean shops in which the would be purchaser can obtain such things as piece-goods, clothes of all sorts and kinds, stationery, enamelled cups and saucers, hukkas, umbrellas, lamps, candles, buttons and general haberdashery, iron pots and pans, steel trunks, furniture of wood and wickerwork, and different sorts of bangles. There are in addition two or three shops which cater for the wants of the European community and a vendor of imported liquor. In the Kazi Bazar the staple articles of trade are various kinds of grain, vegetables, spices. tobacco, molasses, mats, pottery, and kerosine oil.

The district contains only two urban areas in which municipal law is in force, i.e., Sylhet and Habiganj. Sylhet was first

constituted a municipality under Act V. (B. C.) of 1876 in 1878. Act III. (B. C.) of 1884 was introduced in 1888. Habiganj was constituted a union under Act V. (B. C.) of 1876 in 1881.

The municipal committee of Sylhet consists of 15 members, of whom 10 are elected and 12 are non-officials, and they are presided over by a non-official chairman. The principal taxes imposed are (1) A tax on persons at the rate of 3 per cent. of the annual incomes of the assessees; (2) a tax on Government buildings at the rate of 71 per cent. of the annual value; and (3) a latrine tax at the rate of fifteen per cent. on the value of holdings ranging from Re. 1 to Rs. 12 in annual value, five per cent, for holdings with an annual value of between Rs. 13 and Rs. 100, four per cent. if the annual value is between Rs. 101 and Rs. 300, and three per cent. if it Sylbet is the largest town in the exceeds that sum. Province, but its income per head of population during the year 1902-03 was lower than that of any other urban area except Habiganj, Goalpara, and Barpeta. The incidence of taxation on persons was only As. 6-1 per head of population, a rate lower than that prevailing in any town in the Province except Habiganj, Nowgong, and Golaghat. The principal sources of income are the tax on persons and on Government buildings, the conservancy rate, and the tolls on ferries across the Surma, which are to a great extent paid by persons residing outside the municipality. The lowness of the assessment is not, it may be added, due to the want of objects upon which public funds might be suitably expended.

The affairs of Habiganj are managed by a Committee of five nominated members presided over by the Subdivisional Officer. The principal sources of income are pounds, ferries, a grant from the Local Board of Rs. 1,000, and a tax on persons. The latter item is practically the only portion of the public income that is drawn from the inhabitants of the union, and the incidence per head only amounts to As. 4-9. The people of Habiganj may thus look upon themselves as very lightly taxed. Details with regard to the principal items of expenditure and revenue in Sylhet and Habiganj in 1890-91 and 1900-01 will be found in Table XVI.

Sylhet town presents a rather mournful spectacle of general degeneration and decay. In Sylhet Town the days of Muhammadan rule it must have been a place of some importance, and Mr. John Willes reports that the population at the time of the permanent settlement was 75,382. At first sight it would appear that he must have been referring to a much larger area than the town itself, as his predecessor, Mr. Lindsay, characterised it as "an inconsiderable bazar or market place." On the other hand, in 1809 A. D., the Collector proposed to impose a tax on all houses in the kasbah or town of Sylhet, of which he said that there were supposed to be some 31,220, all of which were apparently situated on the land on which no revenue had been assess-In 1811, this assessment was imposed; it was found that there were 10,098 houses, but the total amount of the tax assessed was only Rs. 926-0. Considerable

opposition had been offered to the assessment, the householders had declined to supply the assessing officers with the information they required, and the shop-keepers had closed their shops. The assessment was, on the face of it, ridiculous. But the Collector did not seem disposed to press the point, and proposed, that as the tax had proved, as taxes always do, unpopular, and, as the demand was inconsiderable and out of all proportion to the cost of realisation, the matter might be dropped. In 1813. the Collector estimated the population of Sylhet town as 30,000 persons living within a circuit of two koss, i. e., The first regular census was taken in 1872 four miles. when the population was reported to be 16,846 souls. Since that date it has steadily declined, the figures being 1881, 14,407; 1891, 14,027; and 1901, 13,893, though in the latter year the total was swelled by the inclusion of some 500 workmen who were engaged in the reconstruction of the public buildings that had been demolished by the earthquake.

The town is situated on the north bank of the Surma, and, viewed from the river, seems to consist of two bazars, the Kazi and the Bunder, with an open space in the centre, in which are situated the public offices. The Deputy Commissioners' house stands on the west side of a large tank, near the site which was formerly occupied by the bungalow of Mr. Thackeray, the first Resident of Sylhet, and is confronted by a long row of spacious but somewhat mean looking cutcherries. The Bunder Bazar consists of rows of small shops, in which piece-goods, clothes, and general haberdashery can be procured.

In the Kazi Bazar most of the merchants deal in grain and food stuffs, and their transactions are on a somewhat larger scale. It is here that markets are held on Mondays and Fridays to which the villagers bring their produce for disposal. The residential portion of the town lies back from the river, and its most striking characteristic is the dense jungle of banboo in which the houses are almost invariably embedded. are numerous There roads, many of which are metalled and supplied with solid masonry bridges, but crumbling houses and deserted homesteads are evidence of a glory that has passed away. On every side are to be seen small mosques and the masonry ombs of dead Muhammadan samts, in whose horour lamps are still kindled at nightfall by the faithful. About a mile north of the river is the old polo ground, and the bells of arms which recall the time when a detachment of the Sylhet Light Infantry, whose headquarters were at Cherrapunji, was stationed in the town; while close by is the famous mosque of Shah Jalal. It is in this quarter that most of the houses of the European residents are situated. on low hills from which a fine view is obtained over the surrounding plains, and it is here that the Idgarh has been built, a large masonry platform surrounded by brick walls, on which service is held on the occasion of the Ids.

The public buildings include the courts and offices of the Deputy Commissioner, the Judge, the Sub-judges and the Munsifs, a large jail, the Murarichand second grade college which has been founded and endowed by Raja Girish Chandra Rai, a Government high school, eight other

schools for boys and two for girls, a church, a dispensary and leper asylum, a town hall, and a public library. There are fourteen masonry wells in the town, but most of the people take their water from the river or from small tanks in the compounds of their houses. No less than twenty-four miles of unmetalled and eight miles of metalled road are maintained by the municipality, and as, owing to the extremely light incidence of municipal taxation, the funds at their disposal are not large, many of them are not in very good repair. The roads in Sylhet are rendered beautiful by the groves of graceful bamboos with which they are shaded on either side; but, apart from this, the town has a somewhat unkempt and desolate appearance, and there are no signs of flourishing trade, prosperity, or wealth. This, however, is but natural. the days of Mughal rule it enjoyed the prestige which naturally attaches to the residence of a native official of some importance. It was the largest town on the frontier and was thus the centre of some trade. But with the opening up of Cachar and the development of the southern and eastern portion of the district, trade was naturally diverted to the more direct route along the Kusiyara. The process was accelerated by the gradual silting up of the bed of the Surma and the enormous expansion of the tea industry both in Cachar and later on in the southern portion of Sylhet, which stimulated the growth of places like Balaganj and Karimganj.

The town of Habiganj stands at the confluence of the

Barak and the Khowai in 24° 23' N. and

91° 26' E. Like most of the villages
in this inundated tract it is built on the banks of the

rivers, which are raised a little above the level of the surrounding country. The public buildings and the residential quarter are situated on the left bank of the Khowai, but the most populous and wealthiest portion of the bazar is situated on the left bank of the Barak. There is a considerable trade, most of which goes by country boat. The principal imports are grain and pulse, cotton piece goods, kerosine and other oils, and salt. The chief exports are unhusked rice, jute, mustard, linseed, and hides. The majority of the merchants are natives of the district and members of the Shaha caste. The population of the town in 1901 was 5,236.

Sunamganj is a small town with only 3,530 inhabitants on the left bank of the Surma.

During the rains the whole of the country in the neighbourhood is submerged, and there is a fine view across this waste of waters to the Khasi Hills. The town practically consists of a single road along the river bank, and is altogether a most unprepossessing place.

Maulavi Bazar, the headquarters of the South Sylhet subdivision, has a population of 2,481 persons. It consists of a small bazar on the left bank of the Manu. About a mile to the south, the subdivisional officer's bungalow and court and the subdivisional jail stand upon the northern slopes of the Balisira Hills, a tract of elevated rolling country which rises a few hundred feet above the level of the plain.

Karimganj, the capital of the subdivision of that name, stands on the left bank of the Kusiyara river, in 24° 52′ N. and 92° 2′ E. There is a small bazar near the water's edge, but the place is favourably situated for the purposes of trade as, in addition to the facilities which it enjoys for water transport, the railway passes only a mile away to the south. The public offices and the bungalow of the Subdivisional Officer have been built on the summit of low hills; and command a fine view of the blue ranges of North Cachar. The population of Karimganj in 1901 was 5,692.

There are other places which, though not worthy of the name of town, are still of sufficient importance to merit special mention. Ajmiriganj is situated in 24° 33′ N. and 91° 15′ E. on the banks of the Surma river, and in 1901 had a population of 583 persons. It is an important centre of trade, the chief exports being rice, dried fish, bamboos, and mats, and the imports, grain, oil, salt, tobacco, sugar, and piece-goods. Trade is carried on largely by country boat, though the village is a place of call for steamers.

Balaganj is situated in 24° 39' N. and 91° 50' E., on

a narrow spit of land between the
Kusiyara and the Barbhanga rivers.

It is little more than a mud bank, and is not even
connected by road with any other place, but it is admirably
situated for the purposes of water communication and
is now the most important centre of trade in the Surma

Valley, with a large business in rice, mustard, linseed, jute, oil, sitalpati mats, and salt. The village is a place of call for river steamers, and a European firm has opened a warehouse for the sale of salt and oil.

Baniyachung is stuated in 24° 31' N. and 91° 21' E.

Baniyachung.

It is the largest village in the Province, and in 1901 had a population of 28,883. It is said to have been founded in the first half of the 18th century by Abid Reza, the first of the converted Hindu Rajas of Laur, who submitted to pay tribute to the Mughals. The village contains a mosque of great local repute, a dispensary, a high school, two bazars, and about two hundred shops. It is surrounded by a most and the houses are closely packed together on islets of high land separated from one another by marshy ground and watercourses.

Chhatak is situated in 25° 2' N. and 91° 40' E., on the left bank of the Surma river. The river is navigable by steamers up to this point all the year round, and there is a large export trade to Bengal in lime, potatoes, and oranges. A tall and massive masonry obelisk, erected in memory of Mr. Inglis, who founded a large business in lime, stands on the summit of a low hill, from which a magnificent view is obtained over river, swamp, and forest to the blue line of the Khasi Hills, which rise like a wall from the plains.\* This obelisk was cracked in three places by the carthquake of 1897, and the pieces were wrenched round in

An account of the Inglis family will be found in the Gazetteer of the Khasi Hills.

the same plane without being thrown down. The village is built along the left bank of the Surma, as in Sylhet the banks of the rivers are the highest part of the country.

In 1872, the management of the district roads was entrusted to a committee presided Local Boards. over by the Deputy Commissioner. The funds at their disposal were partly obtained from tolls and ferries on local roads and other miscellaneous sources, but principally from grants made by the Bengal Government from the amalgamated district road fund. 1874, when Assam was erected into a separate Administration, the Government of India assigned one-seventeenth of the net land revenue for local purposes. The district improvement fund was then started, and the administration of its resources was, as before, entrusted to the Deputy Commissioner assisted by a committee. The actual amount placed at their disposal was not large, and, in 1875-76, the total income of the district funds of the Province was only Rs. 1,85,000, which was a small sum in comparison with the twelve and a half lakhs of rupees received by the In 1879, a Regulation was Local Boards in 1903-04. passed, providing for the levy of a local rate, and the appointment of a committee in each district to control the expenditure on roads, primary education, and the. district post. Three years later the district committees were abolished by executive order, and their place was taken by boards established in each subdivision, which are the local authorities in existence at the present day.

The Deputy Commissioner is chairman of the board of the headquarters subdivision, but Functions of Boards. each of the other boards in the district is presided over by the Subdivisional Officer. Local Boards are entrusted with the maintenance of all roads within their jurisdiction, except a few main lines of traffic which have been retained under the direct management of the Public Works Department, with the provision and maintenance of local staging bungalows and dispensaries, and with the supervision of village sanitation, vaccination, and the district post. They are also in charge of primary education, subject to the general control of the Education Department, and are empowered to make grants-in-aid to schools of higher grade, subject to certain rules. For these purposes, they have placed at their disposal the rate which is levied under the Assam Local Rates Regulation of 1879, at the rate of one anna per rupee on the annual value of lands, as well as the surplus income of pounds and ferries, and some minor receipts. This income is supplemented by an annual grant from Provincial Funds. principal heads of income and expenditure are shown in Table XV.

The annual budgets of the boards are submitted to the Commissioner for sanction. The estimates for all works costing Rs. 500 or over must be submitted to the Public Works Department for approval, and important works, requiring much professional skill, are made over for execution to that department. Less important works are entrusted to the Board surveyors.

The roads of Sylhet are of comparatively recent origin, and the great majority of them have been constructed by the various Local Boards. In South Sylhet the local authority has provided funds for the construction of 173 miles of road and 28 permanent bridges. In Karimganj 121 miles of road have been completed. The Habiganj Board, in addition to making many miles of road, has paid for 30 permanent and 22 semi-permanent bridges. The expression "paid for" is used advisedly, as, when the work presents any special engineering difficulties, it is generally entrusted to the Public Works Department for execution.

सन्धमेव जयन

List of Navigable rivers in Sylhet.

a x x x	NAME OF RITER.				COURSE.	88E.			Highest point which can be resched by boat of 4 tons barthen.	nich 4 to	can be resched ns barthen.
	<b>.</b>			From			To		In the cold weather.	<u>.</u>	In the rains.
	NOBTH SYLH ET SUBDIVISION.	<u>;</u>	SUBDIVIE	SION.			4	<u> </u>			
Awirdin	:	Barak	arak	सह		Itakhola at	Itakhola at Mandaruka		Not navigable	:	Throughout the
Babna	:	<u> </u>	Babia	गमेव		Itakhola		:	Do.	:	Do.
Bahia	:		Surma at Tukerbazar	Tukerbaz	аг	Babna at Biswanath	Sigwanath	:	Do.	:	Do.
Barbhanga	:	<u>a</u>	arak at M	loghal B	8Zar	Barak at Moghul Bazar Kusiyara at Balaganj	t Balaganj	ŧ	Do	:	Do.
Betua	:	ğ :	Bahia	:	:	Tolakhal	:	:	Do	:	Do.
Charchandi		<u> </u>	Ballis at Biswansth	iewanat		Jamai Kata haor	s haor	:	Do.	•	ъ.
Chengar Khal		<u> </u>	Goysin	:	:	Surma at Kalaruka	salaruka	:	Up to Goyainghat	#	Do.
Goyain	:	<u> </u>	Hill at Jaflang	lang	:	Chengarkh	l at Goyaing	la t	Chengarkhul at Goyainghat Not navigable		Ъо.
Juri	:	<u> </u>	Dharamnagar hills	gar hills	:	Kusiyara в	t Fenchugan		Kusiyara at Fenchuganj Up to Ghilachara		Batire leagth.
Kappa	:		Kusi	:	i	Jalu		•	Not navigable	:	Do.

~
7
- 5
ತ
-contd.
تب
Q)
2
=
<b>&gt;</b>
ΖĎ
•
in Svihet.
-
rivers
Ħ
Ō
▻
媡
m
~
٥
╦
٣.
ᅋ
Ξ
5
ᄧ
7:
of Mavigable
7
0
List
÷
-

NAME	NAME OF RIVER.		Сод	Соцвяе.		Highest point which can be reached by boat of 4 tons burthen.	le can be reached one burthen.
			From	To		In the cold weather.	In the rains.
Ň	North Sylber Subdivision.—could.	S UBDIVISIOR.	-contd.				
Katagang	:	Kusiyara	6	Surma	:	Entire length	Entire length.
Kusi	•	Kapua	र्धर सद्य	Do.	į	Not asvigable	Do.
Line	:	Khasi Ilills	मेव मेव	Shair	:	Do.	Do.
Peein	:	Do.	) (/ जयत	Surma near Chlatak	:	Up to Lakhat Ba	Do.
Shair	:	Line		Chengarkhal at Goyainghat, Not navigable	glat	Not navigable	Do.
	SUNAMGAN	SUNAMGANJ SUBDIVISION.				W-	
Chamti	:	Makaeingh Nagdipur	river	near Bheramuna	:	Up to Habibpur	Do.
Dakua		Ra	:	Kamarkhali	:	Up to Rasulganj	Do.
Itakhola	:	Junction of Amirdia	ction of the Babnaand Awirdin at Mandaruka	Junction of the Babnaand Kusiyara near Katia	:	Up to Sibganj	Do.

## CHAP. VI.] ECONOMIC CONDITION OF THE PEOPLE. 209

Jadukata	:	Khasi Hills	:	Raktee	Not navigable Up to Panatirtha Bazar.	Up to Panatirtha Bazar.
Khasimara	:	Do.	•	Surma nest Dwara Bazar	Do	Throughout the whole length up to the foot of the hills.
Kabasingt	•	Dekar haor	:	Kamarkhal	Opto village Hason-pur situated on the southern side of Dekar harr	Entire length.
Mahisukhola	:	Khasi Hille		Someswari river near Madhyanagar	near Up to Ghilachuka	Up to Mahish khola Bazar.
Mara Surma	:	Surme near Nagadia	village	Bheramuna Ajwiriganj B	opposite Up to Rajanager	Estire length.
Painda	<b>i</b>	Surms at Painds forry Dhann river	rry	Dhanu river	Eatire leagth	, Do.
Piyain		Klasi Hills	i	Dhanu river in the My. Up to Bhatipara mensingh district	Up to Bhatipara	Up to the foot of the Laur hills.
	HABIGAN	HABIGANY SUBDIVISION.				
Balikhal	:	Barak	•	Ratna near Balakipur	Entire length	Entire length.
Bijna	•	Gopla	i	Barak near Tongirghat	Do.	Do.
Gopla	i	Hill Tippera	:	Barak near Jalalshap	Cp to Matiganj	Up to the foot of the bills.

neld
5
7100
in Sylvet—concid
Kivers
t of navigable
nav
t of
List

	I		List of navigable	List of navigable Rivers in Sylhet—concid.	t—concid.	
NAWB	0F E	NAME OF BIVER.	10O	Course.	Highest point which can be reached by boat of 4 tons burthen.	b can be reached one burthen.
			From	To	in the cold weather.	In the rains.
		Habigany	Habigani Subdivision-concld.			
Gungijuri	:	•	Gopla near Tarapasha Bijna at Noakhal	Bijns at Noskhal	Entire length	Entire length.
Karangi	:	:	Hill Tippera	Barak vid Noakhal	Not navigable	Do.
Khowsi	:	•	 Q.	Barak near Habiganj	Op to Mashajan Op to Ballabazar at the foot of the bille.	Up to Ballabazar at the foot of the hills.
Ratos	ŧ	:	Barek voar Ujirpur	Barak near Bajuka	From Barak to From Barak to Balikhal Khagaura.	From Barak to Khagaura.
Sonai	•		Bill Tippera	Titash	Not navigable Upwards to Man- tale and some d is tance beyond.	Upwards to Man- tala and some d is t a n c e beyond.
Sutang	:	:	Do.	Dhaleswari near Lakhai From Dhaleswari Up to the village to Nosgaon Lalchand.	From Dhaleswari	Up to the village Lalchand.

	Soura Srlers	SOUTH STLUTT SUBDIVISION.				
Dholai	:	Hil Tippera	Manu river near Chaudhury Not navigable Bazar	Not navigable ,	Entire to the bi	Entire length up to the foot of the hills.
Mana	:	Do.	Kusiyara at Manumukh	ρο.	<u>а</u> :	Do.
	KABIMOANI	Karimgani Burdivision,				
Kachua	:	Son bil	Kueiyara	Do	Up to Son bil.	Jon bil.
Langai •	:	Hills to the south of the Eskeluki have Sylbet district	Hakaluki haor	Not navigable	Op to ]	Up to Hatikhira.
Singla	:	Lushai Hills	Son bil	Do.	Up to	Up to Dullabh.
		1 3	2007 E 2007	•		
		यने				
		0				
•	In the rains it is	<ul> <li>In the rains it is connected with the Kusiyara by the Natia Khal.</li> </ul>	a by the Natia Ehal.			

## CHAPTER VII.

## GENERAL ADMINISTRATION.

Land Revenue—Early Settlements—The Permanent Settlement—The Hill Tracts—Temporarily settled estates—Disforestation—The Jaintia Parganas—Toa Land—Land revenue collection—Excise—Income-tax—Stamps—Public Works—Government—Administrative subdivisions—Criminal and Civil Justice—Registration—Police—Chaukidars—Volunteering—Jails—Education—Medical—Leper Asylum—Surveys.

For the purposes of land revenue administration the district is divided into two distinct Land Revenue. areas. Sylhet proper came into the possession of the Company when they acquired the diwani of Bengal in 1765, and a considerable portion of it was included in the permanent settlement; whereas the Jaintia Parganas were not annexed till 1835, and, like the rest of the Province, are temporarily settled.\* Sylhet proper, again, is not a homogeneous tract, but scattered over the permanently settled area there are a large number of estates which were occupied and settled at various dates subsequent to the permanent settlement: while in the south of the district there were extensive tracts of jungle to which claims of a somewhat vague and dubious character were put forward by the neighbouring land-holders.

The whole history of the land revenue system of Sylhet is thus of a very complicated character, and cannot be adequately dealt with in the pages of a District Gazetteer. A more detailed account of the subject will

<sup>•</sup> Even in the Jaintia Parganas there are, however, 33 permenently settled estates.

be found in the Introduction to the Assam Land Revenue Manual, by Sir W. E. Ward, K. C. S. I., pages CXIII—CLVIII.

The earliest settlement of Sylhet proper was that made by Tudar Mall in 1582, and he Early Settlements. is said to have assessed the revenue at Rs. 1,67,040.\* This would, however, have been a rather heavy assessment in comparison with the demand of later years, and it is not probable that the whole of this amount was ever credited in the Imperial Treasury. In 1728, the land revenue actually paid to Government is said to have amounted to Rs. 70,076, and in 1787 Mr. Lindsay reported that it had never exceeded Rs. 1,25,000. In 1776, Mr. Holland assessed the district at about Rs. 2,00,000, and six years later it was farmed out at Rs. 2,50,000, but this amount could never be collected. A few years later Mr. Lindsay concluded his settlement for Rs. 1,87,500.†

Up to this time, the settlements seem to have been of

a very tentative and temporary character, but in 1788 a step was taken
which was destined to leave a permanent mark upon the
district. In the cold weather of 1788-89 the Collector, Mr.
Willes, commenced his measurements and settlements, and
in August 1789 he reported that the work had been completed. He did not, as in most of the other districts of

<sup>•</sup> Principal Heads of the History and Statistics of the Dacca Division page 292.

<sup>†</sup> The revenue was actually assessed and paid in cowries, and in converting it into rupees four kahons of cowries have been taken to be equal to one rupee, but the rate of exchange varied considerably at different times.

Bengal, enter into engagements with the chaudris or land revenue collectors, but settlement was as a rule made direct with the actual cultivators of the soil. The total area covered by his operations was 2,100 square miles, and the character of a detailed settlement, which was carried out over such an extensive area in a single working season. can better be imagined than described. His work must. however, have been so frequently anathematised by his successors, that it is only fair to add that Mr. Willes was not a willing agent in the matter. He wrote somewhat plaintively on the subject to Government in 1790, and it is only fair that he should be heard in his own defence-" I shall first observe that the hastabud of the district did not originate with me.....had I consulted my own ease in preference to my duty I might have stated many plausible objections.....as soon as the rains would admit I entered on the disagreeable task, and in the execution of it I have received every possible opposition from the Kanungoes and other Mussalman inhabitants.....vet. gentlemen, I shall ever conceive it peculiarly unlucky that I should have been so unremittingly employed for a year on an object of so little import to Government, that any credit I might otherwise have obtained is lost in its insignificancy."

Mr. Willes did not, moreover, anticipate that this extremely perfunctory settlement would be accepted as a

<sup>•</sup> Letter No. 119, dated 24-2-1790. The concluding paragraph recalls a similar complaint made by Col. Hopkinson, Commissioner of Assam, who in 1872, after carrying out the re-settlement of the valley, remarked in a letter to the Government of Bengai "I sometimes wonder whether it has often happened to an officer to have taken so large a part in proposing and realizing a measure fraught with such solid advantages to the state as that scheme secured, and to have obtained such scant thanks for it."

permanent engagement between Government and its tenants. Most settlements were at that time for comparatively short periods, and the Collector probably regarded the one carried out under his direction as a temporary makeshift.

He was fully conscious of the imperfections of his work, and for fear lest it might give rise to permanent and serious inconvenience, he caused most of the original documents to be destroyed. The only records in the Collector's office which bear Mr. Willes' signature are the daul and talukwari registers. The other papers bearing on the settlement were produced by the pargana patwaris in 1802, and are either duplicates prepared at the time of settlement, or unauthenticated copies of those duplicates, or possibly, for all we know, the creations of the patwaris' fancy. The chittas purport to show the boundary of each estate, but these boundaries are often of a vague and useless character, and some of the estates are simply said to be bounded by "hills" or "jungle."\*

It soon became clear that there were extensive tracts of land which had never come within the purview of Mr. Willes' perfunctory operations, and in 1802 the Collector, under the orders of the Board of Revenue, directed the patwaris to furnish statements of these unsettled lands.

A list of the records of the decennial settlement in the Sylhet Collectorate will be found in Deputy Commissioner's letter No. 4097, dated 27th August, 1879.

On receipt of these lists, notices (ilams) were issued calling on claimants and objectors to come forward. Board then ordered the Collector to grant leases the lands reported in the lists of the patwaris, and for other land found outside the boundaries of the permanently settled tract. These leases were issued between 1801 and 1807, and, though the term of settlement was not fixed, it was decided in 1869 to treat these lands as permanently settled. The lists of the patwaris were, however, very incomplete, and subsequent surveys have shown that the district contained nearly a million acres of land, in addition to the estates which had been surveyed and settled.\* 1817, the question of the settlement of these excess lands was again raised, and in 1834 it was decided that excess land, which had been included in the patwaris' ilam returns, and to which the rights of Government were undisputed. might be assessed. With regard to the remainder, it was decided in 1840 that they were not worth the trouble and expense of settlement.

Between 1859 and 1865, Sylhet came under the operations of the revenue survey, which is generally known as the takbast, as proprietors were then required to demarcate their estates with taks or marks.

This survey is of such importance that it is only right that the objects aimed at, and the methods by which it was hoped that they would be attained should be described in some detail. The following account is taken

<sup>•</sup> The calculation will be found on page CXXX of the introduction to the Assam Land Revenue Manual, Calcutta, 1896.

from a note recorded by the Director of Land Records and Agriculture, Assam, in 1892. The chief design of the survey of a district was to ascertain the position boundaries, and area of every village and estate in that district. In order to ascertain this, two parties went into the field, viz. (1) an unprofessional party under a special officer called the Superintendent of Survey aided by Deputy Collectors and an establishment of peshkars and amins, and (2) the professional party. The work assigned to the unprofessional party consisted in demarcating the boundaries of villages and estates, and settling bounary disputes, and the demarcation was required to be made a whole season in advance of the survey of the district to be undertaken by the professional party.

Before proceeding to demarcate the villages and estates of the district, the Superintendent of Survey received from the Collector lists of all such villages and estates in the district. These lists having been distributed among the several amins, to whom the work of demarcation was immediately entrusted, the amins proceeded to call upon the zamindars, raiyats, and other occupants of land to point out their boundaries, and, on the boundaries being pointed out, in all cases where the estates or villages given in the Collector's list could be traced, they were demarcated on the ground by taks or marks.

In carrying out the work of demarcation, the unprofessional party first laid down the village boundaries, and after that the position and boundaries of all estates having any lands in that village. They also prepared what are known as "takbast maps," most of which were on the

scale of 16 inches to the mile, which showed the boundaries not only of the village but also of every estate or portion of an estate included in it. The estates or portions of estates entitled to separate demarcation and entry in these maps are specified in sub-section 12 of section II, Chapter XXIII of the Board's Rules of 1866.

When a sufficient number of contiguous villages. with the estates or portions of estates contained in each village, had been demarcated, a mujmili or sketch map was prepared containing 80 to 100 square miles of country, and showing the names and relative positions of the villages which had been demarcated. The professional revenue surveyor then went to work, being guided entirely by the taks laid down by the upprofessional amins. however, confined himself solely to the external boundaries of villages. He had nothing to do with the internal details of villages, i.e., the boundaries of estates or portions of estates beyond calculating the areas of those estates which the Superintendent of Survey sent him for triangulation. The professional maps, therefore, are village maps, showing geographical and topographical features.

The survey was never confirmed as required by section

Takbast survey

4 of Act IX of 1847, and its accuracy

brings out great
increases in permanently settled area. has more than once been called in

question. A test survey was accordingly carried out
in 1881-1882, and the conclusion come to was that
the original revenue survey, judged as a survey,
was probably as accurate as such surveys usually are, but
that the boundaries pointed out were in many cases

wrong. The unprofessional party seem to have accepted without question or demar the boundaries pointed out by the proprietors, and it is hardly matter for surprise that there was found to be a large increase in permanently settled area. These estates in Mr. Willes' day covered an area of 1,685,000 acres; but, on the completion of the takbast, the area was found to be 2,231,000 acres. In individual cases the increase was sometimes quite enormous, two of the most flagrant instances being Nos. 64/47070 Faiz Muhammed and 73/47079 Makanullah, in mauza Srichandanjum pargana Bhanugach. At the permanent settlement neither of these estates covered as much as three roods of land; the takbast allowed each of them 4,725 acres. At the same time, in the absence of any better record, the takbast maps are often accepted by the Civil Courts as evidence of boundaries, possession, and title.

In 1902-03, the permanently settled area in Sylhet

was said to amount to 2,411,081 acres,
classified under the following heads:—

- (a) Dassana, i.e., estates included in the decennial settlement, which became permanent in 1793.
- (b) Bazyafti daimi, i.e., invalid lakhiraj lands, resumed by the Special Commissioner appointed under Regulation III of 1828, and then permanently settled.
- (c) Ilam daimi, i.e., ilam lands permanently settled.
- (d) Khas daimi, i.e., permanently settled estates purchased by Government at sales for

- arrears of revenue, and sold again as permanently settled.
- (e) Halabadi, i.e., land which was not included in the decennial settlement, but which was settled without specifying the term of settlement, and was afterwards declared by Government in 1869 to be permanently settled.
- (f) Khas halabadi, i.e., estates belonging to class (e), which, on being bought in by Government at sales for arrears of revenue, were subsequently permanently settled.
- (g) Permanently settled waste land grants.—The proprietors of three halabadi estates, paying a revenue of Rs. 9-5-3, claimed a large tract in the Raghunandan hills. Their claims were compromised by the grant in perpetuity of two estates, covering an area of 1,659 acres and paying a revenue of Rs. 9-6-0.
- (h) Izad daimi, i.e., excess lands discovered after Mr. Willes' settlement, and then settled permanently.
- (i) Haor mahal.—Marshy land excluded from Mr. Willes' settlement and subsequently permanently settled.

Mr. Willes' system of settling direct with the cultivators had the natural result of creating an enormous number of separate holdings, from each of which a distinct and separate payment was required. According to Sir William Hunter, there were, in 1793, 26,393 estates on the rent

roll held by 29,317 separate proprietors.\* This in itself was bad enough, but by 1865 the number of permanently settled mahals had doubled, yet only one-fifth of them paid a revenue of five rupees or more. 22,000, or nearly one-half, paid a revenue of one rupee or less, the average demand on account of each estate being about 6½ annas, while another 14,000 estates paid between two and three rupees.

It is hardly necessary to point out that the trouble

Little advantage taken of concession authorising permanent redemption of the revenue assessed on small estates. of collection from such an enormous body of land-holders is out of all proportion to the amount of revenue received. In 1865, the Board of

Revenue invited attention to the fact that no less than 437 peons had till recently been employed at sadr, and 71 persons, patwaris and others, in the mofussil, whose principal duty had been the collection of the revenues.† Such an establishment was not only a source of considerable expenditure to Government, but was a cause of harassment to the people, and it was proposed that proprietors of estates paying not more than one rupee should be allowed to permanently redeem their land revenue at twenty years' purchase. This proposal was sanctioned by the Government of Bengal,‡ but, strange to say, comparatively little advantage was taken of the concession.

In a country like India where the rate of interest is so high, it would not of course pay any one from the

<sup>■</sup> A Statistical Account of Assam, Vol. II., p. 316.

<sup>+</sup> Letter No. 370-A., dated 23rd November 1865.

<sup>1</sup> Letter No. 2720, dated 8th July 1867.

strictly pecuniary point of view to redeem a fixed payment at twenty years' purchase, but the sums in question were so small that it was obviously to the interest of the proprietors to free themselves from the necessity of these petty annual payments, even at something above the strict market price. Possibly the orders were not generally known, or obstacles may have been thrown in the way of the people by the Collectorate staff, but, for some reason or another, only 2,414 estates had been redeemed at the time when the permission was withdrawn in 1880. For a time, also, a rule was in force under which the purchaser of a permanently settled estate sold at auction was compelled to redeem the revenue at twenty-five years' purchase, if it was not more than one rupee, but the number of estates redeemed under these orders was comparatively small. This concession was not, moreover, restricted to the permanently settled estates, but under Rule XI of the Ilam Rules of 1876, the revenue on temporarily settled estates could be redeemed at twenty-five years' purchase, provided that it was not more than one rupee per annum.

The ranges which project from the Tippera Hills into the Sylhet plain have The hill treets. fruitful source of litigation Government and the zamindars. The names of these ranges and their estimated area is shown in the statement Ranges Area. aq. miles in the margin, the order given being 61 108 115 Raghunandan that from west to east. At the time of Batgaon Balisira Bhanugach and Ita .. 58+50 the permanent settlement these hills Langla 47 859 118 Pathariya were for the most part covered with Pratapuarh Biddheswar forest, bamboos, and scrub, in which the

Tipperas would clear a patch of land, cultivate it for a few years, and then move on leaving their fields to relapse once more into the jungle from which they had originally been evolved. Certain rights of commonage are also said to have been enjoyed by the owners of the estates lying near the foot of the hills. These rights, which are known as jhum, a term which presumably implied the right to practise shifting cultivation in the hills, or possibly to tax plains men so practising it: tippera, or the right to levy a tax on Tippera villages; and qurkati, or the right to take or tax forest produce, are sometimes mentioned in the early records found in the collectorate as appertaining to certain permanently settled estates, and as having been assets which were taken into account when the revenue was orginally fixed. There is also a fourth easement known as panisikka, but the very meaning of this term is lost, and, apart from the vexed question of the actual locality in which this right was to be exercised, no one at the present day has the very least idea what the privileges were which it conferred.

When it was found that the hill ranges possessed a special value of their own, in that they were excellently adapted for the cultivation of the tea plant, claims were, from time to time, put forward, to hold the land over which these easements had been assigned, as an integral part of a permanently settled estate. One of the most important of these claims is one which is known as the Balisira case, and which arose out of the action of the Maharaja of Hill Tippera, who, in 1882, entered into an agreement to lease 30,000 acres of land in the Balisira hills to-

Messrs. Finlay, Muir & Co. The Maharaja was the proprietor of certain permanently settled estates in the Balisira pargana, to which these curious easement rights attached; but there were 75 other estates in the same pargana which were in much the same condition, and Government denied that either the Maharaja or any other person was entitled to proprietary rights in the Balisira hills. In 1886, Government brought a civil suit against the Maharaja to establish their title to the 30,000 acres which formed the subject-matter of the suit; but the case was never tried, and, in 1897, the matter was finally compromised, and the Maharaja withdrew his claims to ownership.

Difficulty was also experienced in giving leases to tea planters for land over which The question of easements settled by Jhum Regula-tion. other persons exercised vague rights of commonage. A Regulation, known as the Jhum Regulation, was accordingly passed in 1891, extinguishing these claims, but providing for the payment of compensation to any persons who could show that they had legally exercised these rights within the twelve years preceding the passing of the Regulation. This measure in no way affected the interests of persons who could show that any portion of the hills had been actually included within the limits of their permanently settled estates, but the High Court have distinctly laid down that the possession of these easements is not in itself evidence that land over which they were to be exercised was permanently settled with the easement holders.\*

Maulavi Muhammed Ali Amjad Khan v Secretary of State for India.

The temporarily settled estates are divided into the remporarily settled following classes:—

- (1) Ilam.—This is by far the largest class. A history of the ilam settlements is given in the following paragraphs.
- (2) Nankar patwarigiri, i.e., land formerly held free of revenue by the pargana patwaris as nankar, i.e., in lieu of salary. The patwaris were abolished in 1838 and the lands brought under assessment.
- (3) Charbharat, i.e., alluvial accretions.—These, in Sylhet, are liable to assessment, but settlement must be offered to the owner of the property to which the lands are an accretion.
- (4) Bilbharat, i.e., silted up beds of bils which were excluded from the permanent settlement because they were then useless.
- (5) Izad, i.e., surplus lands discovered after the permanent settlement (but not formally proclaimed as the *ilam* lands were), and thus not included in it.
- (6) Revenue free land resumed because found to be held on invalid titles.
- (7) Khas, i.e., permanently settled estates bought in by Government at sales for arrears of revenue and settled temporarily direct with the cultivators.

Theoretically the ilam estates are the lands which were included in the patwaris' returns Ilam lands, Mesn-ing of term and settlements. in 1802, but were not settled under halabadi pattas prior to 1807. They are scattered all over the district, and in some parganas there are only two or three, and in many less than one hundred bighas of cultivated ilam land. Some of the estates consist of a small tank, or a few yards of cow path embedded in the middle of a permanently settled tract, and there are no less than 365 separate plots of ilam land embedded in permanently settled estates which have an area of The ilam lands were first measured less than five acres. up between 1829 and 1834, the total area reported being 229,950 acres. The first settlement was made in 1836 and was for ten years. All cultivated land was settled with the actual occupant, and on the expiry of the lease it was renewed at the same rates of revenue.

In 1871, steps were taken to effect a settlement in a more regular and detailed manner, and llam settlement of 1871. definite rules were laid down in 1876 for the guidance of the officers concerned. Cultivated and culturable uncultivated land were to be assessed at moderate rates, with reference to the rents paid by cultivators for similar land in the neighbourhood. From this assessment 15 per cent. was to be ducted, for expenses and risks of collection, and the remainder was taken to represent the Government uncultivated land in excess of revenue. Culturable one-fifth of the cultivated area was ordinarily to be excluded from settlement; but this provision was not enforced in the case of tea planters who had purchased

ilam leases, as it was recognised that a large proportion of a tea estate must of necessity remain uncropped. They were, however, required to pay revenue on all land under cultivation at the time of resettlement, and for waste equal to one-fifth of the cultivated area, at the same rates as those paid by cultivators for similar lands in the immediate neighbourhood. On the remaining waste the rates laid down in the 30 years lease rules of 1876 were imposed. Leases granted on these terms are described as leases issued under the modified ilam rules 1878, but all of them have now expired.

The classification adopted at the settlement begun in 1871 was needlessly elaborate. Cultivated land was divided into fourteen classes and uncultivated land into ten. There were for instance separate classes for homestead, for land adjoining the homestead on which bamboos were grown, for land on which betel or pan was grown, and for orchards or gardens. The maximum rates were actually as high as Rs. 8-4 an acre for sugarcane, and, whereas at the former settlement the average rate per acre of cultivated land was 11 annas 2 pie, it was now raised to nearly Rs. 1-12. total area settled under the ilam and modified ilam rules. the janualburi \* and other similar rules, and the waste land rules of 1876, was 144,185 acres, of which 21,802 acres were cultivated. But even on the completion of this settlement there was still a considerable area of

The jangalburi rules were issued by the Government of Bengal in 1864. Land could be granted under these rules for the cultivation of ordinary staples as well as of special crops at low but progressive rates of revenue.

waste land in the district which no one was willing to take up.

Some reference must now be made to the land which was included in the jurisdiction The Pratapgarh of the Pratapgarh tahsil, to which, prior to the ilam settlement of 1896, special treatment was This tract of country lies in the valleys of the Langai and Singla in the south of the Karimgani subdivision, and consists entirely of temporarily settled land, while only a small portion of it, towards the north, was included in the takbast survey.\* The cultivated land was settled at the same time as the other ilam estates in 1859, and was included in the operations carried on by Maulvi Hamid Bakht between 1875 and 1878. Prior to this settlement the rates assessed had been extremely light. The land was situated in a remote and jungly portion of the district, extensions of cultivation were probably in most cases overlooked, and, according to the Deputy Commissioner, most of the cultivators were men who had a strong objection to paying rent, and who had deliberately migrated to this somewhat unattractive valley in the hope that they might thus evade the demands either of Government or landlord.

In spite of this the settlement officer did not hesitate to apply rates, which under the circumstances must be considered very high. On homestead land he imposed a revenue ranging from Rs. 5 to Rs. 3-12 per acre, and the charge for double cropped or garden land was very

<sup>\*</sup>A considerable proportion of the Pratapgarh pargana is permanently settled. The jurisdiction of the tabsilder only extended to the temporarily settled estates.

little lower. The total revenue was suddenly raised from Rs. 3,600 to Rs. 11,800, and as a natural consequence the settlement broke down. In 1878, sanction was accorded to the establishment of a tabsil in this locality, and it was determined to collect the revenue direct from the cultivators, and, if this measure succeeded, to make a direct raiyatwari settlement. The rates were reduced and a fresh settlement was made which was extended till 1893. The temporarily settled portion of the pargana was then cadastrally surveyed, and a settlement made for five years to enable the tract to be included in the area covered by the operations of the ilam settlement officer. The Pratapgarh tabsil was abolished in 1894 and this tract is now treated like other ilam land.

Further interest attaches to this pargana from the fact that certain claims, known as baban and rasad baban, are put forward by the owners of some of the permanently settled estates to easements in the Dohaliya hills. This question is of too contentious and complicated a character to be discussed in the pages of a Gazetteer, and is of little interest to the general reader. Those concerned will find further information on this subject in a note by Mr. Cossins, C.S., dated June 25th, 1890.

The area included in the ilam settlement of 1896 fell into two broad classes, high land where the staple crop is sail or transplanted paddy, and low land on which aman is grown and which is liable to flood. These two main classes were again subdivided into better and worse, and the country was thus formed into four assessment classes or circles. Land was divided into homestead, rice land,

land growing other crops than rice, and waste; and in each circle there were two grades for each kind of land, except for rice for which there were three. There were thus 12 classes of rice land, and 8 classes of homestead, other crops, and waste. The rates assessed per acre varied from Rs. 2-10 to As. 15 for homestead, Rs. 2-7 to As. 9 for rice, Re. 1-11 to As. 9 for other crops, and from As. 6 to As. 1-6 for waste. The net result of the operations was that the revenue was raised from Rs. 1,17,785 to Rs. 1,66,112, an increase of Rs. 48,327. Only Rs. 17,258 of this increase was due to enhancement, and the remainder represented the revenue assessed on land which had been newly taken up.

The following statement which has been taken from the report submitted by the ilam settlement officer in 1903 shows the temporarily settled area of the dis-

trict outside the Jaintia Parganas: -

(	Class of estates.		SHALL I		Acres.
1.	Modified ilam	•••			23,713
2.	Ordinary "	***	व जयते	•••	108,350
3.	Khas estates	•••	• • •	•••	71,724
4.	Raiyatwari tract of	Prata	pgarh	•••	<b>2</b> 2,595
5.	Resumed old rule g	rant	•••	•••	3,564
6.	Petty temporarily	ettled	ostutes	•••	27,519
7.	Jangalbu <b>ri</b>	•••	•••	•••	7,152
8.	Waste land grants	•••	•••	•••	100,677
			Total	•••	365,294

The expressions modified and ordinary ilam have already been explained, and the former is now of purely academic interest as all leases issued under this tenure have expired. Khas land falls under two broad heads.

Part of it is what is generally known as Government waste, i.e., land which is too high or too low to be well adapted for cultivation, and which has never at any time been settled with any person. Part of it is composed of permanently settled estates which have for arrears of revenue and bought in by Government. When an estate defaults in this way it is brought on the revenue records of the tabsil in which it is situated and a map is made of it. It is then visited every year by an amin or one of the tahsil staff, and, if any one is found in occupation, an annual lease is issued to him. and the land assessed to revenue. The rates imposed are the rates sanctioned for similar ilam land in the neighbourhood, or if the land is not fit for cultivation, the rates assessed on waste. The tahsil staff to whom these operations were entrusted were originally allowed considerable latitude with regard to the rates they may have thought proper to assess; but from the statement in the

	Are	a settle
	σo	Sprus
		e in 190
	190	i.
Tehsil		Acres,
Badr		870
South Sylhet	***	2029
Habigani	***	684
Sunamganj	***	290
Karimgani	***	943
Hakaluki		200

margin, which shows the area settled on annual lease in 1903-04 in each tahsil outside the Jaintia Parganas, it appears that the total area affected was inconsiderable. It is further fairly clear that, in a densely populated district

like Sylhet, permanently settled estates which have failed to obtain a bid at auction, cannot have many attractions for the cultivator.

Most of the new land which is now being taken up

Manner in which for the first time outside the Jaintia

Parganas is situated either in the hills, where there are still a few small patches of land

suitable for rice cultivation which are called chegs; or in the haors, or great depressions which are gradually silting up, and in which cold weather crops are grown. When an application is received the land is first surveyed. unless it has been already mapped in the course of the ilam settlement, and a report is submitted showing in which of the four circles laid down at the last settlement it falls. It has already been pointed out that these circles do not consist of actual tracts of country bounded by a ring fence, but there is always other ilum land in close vicinity to the plot applied for, which guides the settlement officer in determining the circle to which the land should be assigned. The lease when sanctioned is for ten years, and the rate assessed on culturable land is Re. 1-2 an acre in Circle I and Annas 15 in Circle II, and, in both circles, Annas 6 an acre on waste. In the haors, i.e., Circles III and IV, the rates assessed are either Annas 6 or Annas 3 per acre. Land which is found in the possession of persons who have not formally applied for it is settled on annual lease. The area of khas land in each tahsil is unfortunately not known,

In the Jaintia Parganas land newly taken up is assessed at the lowest rates imposed on cultivated land in that particular village. In this portion of the district there is a genuine system of fluctuating cultivation, similar to that which prevails to such a great extent in Lower and Central Assam. Low land covered with reeds is taken up and planted out with summer rice or mustard, and after the second or third year is resigned. Annual leases are generally first issued, and, if the cultivator

decides to retain the land, a periodic lease, which terminates in the same year as the current settlement, is given to him. 1,120 acres were held on annual lease in the Kanairghat tahsil in 1903-04, and 5,219 acres in the Goyainghat tahsil.

Reference has been already made to the pressure of the people on the soil, and, to meet this very genuine demand for land, the upper valleys of the Langai and Singla, in the south of the Karimganj subdivision, which originally formed part of a reserved forest, were thrown open in 1898 and 1899. Much of the land was found to be unsuited for cultivation and the total area allotted by June 1902 was only 7,436 acres. The rates assessed were 15 annas an acre on flat and 3 annas an acre for hill land, but no revenue was charged for the first year of occupation.

The Jaintia Parganas are seventeen in number and toward and the Jaintia Parganas are seventeen in number and 310,000 acres; of which 214,500 acres are settled under one form of tenure or another, and 95,500 acres are waste. They are situated in the north-east corner of the district, and, with the exception of pargana Satbank, lie between the Surma river and the Khasi and Jaintia Hills. They originally formed part of the territories of the Jaintia Raja, but were formally annexed in 1835, as the Raja declined to surrender the persons responsible for the murder of three British subjects who were sacrificed at the shrine of Kali in 1832. The revenue of the Raja was derived from

several heads. Land revenue was paid in kind or labour, fees were levied on appointments, and tolls on ghats, bazars, and fisheries, an item which was said to bring in about Rs. 8,800 per annum. Other sources of revenue were monopolies, presents, and fines. The total income of the Raja was estimated at from Rs. 25,000 to Rs. 30,000 per annum, and to this must be added the amount required to satisfy the demands of the subordinate officers through whose hands it passed.

In 1836, a summary settlement was concluded for one year by Captain Fisher. Early Settlements. The revenue assessed amounted to Rs. 35,988, which was believed to be a fair equivalent of the amount taken by the Jaintia Raja. In 1838, the Parganas were resettled for a term of five years, and this settlement was subsequently extended up till 1856. During this period the rates were not raised but land taken up for cultivation was assessed, so that the revenue demand, which was Rs. 38,900 at the commencement of the term, was Rs. 42,800 in 1856. The rates assessed were very low and varied from one rupee an acre for the best kind of double cropped land. to 2 annas 6 pie an acre for waste.

In 1856, a settlement was made for twenty years, the

The Settlement of revenue assessed being Rs. 54,443.

The rate for the best kind of rice land was not raised, but a small enhancement was imposed on most of the other kinds of land. The next settlement showed a very great increase. The rate for homestead was raised from 14 annas 9 pie to Rs. 1-14

an acre, and cultivation was assessed at Re. 1-5 per acre instead of at rates varying from 6 annas 3 pie to one rupee. The revenue, which by 1876 had risen to Rs. 61,900 owing to extensions of cultivation, was suddenly rushed up to Rs. 1,67,542, and as a natural result the settlement broke down. After much discussion it was decided to modify the rates in the less favourably situated villages, and the gross demand was reduced to Rs. 1,23,700, but, even then, it was almost exactly double the amount which had been previously exacted.

This settlement expired in March 31st, 1896, and The current settle- two years later another settlement was concluded for a term of 15 years. The land was divided into four classes, homestead, rice fields, cultivation other than rice, and waste, and the villages were distributed into five different grades. acreage rates assessed varied in the case of homestead from Rs. 2-10 to 12 annas, for rice land from Re. 1-14 to 12 annas, for land growing other crops from Re. 1-8 to 12 annas, and for waste from 6 annas to 3 annas. Land taken up for tea was assessed at Re. 1-14 for each acre under cultivation, and 6 annas an acre for waste. For the first five years of the settlement the increase in any village, whether due to enhancement of rates or extension of cultivation, was limited to 33 per cent. of the former revenue, and in the next five years to 66 per cent. The full assessment, when the enhancement exceeds 66 per cent, will only take effect The total sanctioned assessment was Rs. in 1909. 1,86,532, but the amount at first imposed was only Rs. 1,69,345.

Sylhet was one of the last districts in Assam to be exploited in the interests of the tea Land taken up for tea. industry, and contains few estates held under the earlier rules which were framed to govern the grant of land for tea. One estate, covering an area of 1,837 acres, is held under the rules of One-fourth of the grant is exempted from asses-1854. ment in perpetuity. The remaining three fourths had a revenue free period of fifteen years and were then assessed at 3 annas an acre for ten years, and at 6 annas an acre for seventy-four years more, the total period of the lease being thus ninty-nine years. Under the feesimple rules issued in 1861, permission was accorded to the owners of lease-hold grants to convert their tenure into fee-simple by payment of twenty times the revenue at that time due. Only one grant, covering an area of 1,891 acres has, however, been redeemed. The great bulk of the tea land is held under the rules of 1876. which, after the passing of the Assam Land Revenue Regulation in 1886, were incorporated in a revised form as Section I of the Settlement Rules. The land was sold at an upset price of Re. 1 per acre, and the lease runs for thirty years. For the first two years no revenue is assessed, it is then levied at the rate of 3 annas an acre for four years, and at 6 annas for four years more. For ten years it is 8 annas, and for the last ten years of the lease Re. 1 per acre. The issue of leases under these rules has been discontinued in Sylhet, and a considerable area of tea land is held on ordinary lease. area settled under different forms of tenure in the district will be found in Table XIII.

I and revenue is paid in at the headquarters of each of the subdivisions, and at the Goyain-Land revenue collection. ghat and Kanairghat tahsils in Jaintia. In the Jaintia Parganas the revenue from estates paying Rs. 50 or less is due in one instalment in May; other estates pay five-sixteenths of the demand in September and eleven-sixteenths in May. In case of default a notice of demand is issued, and if the amount due is not then paid up, the estate can be at once sold, without having recourse to the procedure in force in the other raiyotwari tracts of the Province, under which the land cannot be sold unless an attempt has first been made to realize the arrears by the attachment and sale of the movable property of the defaulter. The dates for payment in the rest of the district vary from April 30th to May 31st. but from estates paying more than Rs. 50, five-sixteenths of the instalment is due on September 30th. If a permanently settled estate falls into arrears, a notice is issued fixing the date of sale, which must not be less than thirty days from the date of the publication of the notice. and if the arrears are not paid up before the day fixed for the sale, it is forthwith knocked down to the highest bidder. In the case of temporarily settled estates outside the Jaintia Parganas the usual formalities of the issue of a notice of demand and the attachment of movable property must be complied with before the estate can be put up to sale.\*

<sup>•</sup> It has recently (1905) been proposed to allow officers discretion to dispense with the notice of demand and to authorise the imposition of a fine not exceeding one rupes in cases of default.

In spite of the lightness of the land revenue demand, which in 1902-03 only amounted to Difficulty in realis-ing revenue. 6 annas 3 pie per head of population, as compared with Rs. 2-7-1 per head in Sibsagar, considerable difficulty is experienced in recovering the lawful dues of the state. Notices of demand are freely issued, and in 1902-03 orders of attachment issued on no less than 13,244 estates, though the total for the whole Province was only 15,271. The amount of arrears for which property was sold in the Province was Rs. 47,618; and of this Rs. 36,835, or more than three-fourths of the whole, was contributed by Sylhet, though the district pays less than one-seventh of the land revenue of Assam. This difficulty in collecting the revenue is largely due to the system of joint ownership which is so prevalent in the district. It has been already shown that in the permanently settled area the revenue assessed on the great majority of estates is ridiculously small, and even these petty sums are due from several individuals and interests. It is frequently the case that, either from accident or design, one of the co-sharers fails to pay his quota, and the estate is accordingly attached and put up to auction. The very lightness of the land revenue assessment on the individual is no doubt in some degree responsible for the difficulty of realization, as people are often careless about the payment of small sums; and, as far as the issue of notices of demand is concerned, the comparison between Sylhet and Assam Proper is hardly fair. In Sylhet these notices are issued automatically as soon as an estate falls into arrears, whereas in Assam they are generally

only served upon persons who are notoriously unpunctual. Many persons also whose homes are situated at some distance from headquarters save themselves the trouble of coming in to pay their revenue by waiting till the arrival of a peon with an attachment order.

beginnings of excise administration in Sylhet, and of the insignificant amount of revenue obtained. In this respect the character of the district has changed but little during the last century, and, though it contains more than a third of the total population of the Province, it only contributed one-twelfth of the excise revenue in 1904. About one-half of the revenue was obtained from ganja and two-fifths from country spirit. The greater part of the remainder was derived from opium.

Country spirit is manufactured by native methods and generally in what is known as the closed still. The wash is placed in a large vessel beneath which a fire is kindled. The vapour rises into the still-head and then passes by two pipes into two receivers, which are cooled by water that is allowed to run over them, and thus cause the vapour to be precipitated in the form of spirit. These tubes are so fixed to the receivers that the air cannot have access to the spirit, and, though distillation does not proceed so rapidly, the liquor produced is stronger than that obtained from the open still.

Province Rs. 30,24,000. Sylbet Rs. 2,61,000.

The material employed is either the flower of the mohwa tree (bassia latifolia), which Materialjemployed. contains a very large proportion of sugar, or molasses and rice. Mohwa is generally used by up-country distillers, and, as the foreigners, who form a large part of the liquor-drinking population, prefer the mohwa spirit, its use is spreading amongst the Sunris who formerly preferred molasses. The following are the proportions in which these ingredients are generally mixed, mohwa 30 seers and water 60 seers; or mohwa 25 seers, molasses 5 seers, and water 60 seers; or boiled rice 20 seers, molasses 10 seers, and water 80 seers. Susta, the refuse wash which remains in the retort after the distillation, is sometime used in place of water. Muli, a substance composed of leaves, roots and spices. whose actual ingredients are not divulged by the villagers who manufacture it, is frequently added to the wash. which is put to ferment in large earthenware vessels. which, to economise space, are often sunk up to their necks in the floor of the shop. The larger vessels are cleansed before they are filled with wash by heating them with hot ashes or ropes of straw which are allowed to smoulder for some hours inside; smaller vessels are usually washed with water. Fermentation takes three or four days in summer and a week in the cold weather, and the wash is then considered to be ready for the still. The process of distillation takes about three hours. A retort of 40 gallons yields two gallons of spirit in an hour and three-quarters, three gallons in two hours and a quarter. and four gallons in three hours. The best and strongest spirit comes off first, and, in the case of a brew of 30 seers of

mohwa, the first 3½ gallons will be classed as phul if they are at once drawn off from the receiver. If they are allowed to remain while two more gallons are distilled, the whole 5 gallons will be classed as bangla. The exact proportions vary, however, at the different shops, some distillers taking 4½ gallons of phul or 5½ gallons of bangla from 30 seers of mohwa. Occasionally only two gallons of spirit are distilled from 30 seers of mohwa, and the liquor is then called thul, is very strong, and is sold for one or two is also sometimes rupees quart. Thul Only one kind of liquor is generally redistilling bangla. taken from each distillation, as, if the thul or phul were removed, the spirit subsequently distilled would be not only weak but impure. Strong liquor watered to reduce it to a lower strength is not considered palatable, and it seems to be the usual practice to distill the liquor at the actual strength at which it will be sold. One disadvantage of the cheaper kind of liquor is that it will not keep, and in four or five weeks it is said to love all its spirituous qualities.

From the statement in the margin it will be seen No. of shops. Revenue. that of recent years there has been a 1973-74 ... 88 7.689 considerable expansion of the revenue 1889-90 ... 68 1,10,888 under the head of country spirits. This is chiefly due to the growth of the cooly population, most of whom are spirit drinkers, who increased more than fivefold, during the last twenty years of the nineteenth century. During this period, though there was a large increase in the liquor revenue; there was hardly any increase in the number of shops.

सत्यमेव जयत

The outstill system is not theoretically the most desirable, and its justification lies in the fact that where there are such facilities for illicit distillation and for smuggling, the only system possible is one which, by providing consumers with a moderately priced and reasonably accessible supply of spirit, lessens the temptation to resort to illegal methods to procure it. The following measures have recently been introduced with the object of reducing as far as possible the evils attendant on the liquor trade. A special excise establishment has been entertained, the vendor is required to arrange for an abundant supply of good drinking water near his shop, and his license can be withdrawn if he is twice convicted of allowing drunkenness and disorderly conduct near the still.

The shops for which the highest fees were paid in 1904-05 were Sylhet town, Bhadair Deol (in Kamalganj), Sharergaj and Ramnagar, both of which are in the Matiganj outpost, and Hingajiya. Table XIV shows the number of shops in each sublivision and the revenue obtained since 1900-01. By far the largest revenue is raised in South Sylhet, where there is a large immigrant population. A considerable proportion of the natives of Sylhet are, however, spirit drinkers, as is shewn by the receipts in Sunamganj, where there are very few foreigners, and in Habiganj where their number is not large.

Pachwai, or rice beer, is taken by some of the humble

Hindu castes, and is largely used by
garden coolies if facilities are not
afforded to them for obtaining country spirit. The
following is the usual system of manufacture followed.

The rice is boiled and spread on a mat, and muli is powdered and sprinkled over it. After about twelve hours it is transferred to an earthen jar, the mouth of which is closed, and left to ferment for three or four days. Water is then added and allowed to stand for a few hours, and the beer is at last considered to be ready. The usual proportions are-5 seers of rice and 3 chattabs of muli to half a kulsi of water, and the liquor produced is said to be much stronger than most European beers. Liquor is often illicitly distilled from pachwai or boiled rice, by the following simple method. An earthen pot, with a hole in the bottom, is placed on the top of the vessel containing the pachwai and the whole is set on the fire. mouth of the upper pot is closed by a cone-shaped vessel filled with cold water, and a saucer is placed at the bottom of the pot over the hole. The vapour rises into the upper of the two jars, condenses against. the cold cone, with which the mouth is closed, and falls in the form of spirit on to the saucer beneath. Care must of course be taken to see that the various cracks are closed against the passage of the spiritous vapour, but this can easily be done with strips of cloth.

Opium is generally swallowed in the form of pills or mixed with water and drunk. Madak Oplum. is made by mixing boiled opium with pieces of dried pan leaf, and stirring it over the fire. The compound is then rolled up into pills and smoked. Chandu is made out of opium boiled with water till the water has all evaporated, and is smoked like madak in. the form of pills.

The people of Sylhet are not much addicted to the use of opium, and the receipts under this head, which were never large, show a steady tendency to decrease. In 1881 they amounted to Rs. 43,700. The maximum of recent years was reached in 1886 (Rs. 47,400) but from that date onward they gradually declined till in 1902 they had sank to Rs. 18,800.

The number of shops in each subdivision, the quantity of opium issued, and the revenue raised under this head are shown in Table XIV. Karimganj and North Sylhet are the only parts of the district in which opium is taken in appreciable quantities. In South Sylhet there is only one shop, which sells about ten seers a year; and in Habiganj the quantity consumed is well below one maund.

Ganja is usually mixed with water, kneaded till it becomes soft, cut into small strips, and smoked. Wild ganja grows very freely in the hills, but it is doubtful whether it is much used except as a medicine for cattle. It does not produce such strong effects as the ganja of Rajshahi, but the leaves are sometimes dried and mixed with milk, water, and sugar to form a beverage. Sylhet has always been rather a ganjasmoking district, and in 1884 the revenue raised from this drug in Sylhet amounted to more than half the total receipts from ganja in the Province. The receipts under this

	He. (000 omitted)
1891	109
1884	121
1888	88
1891	126
1895	99
1897	128

head of excise have kept fairly steady, as will be seen from the statement in the margin which shows the most violent fluctuations since 1881. The number of shops in each subdivision,

the quantity of ganja issued, and the revenue obtained are

shown in Table XIV. Unlike opium, the revenue obtained from ganja is fairly evenly distributed over most parts of the district, and the difference between the subdivisional receipts is small.

The receipts under the head of income tax in 1904 amounted to Rs. 53,619, or more than Income Tax. one-fifth of the total collections of the Province. About two-fifths of the whole were assessed on the salaries paid to garden managers and their staff; and the salaries and pensions of Government servants also yielded over Rs. 6,000. Nearly half the total amount was, however, realized under Part IV "other sources of income," and there were altogether 638 assessees under this head, or one in every 3,300 of the population. 266 of these persons were described as money-lenders, but most of these people in all probability combined money-lending with agriculture, and there were 68 assessees in the professional class, nearly all of whom were pleaders. assessment is made in each subdivision by a Sub-Deputy Collector or Extra Assistant Commissioner, who visits the principal villages and submits his proposals for the approval of the Deputy Commissioner.

The receipts from income tax have on the whole remained fairly steady, but it is doubtful whether there has been much increase in the taxable capacities of the people. In 1888, the receipts amounted to Rs. 61,000 and the maximum was reached in 1898 with Rs. 75,700. The marked decrease which occurred in 1904, and left the income tax demand lower than at any period since Act II of 1886 became law, was due to Act XI of 1903, which raised

the minimum taxable income from Rs. 500 to Rs. 1,000 per annum. The consequence was that the assessment under Part 1V was less by Rs. 10,000 in 1904 than it had been in 1888. A statement showing the receipts under this head will be found in Table XI.

The stamp revenue of Sylhet is large, judicial stamps yielding in 1904 Rs. 4,04,000. Stamps. and non-judicial stamps Rs. 1,52,000, which in both cases was considerably more than half the total amount realized in the Province under this head of The incidence per head of population was 4 revenue. annas, as compared with 3 annas 4 pies per head in Cachar and 1 anna 11 pies in the Assam Valley. This higher incidence is chiefly due to a higher general level of inteligence. In the other districts in the plains the proportion of aboriginal tribesmen or of garden coolies is much greater than in Sylhet, and people of this class have seldom much occasion to attend our Courts. Trade, too, is more decentralized than in Assam where it is concentrated in the hands of a small and united community of Marwari merchants, who endeavour as far as possible to settle their disputes without paying fees to Government or pleaders. The potential number of litigants is thus larger than in other districts, and the complicated condition of the land tenure is a fruitful subject-matter of dispute. The receipts under the head of stamps in 1902 and subsequent years are shown in Table XI.

Public Works are in charge of an Executive Engineer or Assistant Engineer, who is usually assisted by four upper and three lower subordinates. The Public Works Department are

entrusted with the construction and maintenance of all the larger public buildings. The most important are the jail, the public offices, schools and post and telegraph offices at district and subdivisional headquarters, circuit houses, dâk bungalows, and inspection bungalows on provincial roads. Inspection bungalows on other roads are maintained by the Local Boards. The most important lines of communication directly under the Department are the roads from Sylhet to Companyganj Fenchuganj, the Cachar trunk road as far as Badarpur. and the roads from Habiganj and Maulavi Bazar to the railway stations at Saistaganj and Shamshernagar. Since 1897, a large outlay has been incurred by the Department on the reconstruction of the Deputy Commissioner's and Judge's courts and the district jail. It has already been explained that Local Board works that require professional skill or engineering knowledge are usually made over to the Executive Engineer for execution.

For general administrative purposes the district is divided into five subdivisions. Government. Sylhet is under the immediate charge of the Deputy Commissioner, Karimganj and South Sylhet are entrusted to assistant magistrates who are almost invariably Europeans, and Habiganj and Sunamganj to magistrates who are usually natives of India. The Deputy Commissioner is allowed four subordinate magistrates and three Sub-Deputy Collectors as his assistants at headquarters, and a second magistrate is usually posted at each of the subdivisional stations.

except at Habiganj where there are generally two magistrates in addition to the Subdivisional Officer. The total number of clerks employed under the Deputy Commissioner's orders in 1903 was 181 and they drew altogether from Government nearly Rs. 74,000 in salaries.

In spite of the fact that the district covered an area of nearly 5,500 square miles, a considerable part of which was very densely peopled. Sylhet remained for more than a century under British rule before any attempt was made to decentralize The question was first mooted in the administration. 1860, and it was then admitted that a million and three quarters of human beings could not be adequately governed if all the courts and all the superior officers engaged in the administration were located at one place. Sylhet, the capital of the district, was, moreover, some-There were, at that time, hardly any what inaccessible. roads, and the difficulties of communication in the cold weather must have been very great; while even in the rainy season access could only be obtained to the court of the Deputy Commissioner from some portions of the district after a long and tortuous voyage. In 1867, the district was subdivided by notification in the Gazette, into four minor units, i.e., Sunamgunj, Karimganj, Habiganj, and what now corresponds to, North and South Sylhet, but no less than ten years passed before effect was given to this order; want of money being for some time an insuperable obstacle. The first subdivision was opened at Sunamganj in January 1877, and there was evidently.

even at that time, considerable financial stringency, as the Subdivisional Officer elect, who was a European, was informed that he could build himself a cutcherry and a comfortable dwelling house for at most Rs. 2,000! The sanctioned subdivisional establishment both here and at Habiganj and Karimganj, which were opened in the following year, were one Sheristadar on Rs. 50 per mensem, one clerk on Rs. 30 per mensem, four clerks on Rs. 20 per mensem, a potdar and a daftri each on Rs. 6 per mensem, and a chaptasi on Rs. 5. Subsequently it was found that the sadr subdivision was too large, and in 1882 a fifth subdivision was opened at Maulavi Bazar. The area and population of each subdivision

Area in Population is shewn in the statement in the margin.

Bunamgani North 87 linet 1,005 485,477 Raringani 1,005 485,477 Raringani 1,005 485,477 Raringani 1,005 485,477 Raringani 1,005 840 879,158 Habigani 999 585,001 is the thana, of which there are 16.

The area and population of each thana is shewn in Table II.

Appeals lie to the Deputy Commissioner from the deci
Criminal and Civil sions of magistrates of the second or third class, but the duty of hearing these appeals is sometimes delegated to the Subdivisional Officers of Karimganj, South Sylhet, and Habiganj, and to the senior assistant magistrate at sadr, who are specially empowered in this behalf. Appeals from first class magistrates lie to the District and Sessions Judge, who is subordinate to the High Court of Fort William at Calcutta. In 1902, there were 16 stipendiary and 2 honorary magistrates in the district and two benches of

magistrates. These magistrates decided altogether 4,455 cases in the course of which 21,594 witnesses were examined. Altogether 5,634 cases under the Penal Code were returned as true, about four-fifths of which were either offences against property or against the human body.

In the chapter on the history of the district, reference has been already made to the unruly Prevalence of ag-rarian riots. character of the inhabitants, and to the prevalence of river dacoity and agrarian riots in the early days of British rule. Unfortunately these characteristics still persist, and there is a marked tendency even at the present day to settle disputes arising out of the complicated land tenure by appeals to force. The matter is generally brought to a head by one party resisting the attempt of their opponents to seize the land or crops, and a curious case occurred in 1882 in which some villagers in the Jaintia Parganas deliberately decided to submit their claims to an ordeal by combat. The day hour were fixed, and, in the course of the fight, two men were killed and many wounded. A few months later a date was fixed for a similar encounter, but on this occasion the police were informed of the intentions of the parties and intervened to prevent a breach of the peace.

These riots, as a rule, take place between the disputants for the land, but in 1900 the police themselves were attacked at Bhanubhil, near Kamalganj in the south of South Sylhet. Relations between the zamindar and his raiyats, most of whom were Manipuris, had for some time been strained, and a police guard was posted at the

zamindar's cutcherry to preserve the peace. On October 10th, two constables, two village chaukidars, and four zamindari peons who had been sent to enquire into the fate of a missing man, were seized by the villagers and severely beaten. Some of the accused persons absconded, and on October 17th a party of eight policemen, accompanied by three elephants belonging to the zamindar and about one hundred of his men, proceeded to the villages to arrest the guilty persons. On their arrival, they were confronted by a crowd of over a thousand people; and the head constable, who dismounted from his elephant to address the leaders of the mob, was assaulted with a club. The armed police fired their guns into the air, the zamindar's men fled, and the victorious villagers killed a mohurrir of the zamindar's cutcherry, mortally wounded another man, seriously injured seven of the police, and severely beat a number of other persons. High Court subsequently confirmed the conviction of eleven of the men concerned in the two riots, and imposed sentences of imprisonment varying from seven to two years. Abidabad, Nabiganj, Dirai, Badla, and Astagram have an unenviable reputation for river dacoity.

The average number of murders and culpable homicides annually reported during the ten years ending with 1889 was 24. In the next decade the average rose to 31, and during the past four years (1900-03) the average was 40. The largest number of cases occurred in 1901, when there were 48, or 1 to every 46,700 persons. This was nearly three times the rate prevailing in the Province of Bengal

during that year, but is considerably lower than the rate for Lakhimpur in 1897, when there was one case for every 19,500 persons.

Most of these murders are due to quarrels about women, and not unfrequently the victim is a luckless wife, who, rightly or wrongly, is thought to be unfaithful. The great majority of these crimes are of a senseless and savage character, and the circumstances under which they are committed suggest that the murderer at the time was utterly bereft of sense. A typical case is one reported in 1882. A man abused his wife for neglecting to prepare his evening meal. The woman brooded over her wrongs, and when her husband composed himself to sleep, suddenly seized a dao and cut him about the head. She then murdered her infant child, and finished by cutting her own throat. The husband ultimately recovered, but two lives were sacrificed to a petty squabble about uncooked rice. A much more deliberate murder was committed in the following year by a party of Manipuris. A Muhammadan agent of a zamindar in the Muchikandi thana enticed away the wife of a Manipuri Brahman, and declined to give her up when called upon to do. Instead of applying to the magistrate for redress, the Manipuris held a panchayat, and decided that the Muhammadan should be killed as a punishment for seducing or at any rate harbouring a Brahman woman.\* On the following morning, some two or three hundred of these people went to the zamindar's cutcherry, on

In Manipur itself Manipuri women are extraordinarily lax, and adultery is looked upon as a venial fault and is often winked at by the husband.

pretence of having business with the agent. They succeeded in securing two guns which were in the office, and then arrested the object of their vengeance. He was carried out to the market place, mutilated in a horrible manner, and deliberately beaten to death in the presence of the The Manipuris then sent for two chaukidars, made over the body of the murdered man to one and his guns and property to the other, and called on them to bear witness that vengeance and not robbery had been their motive. It is satisfactory to know that for this cold-blooded murder and defiance of the law, one man was hung and thirty-three transported for life.

In 1900, a family murder was committed under very curious circumstances. A villager named Bir Singh, was so depressed at the death of his wife, and at the loss of a considerable sum of money which she had buried in a spot which she was unable to disclose before she died, that he determined to put an end to his own life and that of all his children. He accordingly sent away his sister who was mothering the orphaned baby, and arranged his children, who were aged seven, five and two-and-a-half years respectively, in a line, one behind another on the floor. He then sat down in front with the infant slung round his neck, placed the muzzle of his gun at his own heart and pressed the trigger with his toe. The result was the instantaneous death of himself and the two children sitting just behind, but though the bullet lodged in the body of the third child it was too spent to kill her. The infant alone escaped unhurt.

Civil justice is administered by the District Judge
assisted by two subordinate judges
and ten munsifs. Prior to 1896, there
was only one subordinate judge, but an additional
officer in that grade was sanctioned in that year as a
temporary measure, and he was made permanent in 1903.

In 1902, the District Judge decided 12 original cases and 78 appeals, the subordinate judges 498 original cases and 447 appeals, and the munsifs 19,236 cases; but out of the total number of cases disposed of in all courts only 3,554 were actually contested. In round figures these civil suits were classified as follows:—Money suits 12,000, rent suits 4,000, title suits 3,000. From the pecuniary point of view they cannot be described as of much importance as two-thirds of the total number were valued at Rs. 50 or less.

Sylhet is the only district in the Province in which there is much registration work. The Deputy Commissioner is District Registrar. Special sub-registrars are entertained at the district and subdivisional headquarters and rural sub-registrars at Balaganj, Kanairghat, Jagannathpur, Madhabpur, Jaldhub, Hingajiya, Patharkandi, and Baniyachung. The total number of documents registered in 1903 was 41,500.

The Civil Police are in charge of a District or

Assistant Superintendent of Police.

The sanctioned strength consists of 6 inspectors, 63 sub-inspectors, and 562 head constables and

constables. 213 smooth-bore Martinis are allotted to Sylhet and a reserve of men is kept up at the district and subdivisional headquarters who are armed with these weapons and are employed on guard and escort duty. Up-country men, Nepalese, and members of the aboriginal tribes are usually deputed to this work, though attempts are made to put all the constables through an annual course of musketry.

In addition to their regular duties in connection with the prevention and detection of crime, the police are required to check the returns of vital statistics, enquire into cases in which death has not been due to natural causes, furnish guards and escorts, and serve all processes in warrant cases.

The district is divided into 31 investigating centres. The names of these stations and the number of men stationed at each centre will be found in Table XVIII.

The Chaukidars.

shape of a village community in Sylhet in the days of native rule, and there was at that time no village officer corresponding to the chaukidar. Chaukidars were apparently first appointed some time between 1818 and 1838, and in a report submitted in the latter year, they are referred to as a standing institution.\*

No attempt seems to have been made to settle the boundaries of the village beats, and there does not appear to have been any efficient machinery for the realization of

Magistrate's letter No. 263, dated April 1838, to Superintendent of Police.

the village policeman's pay. The natural result was that the force, if force it could be called, was in a very unsatisfactory state. In 1840, the Magistrate complained that the chaukidars could not be made the really efficient branch of the police force they were capable of becoming, until they were constituted the servants of Government and not of the village community.\* In 1865, it was said that nothing could be worse than the condition of the rural police, who did not on the average receive more than Re. 1 per mensem. whole question was taken up by Mr. Luttman-Johnson when he assumed charge of the district in 1878, and. on his representation, Regulation I of 1883 was passed, to regularize and legalize the position of the village Under this regulation the chaukidar may be watch. paid in kind as well as in cash, he is left to make his own arrangements with the villagers as to the amount of pay he is to draw, and under ordinary circumstances he collects his salary himself. In cases of recalcitrancy the assistance of the magistrate can be invoked, and it is within the discretion of the Deputy Commissioner to appoint a panchayat to represent the villagers if he considers it desirable to do so.

In 1896, Mr. O'Brien, the Deputy Commissioner of Sylhet, who was acting as Inspector-General of Police, reported that the regulation of 1883 had not worked satisfactorily in practice. The chaukidar, if he received his pay at all, neither received it regularly nor in full, he was entirely dependent on his fellow villagers, and

Magistrate's No. 838, dated 13th April 1840, to Superintendent of Police.

was their instrument and tool and not a servant of the State. Act VI (B. C.) of 1870, was accordingly introduced in North Sylhet in 1898, and has since (1905) been extended to every part of the district. Under this Act the salary of the chaukidar is collected by a panchayat appointed for this purpose. It is then handed over to an officer, who, as a matter of fact, is usually the police officer in charge of the circle, by whom it is made over to the chaukidar. This system tends to improve the condition of the village watch by securing the regular payment of their wages, and at the same time places them more under the control of the police department. The total number of chaukidars employed in Sylhet in 1904 was 5,158, who were entertained at a cost of Rs. 2,67,000.

A Volunteer Corps was first enrolled in Sylhet in

1880 with a strength of 42 members,
but was subsequently amalgamated
with the Cachar volunteers to form the Surma Valley
Light Horse. This admirable corps had a total strength
in 1904 of 334 men, 178 of whom were residing in
Sylhet.

The Sylhet Jail, which was reconstructed after the earthquake of 1897 at a cost of Rs. 1,86,000, is the largest and best ordered institution of that kind in the Province. The premises, which cover an area of 7.2 acres, are surrounded by a brick wall, and on one side there is a large garden enclosed by a bamboo palisade. The

principal sleeping wards, which are ten in number, are erected on high masonry plinths, the uprights are of iron, and the roof is made of corrugated sheets of the same metal. The walls are of whole bamboos, covered with bamboo shutters which can be raised or lowered at will; and the wards are thus warm in winter while in summer they are airy and cool. Two

Convious 15 29 15 cubicles which can accommodate 186 Civil prisoners Observation cells ... 6 0 prisoners and have been erected at a Total ... 636 23 cost of Rs. 20,000. The number of persons who can be accommodated in the jail is shewn in the statement in the margin.

The water-supply is drawn from masonry wells, to one of which filtering beds and arrangements for boiling the water are attached, the total cost of the whole being over Rs. 6,000.

The prisoners are employed on gardening, weaving, carpentering, the manufacture of basket-work furniture and sieves, soorki-pounding, and oil-pressing. Bread and soda water are also manufactured in the jail. The cash earnings of the prisoners in 1903 were said to amount to Rs. 3,561, but this takes no account of the value of goods supplied to other jails, or of raw materials and manufactured articles in store.

The following statement shows the number of deaths that has occurred in each year since 1883, in which the total number

of casualties exceeded ten, and the death-rate per mille on the daily average strength of convicts.

Year.	Daily average strength.	No. of deaths,	Death-rate per milie on the daily aver- age strength,
1883	265	14	53
1884	214	17	79
1885	223	21	94
1886	177	22	124
1889	180	21	116
1891	139	28	201
1894	529	24	45
1895	479	39	81
1896	510	82	63
1897	533	21	39
1898	521	18	35
1899	512	32	63
1900	476	12	25
1901	509	246917	33
1902	426	14	33

Between 1881 and 1892, it was the practice to house bodies of prisoners in temporary jails during the cold weather, and employ them on road construction under the Public Works Department. It was thought that change of scene and employment in the open would have a good effect upon their health, and after the system had been placed upon a proper footing this proved to be the case. At first there was some mortality due to the consumption of impure food and water while at work, and to over-exposure, but these defects were soon remedied. The prisoners were supplied with filtered from obtaining unwholsome food, water, prevented and on their return from work were provided with dry and warm clothing, with the result that, except for occasional outbreaks of cholera, the health in these jails was exceptionally good. The effect upon the statistics of

260

the Sylhet Jail was, however, very striking. Only the weakly prisoners were retained at sadr, and men whose health began to fail were sent back from the temporary iails. in some cases to recover, but in some to die. enormous death-rate shownagainst appears to be an instance of the misleading character of statistics when improperly employed. No less than 20 of the 28 deaths occurred amongst prisoners who had returned from the Lushai Hills temporary jail. This temporary jail had a daily average population of 364 in the cold weather, but not a single death was debited against it. There was also a large temporary iail at Telikhal, which was chiefly manned by prisoners from Sylhet, and both of these two jails were omitted when calcultaing the average daily population and deathrate of the sadr jail. Even apart from this statistical confusion it must be admitted that the death-rate was occasionally most lamentably high. In 1895, the actual death-rate amounted to 81 per mille, which was characterised by the Chief Commissioner as appalling, and led to the issue of stringent regulation for the protection of the convicts when employed on extramural labour. In the following year, the death-rate was again high, and the Inspector-General of Jails came to the conclusion that too much regard had been paid to economy by those in charge, and directed that rations should he issued on a more liberal scale. Since that date the health of the jail has been fairly good, except in 1899 when there was a death-rate of 63 per mille. This high death-rate was partly attributed to overcrowding and to the insanitary character of the sheds in which the

prisoners were housed while the jail was under reconstruction, and partly to the prevalence of a peculiarly malignant form of malarial fever in the town. The arrangements in the jail are now quite admirable, and of recent years the death-rate has been low.

At the headquarters of each subdivision there is a jail in which male convicts are allowed The Subdivisional Jails. to be detained for three months, and female convicts for one. Persons sentenced to a longer term of imprisonment are transferred to the jail at Syl-The wards are constructed on high mud plinths, and have iron posts and roofs and bamboo walls, and are situated in an enclosure surrounded by a bamboo The statement in the margin shows the area palisade.

of the premises and the number of No. of pris-oners prisoners for whom accommodation is eoso be provided. The prisoners are usually employed on gardening or cleaning Acres. the drains and repairing the roads of the town; and, inside the jail, are sometimes put to paddy husking and the mustard oil Table XIX shows the population, the mortality, and the financial results of each jail in 1881, 1891, and

In the days of native rule there were a large number of village schools, in the district, Education. where children were taught to read by the local Pundit or Maulavi and were instructed in the mysteries of Sanskrit or the Koran. For many

1901.

years after our occupation of the country, these indigenous and unaided schools were the only ones the people had, and education on the English system is a plant of comparatively recent growth. In 1867, or less than forty years ago, there were only 28 schools and 1,127 scholars in the district. Nearly half of these children were living in Sylhet town, so that amongst the millions in the mofussil, education on the English system might be said to be almost non-existent. The following abstract shows the development of education since 1874; and how the 1,100 pupils of 1867 had increased to nearly 40,000 in 1901. The figures for later years will be found in the appendix (Tables XX).

Years.	Number of	Papile.	Number of	Pupils.	Total No. of pupils.	ILL GIRG	lastruotic	nge under on to those woing age.
	satiools.		primary	27.88		each pupil.	Malon	Females.
1874-75	27	1,608	195	5,218	6,826	252	•••	
1880-81	31	2,654	285	8,829	11,483	171	7.32	0.09
1890-91	44	4,424	695	22,342	26,766	81	15·35	1.03
1900-01	68	5,701	1,017	33,809	89,510	57	21-39	2.24

High schools are those institutions which are recognised by the Calcutta University as capable of affording suitable preparation for the Entrance Examination. The boys are taught from the earliest stage of their education up to the En-

Principal Heads of the History and Statistics of the Dacca Division, page 326.

trance course as prescribed by the University of Calcutta, but many leave school without completing the course. Till recently English was taught in all the classes. smaller boys no longer learn that language, the standard of instruction is higher than that prevailing in lower secondary (middle) schools. English is medium of instruction in the first four classes of high schools; in the lower classes and in other schools the vernacular is employed. The course of instruction at middle English and middle vernacular schools is the same, with the exception that English is taught in the former and not in the latter. The following are the subjects taught in the middle vernacular course:-(1) Bengali comprising literature, grammar, and composition, (2) History of India, (3) Geography, (4) Arithmetic, (5) Elements of Euclid (Book I), mensuration of plane surfaces and surveying, and (6) simple lessons on botany and agriculture.

Primary education is again divided into upper and lower, but the proportion of boys in upper primary schools is less than six per cent. of the total number, and this class of school, like the middle vernacular, is slowly dying out. The course of study in lower primary schools includes reading, writing, dictation, simple arithmetic, and the geography of Assam. In Upper Primary schools the course is somewhat more advanced, and includes part of the first book of Euclid, mensuration and a little history. The standard of instruction given still

leaves much to be desired, but efforts have been recently made to improve it, by raising the rates of pay given to the masters. Fixed pay is now awarded at average rates of Rs. 8 per mensem for certificated and Rs. 5 per mensem for uncertificated teachers, supplemented by capitation grants at rates ranging from 3 annas to 6 annas for pupils in the three highest classes.

Sylhet is fairly well supplied with secondary schools. second grade Murarichand The Sites of College and principal schools. unaided College in Sylhet town was founded by Raja Girish Chandra Roy in 1892 and is supported by that gentleman. There is a Government high school at Sylhet, aided high schools at Habiganj, Sunamganj, Maulavi Bazar, and Karimganj, and unaided high schools at Sylhet and Baniyachung. There are also one Government, 40 aided and 4 unaided middle English schools, and 14 schools which are classified as middle vernacular. A list of these schools will be found in the Appendix, In 1901, the proportion of literate males was 81 per mille, which was higher than that in any district of the Province, with the exception of the Cachar Plains. Female education has made very little progress, and only four women in every thousand were returned as literate at the last census.

The district is in the medical charge of the Civil

Surgeon who is stationed at Sylhet.

Medical General Surgeon who is stationed at Sylhet.

It contains 43 dispensaries, and the supervision of the work done at these institutions is one of the most important of his duties. He

also acts as Superintendent of the Jail and Leper Asylum, he controls and inspects the vaccination department, and is required to visit and report on all tea gardens on which the death-rate for the previous year has exceeded 7 per cent.

The conditions under which the majority of the people pass their days are far from conducive Absence of rural sanitation. to a long term of life. Their houses are small, dark, and ill-ventilated, and the rooms in summer must be exceedingly close and oppressive. They are built upon mud plinths, and are in consequence extremely damp, and the poorer people, instead of sleeping on beds or bamboo platforms which would cost but little to provide. often pass the night on a mat on the cold floor. houses are buried in groves of fruit trees and bamboos, which afford indeed a pleasant shade but act as an effective barrier to the circulation of the air, and increase the humidity of the already over humid atmosphere.\* Sanitary arrangements there are none, the rubbish is swept up into a corner and allowed to rot with masses of decaying vegetation, and the complete absence of latrines renders the neighbourhood of the village a most unsavoury place. The water-supply is usually bad and is drawn either from rivers, or from tanks in which the villagers wash their clothes and persons. Hindus are generally burnt upon the river bank, and the mattress on which the corpse was carried to the pyre is left to rot upon the ground, to be carried off in the next flood

The Civil Surgeon has found that excellent results have attended the clearance of bamboo jungle in places where fever has been particularly bad.

with all the germs of disease it may contain. In the cold weather the carcases of dead cattle are thrown into the river, and the Civil Surgeon has seen more than sixty in a single trip from Karimganj to Fenchuganj. These masses of decaying matter often drift into back eddies, where they thoroughly pollute water which is often subsequently used for all domestic purposes. All of these are undoubtedly factors which contribute to produce a high mortality, and nearly every one of them could be eliminated.

Vital occurrences are reported verbally by the village chaukidars to the police, but the accuracy of the statistics leaves much to be desired. In 1902, enquiries were made by the testing staff with regard to 34,000 births and deaths, and it was found that 6 per cent. of them had been omitted from the registers. The mean recorded birth-rate for the decade, 1891-1901, was 34, and the death-rate 33 per mille.

The diseases which are most common in the district are fevers of various kinds, small-pox, chicken-pox, measles, cholera, dysentery and diarrhæa, skin diseases, and worms. Enteric and gastric fevers, dengue, and diptheria are seldom met with. Fevers are divided into three main classes: intermittent fever with ague, remittent fever which generally lasts some fifteen days with a long and tedious convalescence, and kala azar, which is here known as pet mota or mulkipira. Kala azar has been prevalent for many years in the Brahmaputra Valley and has produced the most appalling mortality in the Garo Hills and in Lower and Central

Assam, but till comparatively recently it was thought that Sylhet was free from the disease.

In 1897, after the great earthquake, malarial fevers became extremely common, and some of them assumed a malignant and fatal type which was not amenable to ordinary treatment. The people themselves looked upon this fever as a new disease, and after some enquiry the Medical. Department came to the conclusion that it was probably identical with the dreaded kala azar of Assam. Their uncertainty was due to the fact that it is difficult to distinguish between kala avar and ordinary malarial fever, the principal points of difference being the ease with which it can be communicated from the sick to the healthy, the extreme condition of cachexia which is rapidly induced, and the small proportion of recoveries. As to the exact nature of the disease the medical profession is still in doubt: as to the appalling effects it can produce there is unfortunately no question.

The fever in Sylhet is of a remittent type, the spleen and liver are enlarged, the complexion is of a leaden hue, and there is considerable wasting of the muscles. The disease is not so widespread or of such a fatal type as the form that is found in the Brahmaputra Valley, but it is said to be intensely prevalent in some portions of the district. The mortality in 1897 was very high in Sylhet, but that year was an exceptionally unhealthy one in every part of the Province, and since that date the health of the district has been fairly good. Serious outbreaks of fever also occurred in 1879, and again in 1884 and 1885. For the present at any rate, the North

and South Sylhet subdivisions appear to be the most feverish portions of the district. The inhabitants of Habiganj and Sunamganj enjoy better health, possibly because almost the whole of the country goes under water in the rains.

Cholera appears every year in the Habiganj, Sunam-Cholera and other diseases. ganj, and North Sylhet subdivisions and is a regular visitor to the police stations of Jagannathpur, Dirai, Baniyachung, Nabiganj, The disease is generally most severe in and Biswanath. the autumn when the floods are drying up, and its dissemination is assisted by the careless habits of the people and the reckless way in which they allow their drinking water to be polluted. On the outbreak of an epidemic, native doctors are sent amongst the people, and efforts are made to prevent the villagers from flinging carcases and dead bodies into the haors and rivers. The district is, however, fairly free from cholera. Only four times in the last twenty years has the recorded death-rate from this disease exceeded 4 per mille, and not once has it been as high as 5 per mille, but in 1870 there was such a violent outburst of this dreadful epidemic that the Magistrate closed the courts for 17 days. Small-pox of course exists, but the mortality is far from high, and virulent outbreaks are not so common as in other parts of the Pro-It is perhaps on this account that the inhabitants seem a little indifferent to the advantages of vaccination. In the five years ending with 1902-03, only 34 per mille were on the average annually protected as compared with 44 per mille in the Province as a whole. Skin diseases

are very prevalent and so are worms, the uncleanly habits of the people rendering the dissemination of the ova a very simple matter. The parasites most generally found are the round worm, the tape-worm, the whip-worm, and the anchylostomum duodenale. Goitre and elephantiasis are very rare, but venereal diseases are said to be fairly common.

The native methods of midwifery leave much to be desired. The old Hindu Ayurvedic system seems to have prescribed a fairly reasonable treatment. The hut in which the patient was confined was to be newly erected for the occasion, fairly spacious, well ventilated and dry; the bedding was to be clean, and the attendants were required to cut their nails and wear clean clothing. After delivery the mother was to be carefully tended, and protected from anything likely to retard recovery till her health was properly restored. In the case of unnatural presentations the infant should be thrust back into the uterus and turned if possible, and when this proved to be impracticable, it was dismembered and brought out in pieces.

At the present day the practice of erecting a new hut is often disregarded, and, where one is built, it is generally of the most unsanitary description; but in many families a dark and ill-ventilated room which is attached to the main house is specially reserved for lying in. The patient is attended by low caste widows who are ignorant and uncleanly. In a natural and easy labour they have not much opportunity of doing harm, but where delivery is retarded, they often do much injury

alike to mother and to child. They generally endeavour to induce the premature expulsion of the placenta and thus cause hæmorrhage which is sometimes fatal. The mortality of mothers in child-birth is said to be considerable. The zenana system is supposed to have a prejudicial effect upon female health, early marriage is common, little girls become mothers before they are fitted to support the strain, and the shock of parturition not unfrequently is fatal to a constitution already weakened by malaria. Septicæmia is often caused by the uncleanliness of the surroundings of the mother and her attendants, and the treatment after delivery is generally most in-The patient, instead of being allowed to rest iudicious. in quiet, is encouraged to move about, and often takes a cold bath in the tank before the house. Midwives from Behar and Upper India are reported to be not quite so ignorant and unskilful as those of Bengal.

The Ayurvedic system of medicine is said to have fallen into disrepute owing to the ignorance of the Kabirajes who are its principal exponents. The medicines are generally prepared from iron, silver, copper, arsenic, sulphur, mercury, from plants and trees, and sometimes from cobra poison. A native doctor who has now retired from Government employment reports that he has found the use of cobra poison to be attended by the most excellent results. Ganaks treat cases of small-pox, chicken-pox, and measles, but decline to reveal their methods. Ojhas attempt to cure the sick by incantations, and Mullas by reading the Koran in a chorus.

Though there can be little doubt that many lives are interesse in facilities for obtaining by proper treatment, it is satisfactory to know that of recent years there has been a great increase in the facilities for obtaining medical aid, and in the extent to which the people avail themselves of the advantages now offered to them. The first dispensary was opened in Sylhet in 1863. From the statement in the

margin it appears that for every patient treated in 1881 there were Dispensaries. 17 in 1901, while the number of operations performed rose from 390 to 8,068. The principal dispensaries are those situated at Sylhet, Maulavi Bazar, Rabir Bazar, Habiganj, Sunamganj, Srimangal, and Kulaura, each of which had a daily average attendance in 1903 of more than 40 persons, while Sylhet headed the list with 81. The diseases for which treatment is most commonly applied are worms, cutaneous disorders, malarial fevers, diseases of the eye, dysentery and diarrhea, and rheumatic affections. Further details with regard to the medical administration of each subdivision will be found in Table XXII, and with regard to each dispensary in Table XXIII. Table V registered mortality from certain of the the The figures are not correct but give principal diseases. some idea of the comparative value of these different ailments as lethal agents. Of recent years the district has been fairly healthy and since 1899 the recorded birth-rate has generally exceeded the recorded death rate by about 8 per mille.

An asylum for the reception of lepers was opened at

Sylhet in October 1898. It is situated on
the north bank of the Surma on the outskirts of the town, and consists of twenty small cutcha
houses which can accommodate 18 single lepers and 14
families. Under the Lepers Act III of 1898 pauper lepers
may be sent to the asylum from Sylhet, Sunamganj,
Karimganj, Maulavi Bazar, and Habiganj, and from Silchar
and Hailakandi. Twenty lepers were under treatment in
the asylum at the end of 1903.

The following is a list of the various measurements and surveys which at different times have been made of different portions of the district:—

	ESTEROY STREETS	
1.	Hastobad by Mr. Willes	1788 to 1790
2.	Halabadi (a) partly by Mr. Ward	1820
	(b) " ., " Tucker	1822 to 1825
3.	Lieutenant Fisher's Survey of ilam lands	1827 to 1834
4.	Survey for the resumption of invalid Revenue-free grants by deputy collec- tors	18 <b>36</b> to 1840
5.	Lieutenant Thuillier's Survey of Jaintia	1837 to 1840
6.	Ditto 11 parganas of Zilla Latu	1842
7.	Takbast Survey	18 <b>59 to 1866</b>
8.	Survey of ilam and other petty temporarily settled estates in the district	
	by deputy and sub-deputy collectors	1871 to 1880
9.	Survey of Jaintia by Mr. Beckett	1875 to 1878

10.	Karimganj, South Sylhet, and Habiganj subdivisions by Major Badgley and	*0## 1 . *00*
	Colonel Woodthorpe ***	1877 to 1883
11.	Survey to test the accuracy of the tak- bast measurement by Mr. P. A. G.	
	Cowley	1882
12.	Cadastral Survey of pargana Pratapgarh by Mr. Barrett	1891 to 1892
18.	Cadastral Survey of Jaintia Parganas by Mr. Barrett	1892 to 1898
14.	Cadastral Survey of ilam estates in Syl- het Proper, by Babu G. C. Das, E.A.C.	1896 to 1897

The revenue survey of 1859—1866, which is generally spoken of as the takbast, is of considerable importance, as the maps and papers have on more than one occasion been held by the Civil Courts to be valuable evidence of possession and title. It was never confirmed, as required by section 4, Act IX of 1847; but, in spite of this, it is the general policy of Government to decline to recognise any claims to land which was not included in the purview of its operations.



सद्यमेव जयते

## APPENDIX.

	LIST OF TA	BLES.	D
			Pages.
Statement A.		•••	277—291
- " B.	•	•••	292—295
" 0.			296—300
,, D.	List of middle school	ols in 1905	801
Table I		•••	302
,, II.	<b>-</b> -		303
,, 111.			
,, Ι∇.	Birth place, race, cas	te and occup	
" V.	Vital statistics	***	808
" VI.	Crop statistics	***	309-314
" VII.	Reserved forests	2.00	315
" VIII.	Outturn of forest pro	duce	316
" IX.	Prices of food staples	(S)	317 & 318
" X.	Criminal and civil ju	atice	319-332
" XI.	Finance-Receipts		383
" XII.	Miscellaneous land re	evenue	334
" XIII.	Land tenures		335—337
" XIV.	Excise		338340
" XV.	Income and expen	diture of	Local
•	Boards		341-348
" XVI.	Income and expendi	ture of Mu	nicipality
	and Union	•••	344
" XVII.	Strength of police for	orce	345
" XVIII.	Police stations and o		346
" XIX.	Statistics of jails	•••	347—849
" XX.	Education	•••	350 & 851
" XXI.	Educational finance	•••	352
, XXII.	Medical	•••	358
, XXIII.	Dispensaries	***	354357
**	•		



सद्यमेव जयते

## STATEMENT A. List of Tea Gardens.

	Name of garden.	Name of owners or Company to which it belongs.	Thana in which situated.	Approximate distance by road from subdivisional bead-quarters.	Ares on 31st De- cember 1904.	Area under toa (both mature and immature) on 31st December 1903.	Labour force on 31st Decem-
	1	6	3	4	5	9	-
	NORTH SYLHET Sobdivision.	यमेव व		Miles.	Acres.	Acres.	
-	Bagchara	The Consolidated Tea Jaintiapur and Lands Co., Ld.	Jaintispur	31	713	222	156
ei	Berjaa	. Ditto	Sadr	10.	788	205	241
က်	Brahmanchara	Mbd. Bekht, Karim Bakeh, Golam Reb- bani and Abdul Majid.	Ditto	4	329	130	43
<b>√i</b>	Cherragong including Fatebpur.	Cherragong includ- The Consolidated Tea Goyainghat ing Fatebpur. and Lands Co., Ld.	Goyainghat	10	872	336	534
ij	Chicknegu!	Babu Juwar Mohal	Ditto	<b>\$</b> 01	2,430	204	218
ė	Dawkergul	Lubba Tea Co., Ld   Kanairghat	Kaneirghat	9	 089 _	170	203

STATEMENT A.—contd. List of Tea Gardens.

Name of garden.	Name of owners or Company to which it belongs.	Thana in which situated.	Approximate distance by road from subdivi. sional head-quarters.	Ares on 31st De- cember 1904.	Area under tea (both mature and immature) on 31st December 1903.	Labour force on 31at Decem- ber 1903.
1	67	8	4	5	6	1
	यमेव	'n	Miles.	Acres.	Acres.	
NOBTE SYLHET SUBDITION—confd.	नपते जयते		\$\			
7. Galni	The Consolidated Tea	Goyainghat	12	1,368	97	89
8. Indanagar	Lubba Tea Co., Ld Fenchuganj	Fenchuganj	₹1 <b>2</b>	2,631	<u> </u>	<b>4</b> 68
9. Jaffang	The Consolidated Tea Goyainghat and Lands Co., Ld.	Goyainghat	88	1,910	1,072	1,350
10. Jaintia	Ditto	Jaintiapur	38	612	165	146
11. Kalagul	. Ditto	Sadr	o	1,378	429	463
12. Kewachara	Lakatura Tea Co., Ld,	Ditto	54	1,155	489	308

									<del></del> .				
210	633	\$23 	324	286	622	218	233	106		1,040	649	1,428	1,049
257	809	187	485	620	460	250	213	136		908	₹99	1,260	1,188
3,712	1,831	1,396	892	2,497	2,175	937	1,027	206		2,840	1,887	4,551	3,151
_ 	က		35	क्र	ଛ	*8	33	C4		<b>8</b>	នា	23	16
:	:	:	:	:	(						:	:	
Ditto	Ditto	Jaintiapar	Kanairghat	Sadr	Fenchuganj	Kanairghat	Ditto	Parkul		Kuchikandi	Ditto	Ditto	Ditte
North Sylbet Tea Co., Ld.	Lakatura Tea Co., Ld.	The Consolidated Tea	Lubba Tea Co., Ld Kanairghat	Sylbet Tea Co., Ld Sadr	Maurapur and Ani- Land Mortgage Bank Fenchaganj pur.	Lubba Tea Co., Ld	Ditto	Baba Baikuatha Chand- ra Gupta.	ते व	Mesers Aitchison, Alex, Milne and A. Odling.	Chandichara Tea Co., Ld.	Chapndur Tea Co., Ld.	Bharaura Tee and Messrs. McLeod & Co., Ld.
Khadimnagar	Lakatura	Lelakhal	Lubbachara	Malnichera	Maurapur and Ani-	Mulagul	Nunchara	Tarapur	HABIGANJ Schotveion.	Amo or Ghanesyam-	Chandichara	Chandpar	Daragaon
13.	14,	15.	16.	17.	18.	19.	20.	21.		<del>-</del> i	લં	erà	<b>→</b>

(a) Estimated

STATEMENT A.—contd. List of Tea Gardens.

1	Name of garden.	Name of owners or Company to which it belongs.	Thana in which situated.	Approximate distance by road from subdivi: sional head-quarters.	Ares on 31st De- cember 1904.	Area under tea (both mature and immature) on 31st December 1903.	Labour force on 31st Decem- ber 1903.
1 1	1	2	3	4	5	9	7
Ø	HABIGANJ Subdivision.—contd.	र्यापन ज		Milea.	Acres.	Астев.	
κi	5. Deundi	Messrs. R. L. Alston and J. E. Aird.	Machikandi	17	1,962	790	730
Ġ	6. Laichand	Mesers. R. L. Alston and M. H. Alston,	Ditto	12	2,000	636	720
.:	7. Leskarpur	Laskarpur Tea Co., Ld.	Ditto	19	3,090	756	288
œί	Parkul	Parkul Syndicate	Ditto	19	2,044	300	335
<b>ં</b>	Basidpur	Bharaura (Sylbet) Tea Co., Ld.	Ditto	16	4,310	1,328	1,323
10.	10. Bema	Imperial Tea Co., Ld.	Ditto	24	1,911	749	638

896	646		1,491	959	205	1,041	495	583	183	1,359	230
826	650		1,030	689	450	7,00	7,*00	555	316	823	328
4,025	1,562	,	3,624	3,096	1,974	~		5,313	1,393	3,042	1,359
8	ឌ		16	24	ä	14	15	3	17	10	27
:	:		<u>:</u>	:				:	i	:	<u> </u>
Madbabpur	Ditto		Kamalganj	Srimangal	Bajnagar	Srimangal	Ditto	Ditto	Bajnagar	Kamalganj	Hingejiya
Ditto	Teliapara Tea Co., Ld.		Alivagar Tea Co., Ld,	The Consolidated Tea Srimangal and Lands Co, Ld.	Moesrs, Macneill & Co. and Executors of late Moesrs, Davidson and Malet.	Bharaura (Sylhet) Tea Co., Ld.	Ditto	The Consolidated Tea and Lands Co., Ld.	Lubha Tea Co., Ld Bajnagar	Alinagar Tea Co	Messre, K. C. narrison, G. S. Beatson, H. A. Hurrison and others.
Surma	Teliapara	SOUTH SYLHET Bubdivision.	1. Alinagar	Amrailchara	Beremchal	Bharaura (North)	Do. (South)	Burmachara	Chandbhag	Chatlapur	Clevedon
11.	12.	<b>V2</b>	-	લં	<b>10</b>	<b>→</b>	νά	<b>&amp;</b>		ထင်	சு 36

(b) Includes figures for Huglichars.

STA FEMENT A.—contd. List of Tea Gardens.

	Name of garden.	Name of owners or Company to which it belongs.	Thans in which situated.	Approximate distance by road from arbdivicational head-quarters.	Area on 31st Ds- cember 1904.	Area under tea (both mature and inmuture) on 31st December , 1903.	Labour force on 31st Decem- ber 1903,
	1	82	8	4	5	. 9	1
-,	SOUTH SYLHET	भव ः		Miles.	Acres.	Асгея.	
20. 10.	SCEDIVISION—contd.	Dhelai Tea Co	Kemalganj	83	1,500	670	755
Ξ.	11. Foltsia	New Sylhet Tea Co	Hingajiya	33	2,865	1,100	1,510
12.	Fuskari	The Consolidated Tea	Matigaoj	22	9,878	490	433
13.	13. Gandichara	Ditto	Ditto	23	345	Not available	564
Ξ.	14. Gayasnagar	Mr. H. P. S. McMeekin. Maulavi Basar	Maulavi Basar	2	1,608	391	428
15.	15. Geripur	Meers, Andrew Yule & Co., W. Marillier, 'E. Wood and Dr. Le Franc.	Hingajiya	33	1,124	240	285

_			Ė		-   6	(d) Indiadae Games Con Contact	1.4) Indiades &			1
	1,903	1,120	1,362	16	:	Kamalganj	The Langia (Sylbet) Kamalganj Tea Co., Ld.	<u>:</u>	Kanibati	_
	445	Not available.	232	<b>54</b>	;	Hingsjiya.	Kaliti Tea Co., Ld Hingujiya	•	Kaliti	
	1,035	216	1,683	19	•	Ditto	Ditto	•	Kalighat	
	503	419	2,069(e)	11	:	Ditto	Ditto	:	24. Kakischara	
	852	569	Incinded in Fuskuri	53	3	Ditto	Ditto	:	Kajurichara	
	1,091	98	2,473	=		Srimangal	The Consolidated Tea and Lands Co., Ld.	:	Jagobara	
				YTHIS			Co., Ld.			
	1 590	1 200	3 670	16		Manlavi Bazar	Langla (Sylbet) Tea		Ita	
	167	694	Included in Ameril.	56	6	Srimsogal	The Consolidated Tea	:	Huglichara	
	1,129	942	2,118	15	:	Hingajiya	Chargola Tea Association, Ld.	:	Hingajiya	
	31	32	100	16	i	Rajuagar	Babu Surja Maui Das Rajuager	:	Barchara	
	387	285	572	77	ŧ	Hingajiya	The Consolidated Tea	:	Balaichara	
	618	655 Not available.	655	ន	:	Kamalganj	Babus Baikuntha Nath Kamalganj Swima, Bukhamaya Chaudhuri and Rasha- maya Chaudhuri.	:	10. Govinapur	

(d) Includes figures for Kajurichara, Puttischara, and Tiprachara.

# STATEMENT A.—contd. List of Tea Gardens.

Name of Garden.	Name of owners or Company to which it belongs.	Thens in which situated.	Approximate distance by road from subdivi- sional head-quarters.	Area on 31st De- cember 1904.	Area under tea (both mature and immature) on 31st December 1903.	Labour force on 31st Decem- ber 1903.
1	2	3	0	9	9	1
SOUTH SYLHET SUBDIVISION— contd.	यमेव व	ļŅ!	Miles.	Acres.	Acres.	
28. Kapnapahar	Messrs, H. B. Klugh, A. J. M. McLaughlin and D. Laing.	Eingajiya	90	1,082	345	350
29. Karmachara	Mr. Thomas McMeekin Kamelganj	Kamalganj	22	3,887	745	1,191
30. Lakhaichara (Lucki- chara).	The Consolidated Teasund Lands Co., Ld.	Srimengel	କ୍ଷ	271	Not available.	743
31. Langla	The Langla (Sylbet) Hingsjiya Tea Co., Ld.	Hingejiya	7	4,674	1,450	2,303
32. Luayoni	Mr. B. L. Alston	Ditto	12	1,200	400	425
33. Madlabpur	Mr. Thomas McMeekin   Kamelganj	Kamelganj	61	3,001	619	906

791	547	342	23	<b>408</b>	1,337	286	409	942	635	1,204	213
099	040	338	09	330	962	899	459	689	483	628	525
3,595	2,842	2,201	256	1,726	4,392	Included in Kakia-	Included in Fuskari.	Included in Burms.	chera. 2,317	2,240	2,000
6	ø,	90	92	80	83	18	83	25	36	10	21
:	:	:	:				1	- <del></del> -	:	-:	<u>.</u>
Srimengel	Kamalganj	8rimenge]	Bingajiya	Rajuager	Kamelganj	Srimangal	Ditto	Ditto	Hingsjiys.	Rajoagar	Hingajiya
Majdihi Tea Oo., Ld Brimangal	Mesrs, J. Peter and B. L. Alston.	Messr. C. E. Lane, M. Bigge, E. R. Hunt, R. Hunt and W. V. H. Cobbett.	Syed Ali Akbar Kband- Bingajiya kar.	Mre. Balfour	Mr. Thomas McMeekin	The Consolidated Tea	Ditto	Ditto	The Surma Valley Tea Co., Ld.	Rajnagar Tea Co., Ld.	Maulavi Ali Amjad Hingajiya Khan.
:	:	:	:	:	ŧ	i	į	:	i	:	i
M•5dihi	Mirtings	Mirzapur	Pullakandi	Parbatpur	Patruklinia	Phulchara	41. Puttiachara	Rajghat	Rojki	Bajoagar	45. Rangiachara
34.	35.	96.	37.	38.	33.	<b>.</b>	<b>‡</b>	42,	£.	4.	45.

# STATEMENT A.—confd. List of Tea Gardens.

Z S	Name of garden.	Name of owners or Company to which it belougs.	Thans in which situated.	Approximate distance hy road from subdivi-sional head-quarters.	Area on 31st De- cember 1904.	Area under tea (both mature and immature) on 31st December 1903.	Labour force on 31st Decem-
	1	2	60	4	2	9	7
SOT Subi	SOUTH SYLBET Subdivision—concid.	र्ग (०) यमेव ज		Miles,	Acres.	Асгев.	
46. Batna		[mperial Tea Co., Ld	Hingajiya	83	1,551	361	594
47. Sagarual		The Consolidated Tea	Ditto	30	1,564	630	812
48. Sh	samshernagar, in-	Shamehernagar, in- The Langla (Sylhet) Kamalganj cluding Buagichara Tea Co., Ld.	Kamalganj	15	3,674	1,550	2,173
49. B	Satgaon	Meesrs. J. Aitkin, J. Srimangal Lilhurne, J. Steel, R. H. Steel, H. Wat- con, J. Watson and T. H. Watson.	Srimangal	12	2,022	188	1,202

											_
333	604	303	587	264	310		624	469	535	670	
162	594	333	634	288	341		200	(a) $1,673$	412	594	
2,366	Included in Barms-	chars. 1,860	Included in Fuskuri.	1,256	1,223		2,831	1,127	1,748	1,804	-
34	75	18	98	13	115	100	83	30	98	35	
i	:	:	:	10			·	·	i	:	
Hingajiya.	Srimangal	Hingajiya	Srimangal	Rajuagar	Ditto		Patharkandi	Rataburi	Patharkandi	Ditto	
The Surma Valley Tes Hingajiya.	The Consolidated Teasnd Lands Co., Ld.	Ditto	Ditto	Meesra, H. S. Currie and Cecil Chapman and Rev. W. H. Chapman.	The Indeswar Tea and Trading Co., Ld.	मधने नथने	Mr. H. A. Brown Con- stable.	Chargola Tea Associ- Batabari	The Consolidated Tes Patharkandi and Lands Co., Ld.	Mesers. M. C. Nosd, Lewis and F. H. Nosd	
Shiilus	51. Shindurklan	Singoor or Degai-	Tiprachara	Udas	55. Uttarbhag	KARIMGANJ Subdivision.	1. Ademtila	Anipur	Baitakbal	Bhubirghat or Eve-	
50.	51.	52.	53.	54.	55.		<b></b>	લં	က	<b>√</b> i	

(a) Includes figures for thergola, Kalachara and Tarvinchara.

STATEMENT A .- could.

# List of Tea Gardens.

	Name of garden.	Name of owners or Company to which it belongs.	Thana in which situated.	Approximate distance by road from subdivi- sional liead-quarters.	Area on 31st De- cember 1904.	Area under tea (both mature and immature) on 31st December 1903.	Labour force on 31st Decem- ber 1903.
1	1	2	· 63	- C.22	9	9	7
<b>V</b> 2	KARIMGANJ Subdivision—contd.	प्रमेव ज	Ŋ	Miles.	Acres.	Acres.	
ĸi	5. Champabari	Puthni Tea Co., Ld Patharkundi	Patharkundi	25	1,326	643	533
6.	Chandkbira	Chandkhira Tea Co., Ld.	Ditto	54	1,019	392	519
7.	Chandnighat Bidyanagar.	s n d Raja G. C. Roy	Ratabari	:E	976	895	116
<b>∞</b>	Chargola	Chargola Tea Association, Ld.	Ditto	S <sub>S</sub>	1,675	Included ia Anipur	1,403
6	Dakbingul	Bupendra Sri Ghosh Jaldhub	Jaldhub	21	288	492	200
30.		Dhamai and Silghat Dhamai Tes Co., Ld	Ditto		4,110	922	808
11.	11. Eraligul	Brailgul Tea Co., Ld   Patharkandi	Patharkandi	17	1,324	492	774

569	1,162	379	294	808	:	1,150	453	1,140	241	880	404
427	Not available.	Incladed in Anipar	405	454	Not available.	\$22	352	594	204	675	<b>789</b>
1,326	1,943	Incladed	2,000	3,695	823	12,737	169	1,150	1,395	1,604	2,185
66	32	35	30	<b>4</b> 0	0	37	27	23	15	2	en en
:	:	•	•			i		) I	:	:	:
Ratabari	Patharkandi	Bataberi	Ditto	Ditto	Patharkandi	Ratabari	Patherkandi	Ditto	Jaldhub	Ratebari	Ditte
The Copsalidated Tes Ratabari and Lands' Co., Ld.	Batikhira Tea Co., Ld. Patharkandi	Chargola Ten Associ- Batabari ation, Ld.	Bharat Sawiti, Ld	The Consolidated Tea	Babus L. C. Dutta and Patharkandi P. K. Dutta,	Lalchars and Fanai East India and Ceylou Tea Co., Ld.	Lalkhira and Sona- Langai Valley Tea Co., kliira.	Ditto	Babus lewar Chandra Datta and Prasanna Kumar Datta.	Chargola Tea Associ- Ratabari ation, Ld.	Gast India and Geylon Tea Co., Ld.
Gambhirachara	Hatikhira	Kalachera	Kalinegar	Kekragul	17. Lakshmichara	Lalchars and Fanai	Lalkhira and Sona-kliira.	Langai Valley	Madanpur	Magurachara	Mukamchara
12	13.	14.	3	16.	17.	18.	헕	20.	21.	ន្ត 37	23.

# STATEMENT A-concid. List of Tea Gardens.

	Name of garden.	Name of owners or Company to which it belongs.	Thans in which situated.	Approximate distance by road from subdiviresional head-quarters.	Area on 31st De- cember 1904.	Area under tea (both mature and inmature) on 31st December 1903.	Labour force on 31st Decem- ber 1903.
1	1	8	က	4	5	9	L
ő	KARIMGANJ Surdivision—concid.	यमेव जय	1111	Miles.	Acres.	Acres.	
24.	24. Oliviachara .	The Consolidated Tea Batabari and Lands Co., Ld.	Batabari	40	824	310	470
<b>3</b> 2	25. Peplagul	Puthni Tes Co., Ld Patharkandi	Patharkandi	26	1,555	548	836
<b>3</b> 8	Puthai,	Ditto	Ditto	22	2,100	695	1,091
27.	Salgai	Hatikbira Tea Co., Ld.	Ditto	30	1,898	1,300	1,005
83	Semenbheg	Samanbhag Tea Co., Jaldhub	Jaldhub	27	6,612	882	1,263
8	Shabajpur	Baba Golak Chandra Das and others.	Jaldhub	15	2,450	230	8

_					
1,031	2,038	1,062	809	333	966
2,460 [Not available	1,500	550	909	Included in Anipur	56 50
2,460	3,325	1,377	1,627	765	283
<b>3</b> 6	28	35	27	30	<b>₹</b>
:	:	<u>.</u>	6		
Batabari	Tea Patharkandi	Ratabari	Jaldhub	Batabari	Patherkandi
ABOCi-	Tea	Ceylon	enzies, W. R. Major zie.	Associ-	ck and
Tes A	Bil	Ed.	C. M. rake, and and facken	ğ	O, Blac
Chargola ation Ld.	Sephinjuri Co., Ld.	East India and Ceylon Ratabari Tea Co., Ld.	Messie, C. Menzies, Jaldhub R. B. Drake, W. R. Walker and Major J. S. F. Mackenzie.	Chargela Tea Associ- Batabari ation, Ld.	Mr. G. M. O. Black and others.
Beli-	:	:	:	:	:
30. Singlachars and Bali- Chargola Tea Associ- Ratabari chara.	Sipbinjuri Bil	Sivachara	Bonarupa	34. Tarvinchara	35. Tilbbum
oi .	3.	32.	<b>8</b>	ಹ	3.

# STATEMENT B. List of Post Offices.

Name of Office,		Thana or Outpost and Pargana in which situated.
Adampur*	•••	Kamalganj, Adampur
Ajmiriganj 🐽	•••	Abidabad, Juar Baniyachung.
Akhalia	•••	Sylhet, Akhalia.
Assampara	•••	Muchikandi, Taraf.
Atgram	•••	Karimganj, Ichamati
Badarpur*	•••	Karimganj, Chapghat.
Bahubal	••.	Habiganj, Faizabad.
Balaganj <sup>e</sup>	• • •	Balaganj, Bualjur.
Bamai •••	0	Lakhai, Bamai.
Baniyachung		Baniyachung, Baniyachung.
Barlekha	***	Jaldhub, Pathariya.
Begumpur	8	Balaganj, Burunga.
Bejora		Madhabpur, Bejora.
Bekiteka	444	Habiganj, Taraf.
Bhangabazar	•••	Karimganj, Chapghat.
Bianibazar		Jaldhub, Panchakhanda Khurda.
Birasri	***	Karimganj, Kusiarkul.
Biswanath	•••	Biswanath, Bajubanbhag.
Bithangal	-36	Abidabad, Bithangal.
Bramandura		Habiganj, Uchail.
Chandkhira*	9 10	Patharkandi, Pratapgarh.
Chandpur Bagan*		Muchikandi, Taraf.
Oharkhai	•••	Jaldhub, Charkhai.
Chatali*	•••	Maulavi Bazar, Chatali.
Chhatak	•••	Chhatak, Chhatak.
Chhatiain	••	Habiganj, Bejora.
Dakhinbhag*	•••	Juldhuh, Pathariya.
Dhakadakshin	••	Golapganj, Dhakadakshin.
Dharmapasha	•••	Dharmapasha, Selbaras
Dighirpar	••	Maulavi Bazar, Chowalis.
Dirai Chandpur	•••	Dirai, Khalisa Betal.
Dullabchara*	•••	Patharkandi, Pratapgarh.
Dullabpur	•••	Maulavi Bazar, Chowalis.

FOOT-NOTE.—The offices marked with asterisks are combined post and telegraph offices and there is a departmental telegraph office at Sylhet town.

# STATEMENT B-contd. List of Post Offices.

Name of Office.		Thana or Outpost and Pargana in which situated.
Duttagram	•••	Kamalganj, Kanibati.
)warabazar*	•••	Chhatak, Dualia.
Fenchinganj*		Fenchugani, Mowrapur Howli.
Jankul		Jaldhub, Pathariya.
laurarang	•••	Sunamganj, Lakshansiri.
Jobindaganj	•••	Chhatak, Kauria
Jobindapur	•••	Habiganj, Kasimnagar.
lolapganj		Golapganj, Baraya.
Зорауа •••	••• }	Habiganj, Taraf.
Goyainghat	901	Goyaingliat, Dhargam
Habiganj*		Habiganj, Taraf.
Inathganj	de	Nabiganj, Agua.
Indeswar	(2.5)	Rajnagar, Indeswar.
Itakhola"	994	Madhabpur, Bejora.
Jaflang	68	Goyainghat, Jaffang.
Jagannathpur	•••	Jagannathpur, Atuajan Kismat.
Jaintiapur 🚥	• • •	Jaintiapur Jaintiapuriraj.
Jaldhub		Jaldhub, Bahadurpur,
Jalsuka	144	Abidabad, Jalsuka.
Jatua	, Pito	Chhatak, Jatua.
Kajaldhara*		Hingajiya, Langla.
Kaliarbhanga	112	Nabiganj, Baniyachung,
Kalighat*	. • •	Matiganj, Balisira
Kamalganj	***	Kamalganj, Bhanugach.
Kamarkhal	•••	Jagannathpur, Naigang.
Kanaibazar	•••	Patharkandi, Pratapgarh.
Kanairghat	•••	Kanairghat, Choura.
Karimganj*		Karimganj, Kusiarkul.
Khadimnagar	•••	Sylhet.
Kubajpur	***	Jagannathpur, Atuajan.
Kulaura	***	Hingajiya, Langla.
Kurua	•••	Balaganj, Kurua.
Lakhai	•••	Lakhai, Lakhai.
Lalabazar		Sylhet, Chaitanyanagar.
Lalchand	•••	Habiganj, Taraf.
Langla*	•••	Hingajiya, Langla.

FOOT-NOTE- The offices marked with asterisks are combined post and telegraph offices.

# STATEMENT B—contd. List of Post Offices.

Nam	e of Offic	e.	Thana or Outpost and Pargana in which situated.
Latu	•••	**,	Karimganj, Barapara
Lugaon	***	***	Nabiganj, Dinarpur.
Madhabpu	r •••	•••	Madhabpur, Bejora.
Madhyanag	gar .	•••	Dharmapasha, Bangsikunda
Manumuki	1 ***	•••	Maulavi Bazar, Satrasati Howli.
Maulavi Ba		•	Maulavi Bazar, Chowalis.
Moglabazai		001	Sylhet, Renga.
Muchikand		•••	Muchikandi, Taraf.
Mudna*		***	Lakhai, Lakhai.
Munshibaz	ar*	410	Maulavi Bazar, Bhanugach.
Nabiganj	14)	•••	Nabiganj Juar Baniyachung.
Narpati	***	60	Muchikandi, Taraf.
Nilambazaı		200	Karimganj, Deudi.
Pagla Pagla	•••	***	Sunamganj, Pagla. Babiganj, Taraf.
Pail	***	•••	Habiganj, Taraf
Pailgaon	745	100	Jagannathpur, Atuajan Kismat.
Patharkand	li*	•••	Patharkandi, Pratapgarh.
Pathariya	***	•••	Sunamganj, Khalisa Betal.
Phultola	•••	***	Hingajiya, Bhatera
Prithimpas	ha	2.0	Hingajiya, Langla.
Pukhura	***	***	Baniyachung, Baniyachung.
Putijari	***	44.	Habiganj, Putijuri.
Rainagar	***	***	Sylhet, Kashba Sylhet.
Rajaniganj	***	944	Hingajiya, Langla,
Rajnagar	***	***	Rajnagar, Shamshernagar.
Ratabari	•••	•••	Ratabari, Paldahar.
Bachna	***	•••	Dharmapasha, Khalisa Betal
Bagarpal	***	•••	Hingajiya, Langla.
Baistaganj*	***	***	Habiganj, Taraf.
Batgaon	***	••	Matiganj, Satgaon.
Satiajuri	•••	•••	Habiganj, Tatuf.
Shamsherge		•••	Matiganj, Satgaon.
Shamshern	agar"	***	Kamalgani, Shamshernagar.
Srigauri	***	•••	Karimgani Chapghat.
Brimangal	•••	80-	Matiganj, Balisira.
Bugbar	404	•=	Habiganj, Taraf.

FOOT-NOTE—The offices marked with asteriaks are combined post and telegraph offices.

# STATEMENT B-concld.

# List of Post Offices.

Name	of Office.		Thana or Outpost and Pargans in which situated.
Sujatpur Sukhair Sunamganj Syedpurbaza Sylhet Tahirpur Tajpur	••• ••• ••• •••	000 000 000 000 000	Habiganj, Juanshai. Dharmapasha. Sukhair. Sunamganj, Lakhansiri. Nabiganj, Agna. Sylhet town. Tahirpur, Laur. Balaganj, Dulali.

FOOT-NOTE-The offices marked with asterisks are combined post and telegraph offices.

सन्धमेव जयते

# STATEMENT C. List of Trade Centres.

Thana or Outpost.	Trade centres.	Thana or Outpost.	Trade centres.
SUNAMGANJ SUB-DN. Tahirpur	Badaghat Bazar, Sripur Bazar, Tahirpur,	SUNAMGANJ SUB-DN-concid. Ohhatak-concid.	Chaudhuri's Hat. Duhalia. Dwara Bazar. Him Chaudhuri's Hat
Dharmapasha	Biohna. Bir. Oharmapasha. Jayasri. Madhyanagar. Mahishbola. Paikarhati. Rajapur. Sanbari.		Imamgenj Hat. Jauar Hat. Gobindaganj, Jiapur. Kalaruka. Mangalpur. Marja. Nosbazar. Singchapair. Sonauta.
Dirai	Anandapur. Bara Matabpur, Charnarchar. Dirai. Gachia. Hushanpur, Rahutola. Ranarchar. Sajanpur. Saila. Syamarchar.	HABIGANJ SUB-DN. Bapiyachung and Abidabad.	AJMIRIGANJ. BANIYACHUNG. Rirat. Bithangal. Gunai. Ikram. Jalsuka. Kamalganj. Markhali. Pukhura.
Sunamganj	Jaikalaa. Jainagar. Pagla. Sachna. Sunamganj.	Lakhai	Sangar, Sujatpur, Rulla, Lakhai.
Jagannathpur	Budhrail. Hushanpur. Isakpur. Jogannathpur. Kamarkhul. Kaminipur. Keshabpur. Paligaon. Patkura. Rumapatipur. Rasulganj. Shibganj.	Madhabpur	Baghasura. Bejora Hat. Chenghar Basar. Chhatiain. Deogas. Dharmaghar. Harinkholar Bazar. Itakhola. Jagadishpur. Kalirhasar. WADHABPUB BAZAB. Mantala Bazar. Munshi Bazar.
Ohbatak	Ambari. Baruigaon.		Surmachara Garden. Teliapara Garden.

# STATEMENT C-contd.

Thans or Out-	Trade centres.	Thana or Outpost.	Trade centres.
HABIGANJ SUB-DN-concid.		NORTH SYLHET SUB. DN—contd.	
Habiganj	Bahubal, Bekiteka. Daudnagar, HABIGANJ. Mashajan. Mirpur, Nandanpur, Pail, Purikhola. Putijuri. Saistaganj. Sarkarer Bazar Shahji Bazar. Sughar. Tungeewar. Amu. Assampara. Basirganj. Chandbhanga. Chandbur. Chunarughat. Daragaon. Deundi. Gargaria. Gaziganj. Habibulla. Lalchand. Laskarpur. Muchikandi. Parkul. Rajabazar. Remachara. Sakir Mahmud.	Biswanath—concld.  Balaganj  Sylhet  Fenchuganj	Habrar Bazar. Kaliganj. Kamal Bazar. Lamakazi Hazar. Mufti Bazar. Pargana Bazar. Rajnganj. BALAGANJ. Burnuga Bazar. Dewan Bezar. Goala Bazar. Goala Bazar. Khankar Bazar. Mangal Chandir Bazar. Muktarpur Bazar. Noabazar or Umarpur Bazar. Parganar Bazar on Dakshiner Bazar Purkayasther Bazar Sarkar Bazar. Thanar Bazar. Akhalia. Sylhet Town. Fenchuganj. Ghilachara known as Dewilband Bazar. Indanagar known as
	Gopla. Inathganj. Khagaura. NABIGANJ. Saidpur. Shibganj.		Chaudhuri Bazar. Kayasthagaon known as Bialia- bazar. Kotalpur known as Sen Bazar.
orth sychet sub-dn.			Binnakandi. Chailakhel. Garo.
	Amtail. Bairagi Bazar. Biewanath.		Goyain. Haripur. Joga Bahar Haor. Kohaighar.

# STATEMENT C-contd.

Thana or Outpost.	Trade centres.	Thana or Outpost.	Trade centres.
NORTH SYLHET SUB-DN-concid.		SOUTH SYLHET SUB-DN-contd.	<del></del>
Goyainghat— concld.	Manikganj Bazar. Mitiri Mahal (Salutikar). NIJPAT. Panoh Hatikhel. Jaflung Garden. Panichara. Sarufaud.	Maulavi Bazar— oonold.	Dhipir Bazar in village Marukuna. Dighirpar in village Atgaon. Durgaganj in village Goalnagar known as Gayghar. Fakirer Basar in village Damia.
Golapganj	Baiyar Bazar, Chandarpur Bazar, Chandhuri Bazar, Golapganj Bazar, Kurer Bazar, Puran Baiyar Bazar, Purbabhag Bazar, Purkayasther Bazar Rakhalganj Bazar, Sanapatir Bazar, THAKURBARI BAZAR,		Gobindapur iu village llughar. Gopinathganj in village Shatia. Kalekhar Bazar in Nij Athangiri. Kasir Bazar iu village Bekamura. Madanganj in village Mutukpur. Manumukh. MAULAVI BAZAR. Nayabazar in village
Kanairghat	Aghbatia. Bhabaniganj. Birdhal. Chanderhat (Fatebganj.) Chatal Bazar. Gaobbari. Kanairghat. Lalakhal.	जयते	Kamalpur. Shamsherganj in village Daulatpur. Sarkar Bazar in village Sadhuhati. Shibganj in village Damia. Syam Roy's Bazar in village Barman.
SOUTH SYLUE	Manikganj. Mukiganj. (Jhingabari.) Mukgul. Natanpur. Rajaganj. Sharukerhat.	Matiganj	Bhairab Basar, Bowlasir, Jibanganj, Kakiachara, Kulapur, Gosain'a Basar, Matiganj, Itajar Basar, Sindurkhan,
SUB-DN.  Maulavi Bazar		ł	Srimangal.  Baburbazar. Bagiohar Bazar. Bhairabganj. Ghangor Hat. Bhater Bazar. Chaudhuri's Bazar.

# STATEMENT C-contd.

Thans or Out.	Trade centres.	Thana or Out- post.	Trade centres
80UTH SYLHET SUB-DN—contd.		SOUTH SYLHET SUB-DN-concid.	
Rajnagar—conold.	Dewandighirpar Ghargaon, Ghoser Buzar, Kadamhata, Kankapan, Rajkrishna Basar, Saheber Basar, Sarkarer Basar, Sonatola Basar, Tarapasha.	Kamalganj— oonold. Hingajiya	Tulsidasir or Joffar Bazar (Madhab- pur.) Bhatera, Chaudhurir Bazar, Fulertal, Hingajiya, Kajaldhara, Kajaldhara, Katarkona,
Kamalganj	Adiachara Garden. Alinagar do. Babur Basar (Kamarteki.) Babur Basar (Srinathpur.) Bade Ubhahatar Basar. Bairagir Bazar. Dighirparer Bazar.	KARIMGANJ SUB-DN.	Kaukapan. Kulaura. Lalbag. Langla Garden, Rabirbazar. Rangiohara Garden, Sakaband.
	(Brindaban pur) Dourachara Gurden, Ghater Buzar (Dharmapur) Heringar Bazar, Kamalganj Bazar, Kanihati Garden, Katabil Garden, Kurmachara Garden Madanpur Garden Madhapur Go. Mahalarparer Bazar	Karimganj	Babur Bazar. Bachlar ", Badarpur ", Bhanga ", Bholanath ", Biabain Bazar (New) Do, (Old) Bidyanagar. Chadnighat Bazar. Chapre. Chagli.
	(Srigar.) Mirtinga Garden. Munshi Bazar. Pathariya Garden Ranir Buzar. Salimullar Bazar (Srinathpur. Bhanugach.) Shamshernagar Garden. Sarkarer Razar (Madhabpur.) fetoigaon Bazar. Tilar Bazar or Kanaidasir Bazar		Dattapur. Durgarbazar. Ghoramara Laskar's Bazar. Kachuamukh. Kalibari Bazar. Kalibagar. Kalinagar. Kapimganj. Kazirkhalerparer Bazar. Khalar Bazar. Kuchkhauri Bazar. Lakhir Bazar.

# STATEMENT C-concld.

Thana or Outpost.	Trade centres.	Thana or Out- post.	Trade centres.
KARIMGANJ SUB-DNcontd.		KARIMGANJ SUB-DNconcld	
Karimganj— conold.	Mirerbasar. Miyakhali. Miyar Bazar. Manshi Bazar. Nilambazar. Noabazar. Puran Bazar. Ratabari. Ratanganj. Sarupganj. Shahaja Bazar. Shaha Jaluer Bazar Srigauri Bazar. Srikona, Suranandapur Bazar.	Jaldhub	Bag Prachanda Khan's Bazar. Bairagir ,, Barlekha. Barnir liazar. Bholadahar. Biani Bazar. Biohra ,, Bohalir Bazar. Charia ,, Churkhai. Dakhingul Garden. Daser Bazar. Dhamai Garden. Dubager Bazar.
Ratabari and Patharkandi	Adam Tila Garden. Anipur Garden. Audhan Bazar. Babur Bazar. Babur Bazar. Baitakhal Garden. Balichara Bazar. Barnail. Chandkhira Garden. Chargola Eraligul Eve Tila Garden. Isaganj Kanair-Bazar. Langai Garden. Medli Noabazar. Parganar Basar. PATHARKANDI. Puthini Garden. Salgai Tilbhum	जयत	Fakirer Gajbhag Garden, Gaigkul. Ghagur Basar. Gogra, Gopal Roy's Basar. Jaldhub, Kakura Basar. Kadibari ,, Kamalar ,, Kamongu's Basar. Kathaltoli. Miyakhanir Basar. Munshirkhalparer Basar. Pakhiala. Radhar Basar. Radhar Basar. Rajar ,, Ramdha ,, Saleswar , Shabajpur Basar.
	Abhangir Bazar. Afisher Ajimganj Ajingar ,,		Shibganj Sonarupa Garden, Sujanagar. Talimpur, Feradaler Bazar,

# STATEMENT D. List of Middle Schools in 1905.

## NAMES OF SCHOOL.

# NAMES OF SCHOOL.

# North Sylket Subdivision.

Akhalia M. E.
Balaganj M. V.
Begumpur (Sarat Sundari M. E.
School).
Burunga M. V.
Dattaran M. E. (Dhakadakshin)
Jaintia M. V.
Kanairghat M. E.
Mangalchandi M. E.
Moglabszar M. E.
Naikhai M. V.
Rankeli M. E.
Sylhot town (Girish M. E. School)
1, (Model Girl's M. V, School)

# Sunamgung Subdivision.

Brakmanjhulia M. E.
Chhatak M. E.
Duhaliya M. E.
Jotna M. V.
Kubajpur (Lalchand M. E. School)
Madhyanagar M. E.
Pngla M. E.
Rajanagar M. E.
Sunamganj (Raj Gobinda M. V.
School)

# Habiganj Subdivision.

Agna (Uday Gobinda M. E. School)
Ajmiriganj M. E.
Bamai (Ramdhan M. E. School)
Baniyachung (Loknath M. E. School)
Bejora M. E.
Gobindapur M. V.
Gopaya M. E.
Habiganj M. V.
Imauaganj (Baidyanath M. E. School)

# Habiganj Subdivision—concld.

Jalsuka (Krishna Gobindo M. E. School)
Machulia M. V.
Mirasi M. E.
Mirpur (Ram Gopal M. E School)
Nabiganj M. E.
Putijuri M. E.
Rajarbazar M. V.
Rarisat M. E.
Saistaganj M. E.

# South Sylhet Subdivision.

Bhatera M. E.
Bhunabir M. E.
Kamalganj M. E.
Maulavi Bazar M. V.
Munshi Bazar (Kali Prosad M. E.
School)
Panchgaon (Kamal Charan M. E.
School)
Prithimpasha (Ali Amjad M. E.
School)
Srimangal (Victoria M. E. School)
Tengra (Porteous M. E. School)

# Khrimganj Subdivision.

Agiaram (Vishnupriya M. E. School)
Bhanga M. E.
Bianibazar (Panchakhanda M. E.
School)
Biraeri M. E.
Dhakauttor M. V.
Karimganj (Tilak Chand M. V.
School)
Latu (Baikunta Chandra M. E.
School)
Lauta M. E.
Nilambazar M. E.
Pathariya M. E.

TABLE I.
Rainfall.

The number of years for which the average has been calculated is shewn below the name of each station.

				Avera	GE RAINI	PALL IN	INCH ES.	
	)NTH8.		Funam- ganj. (22)	8ylhet. (47)	Karim- ganj. (22)	Langla.	Maulavi Bazar. (18)	Habi- ganj. (22)
January	<b></b>		0.49	0.37	0.57	0.28	0.39	0.34
February	•••	•••	1.17	1.48	1.67	1.25	1.81	1.27
March	•••	•••	6.14	6.25	10.74	5.83	5.86	5 <b>-6</b> 8
<b>≜</b> pril	•••	•••	10.09	13.92	19·16	10-10	9 03	8:04
May	•••	•••	21 19	21 89	24-19	18-29	18:85	16.61
June		•••	89· <b>6</b> 0	32-17	30·5 <b>5</b>	20.63	18-97	18.66
July	•••	•••	43-44	25.39	22.48	14.24	16.28	14:17
August	•••	•••	48.94	25.39	22.57	14.36	14.74	12.73
Beptember	•••		31.74	20.55	¹ <b>8·9</b> 0	13:04	12.18	11:81
October	1 <b>tu</b>		8.07	7•90	7.74	5.75	5.65	4.84
November	•••		0.62	1.12	1.06	0.98	1.07	0.61
December	•••	•••	0.18	0.27	0.72	0.38	0.40	0.30
Total c	of year		209-68	156-64	160.25	105.50	104·18	94.51

TABLE II.

Distribution of Population.

THANA,	Population in 1901.	Population in 1891.	Difference-	Area in square miles,	Popula- tion per square miles.	Number of persons censused on tea gardens.
Sadr	241 811	255,064	- 13,253	6 4	400	6,738
Kanairghat*	79,677	82,960	-3,283	229	348	6,555
Balaganj	141,989	144,317	-2,328	222	6 <b>4</b> 0	*******
Sanamganj	118,088	107,531	+5,557	431	262	*******
Chhatak	90,683	88,706	+1,977	257	853	•••••
Dirai	151,020	144,028	+ 6,992	484	312	*******
Diarmapasha )	78,961	73,116	+5,845	821	246	
Habiganj	214,710	198,716	+15,994	355	605	16,021
Banlyashung	130,198	116,560	+ 13 638	264	493	•••••
Madhabpur	119,153	108,037	+11,118	183	651	2,841
Nabiganj† -	PO,940	81,279	+9,661	150	606	*******
Moulavi Bazat†	276,592	267,837	+8,755	580	477	51,239
Hingajiya	102,566	101,804	+782	260	394	18,605
Karimgan j	281,565	259,237	+22,328	797	353	87,393
Jaldhub	128,895	125,401	+3,494	<b>15</b> 1	614	5,484
Total district	2,241,848	2,154,593	+87,255	5,388‡	416	144,876

<sup>\*</sup> The outpost Goyainght, which in 1891 was under the Kanairghat thana, has been transferred to the Sadr thana. The figures for 1891 have been corrected.

<sup>†</sup> Hauli Satrasati pargana, which in 1891 contained 4,263 persons, has since been transferred to the Manlavi Bazar thans. The figures for 1891 for these two thanse have been corrected accordingly.

for these two thanse have been corrected accordingly.

† The total area of the district is probably about 5,435 squaremiles but the Survey Department are quable to guarantee absolute accuracy in a matter of this kind.

# TABLE III. General statistics of population.

							•	,						
PARTIOULARS.	.Bs.	North Bylhet Subdivision,	BUBDIVISION.	BUNAMGANJ Subdivision	GANJ ISION.	HABIGANG Subdivisio	HABIGAM, BUBDIVISION.	SOUTH SYLHET SUBBIVISION.	INTERT ISTON.	KARIMGANJ Subdivigion	Karimganj Subdivigion.	Tor	TOTAL DISTRICT.	F.
		Haloe.	Peros.	M a les	Fems.	¥ n les.	Fems.	Meles.	Fems.	Males.	Fems.	Persons.	Maler	Fems.
-		27	93	-	و	•	2	80	8	92	=	12	n	=
Population—				1	1		-	É						
		25.23	229 230,246,490 236,851	TEUR	230,030 203,732 319,149 194,232 382,560		253,290] 276,599 253,290] 251,302	191,318 187,875 18 318,477	191,318 187,940 187,875 181,760 318,477		195,134 189,504 343,421	2,241,848 2,154,593 1,969,009	ج ب	1,100,789
			111,268	rogs	2 2 3	To Car		265,	69	<b>3</b> 00,00 <b>0</b>	8	1,719,539	880,330	839,209
VARIATION-		18.61		10.881	6 Eng. 110 891 19 400 125 119 1-95 507	+25.112	1.9% 907					2		
1881-1891 1872-1881	::1			+30,821	821 748	+26,803	803	+61,164 +62,608	10.00 go	70,012 712,947 712,016 54 741,217 08 743,421	17 72	+185,584	+101,153	+47,133 +84,431 +130,016
1901.													-	
RELIGION							_							
Total Hindus	:	17,923		104,235	90,085	117,592	129,827	115,378	115,481	108,948	106,394	1,049,248	533,975	
Baktita			20,677					1,314					160,173	153,349
Muhammadans	: : : :	_	_	=	=	14	Ξ	74,718	ξ.	ă	74,77		600,680	
Total Oliristissa	::	<b>-</b>	28.	# 95 40 40 40 40 40 40 40 40 40 40 40 40 40	2	P.	7	1,007	86	1,116	1,102	≓	468	5,650
Anglican Communion		12		-	:	7	22				2	133		<b>3</b>
Roman Catholia	: :			•		-	: :	ā •	•	<b>a</b> <u>g</u>	<u> </u>			5.0
Other religious	: :	<u> </u>			- ::	=	=	3	ਭ	200	3		156	3 \$

	ga b	******	1 9
412,948 464,798 333,647	4,996 111 1,096,937	1,017,348 50,846 4,568 4,866 14,865 14,371	d from th
665,093 436,378 40,594	88,761 6,846 1,048,092	1,061,306 51,677 4,607 5,023 14,386	transferre
1,077,436 850,171 374,241	62,057 6,968 3,144,339	2,068,549 106,622 9,908 2,908 26,667	Taber 1891
75,441 86,149 41,779	713 14 201,650	172,978 19,767 1,390 6,618	in Bepte
120,490 80,398 7,193	18,329 1,017 190,540	177,539 20,563 1,893 6,827	sales, was
63,830 82,886 41,634	13,124 0665 376 29 177,646 187,108	150,998 22,027 1,866 2,488 5,399	8,150 fear
106,277 77,036 8,006	13,124 976 177,646	164,396 23,985 2,864 2,486 5,414	les and
99,206 117,3\$2 60,073	1,418 2,2 2,1,272	268,231 4,306 1,312 214 1,092	2,112 m
157,659 111,487 9,256	26.293 1,456 255,664	268,147 5,398 1,350 275 1,004	lation of
82,123 79,140 41,643	432	236.603 202,146 2,063 380 36 11	a popa
139,970 88,757 8,003	13,219 435 663 7 216,567 202,284	226.602 2.063 2.063 3.064 3.064	containe
92,244 89,481 48,583	1,068 87 829,052	222,991 3,456 680 716	1881 u
141,397 82,694 8.187	\$0,796 1,803 \$10,835	234.530 4,688 790 739	which
: # :	:::	:::::	Satragasti,
:::	ngali Slish	:::1;	Haufi S
Unparried Married Widowed	Liferake in Bengalt Liferake in Boglish Liferake	LANGUAGES SPOKER— Bengali Essten Bindi Types Oriya Manipuri	Pargana Hauli Setressti, which in 1891 contained a population of 2,112 maies and 2,150 females, was in September 1891 transferred from the

TABLE IV.
Birth place, race, caste, and occupation.

		NORTH SYLHET SUBDIVISION.	ORTH STLUET SUBDIVISION.	BUNAMBANJ BUBDIVISION	FOANS TSION.	HABIGANJ Subdivision		SOUTH SYLER SUBDIVISION	SYLHRY VISION.	Karimganj Surdivision	GANJ ISTON.	TOT	TOTAL DISTRICT.	ior.
		Males.	Fems.	Males.	Fems.	Males.	Fems.	Males.	Fems.	Males.	Fems.	Persons.	Males,	Fems.
1		64	*	•	us	8	~	8	a	92	=	12	13	77
BIRTH PLACE-														
Born in the district	:	224,313	64	218,921	197,068	280,801	259.691	161,051	167,778	186.104	182.137	2.071.682	1,061,190,1	.020,492
" other parts of Province	8	856	713	90	510	276	276	438	625	1,050	83	5.271	2,770	109
" " Obota Nagong	maddir •	1,514	Ų.	233	13	3,362	3,378	6.609	6.067	1.537	1.713	24.697	11,945	13.682
" " other parts of Bengal	: :	2,875	ar.	1,291	77	3.176	1,709	6,867	7,123	2,682	1.631	29,697	16,891	12,806
2	:	1,508	ù	1,068	288	8.208	1,464	9,959	9,586	12.236	12,067	61.068	26,980	24,038
alsewhere	::	877	a 3	158	9	1,042	1,005	4,733	8,787	1,395	1,069	13,952	7,847	6,106
BACE & CASTE.			12		1	ý	THE PERSON NAMED IN			•				
Ahir	:	20	À	P		182	136	833	610	1,764	1,68	5.093		2,337
Baldya	:	523		163	158	444	457	603	671	240	203	3,798		1,834
Ranri	:	900	990		-	1,113	1,122	4,550	4,470	1,978	1,860	16,346		900,0
Bhar	:	855		17	•	76.	200	2,03	100	13.5	200	, o		707
Bhuinmall	: :	3,265	3,189	917	615	1,948	1.932	9,046	9,367	6,388	5,517	41.184	20,684	20,620
Bhaise	:	427	458	:	:	445	100	2.121	1,963	632	099	7,006		3,481
Bratman	:	4 633	428	. 0	900	994	537	011.1	2,2	27.0	208	5.078	•	3,618
Ohemar	: :	270	228	164	112	185	776	5.038	5,129	695	3.162	19 759	''	9.407
Halws Das, 8	ndra and		;	-			:	-						1
Sudra Das	:	12,654	12,429	32,875	က	16,652	17,320	10,338	10,415	10,502	11,000	_	82,831	81,442
Dhoba	:	283	833	198		1,987	2,117	1,718	1,781	1,070	1,248	12,524	6,110	6.414
Diobi	:	1,867	1,354	7,439		293	426	88	1,322	963	174		0,759	<b>₹</b> ,225
Dam Press	:	404	200	200		61.6	613	3,047	3,503	200	273		4.4.4	5,189
Burasian	:	77.	, .	2,12		5 6 K	2,42,4	, ·	60,00	502.61	70,04		991'/5	90.078
Regionage (a)	:	76	•	:	:	•	14	197	:	1	-	6	94.6	
Canak	: ;	362	345	510	116	1.281	1.327	89	415	226	230	5.616	2.847	2.763
Goals	:	720	808	8	163	2,391	2,393	2,838	2,936	976	757	14,137	7,283	6.844
Jugi	<del>·</del>	7,547	7,667	<b>2</b> ,966	5,403	10,573	11,413	8,068	7,796	7,459	7,8 0	78,915	29,613	508.08

(a) Includes allied races

TABLE V. Vital statistics.

	Population under	Ratio of births	Ratio of deaths	Rat	to of deaths	per mille f	rom.
Year.	registration in 1901.	per mille.	per mille.	Cholers.	Small-pox.	Fever.	Bowel com- plaints.
1901	2,241,848	36-49	28-89	1.25	1·13	13.08	1.80
1902	2,241,848	37·15	33.88	8.93	2.34	12.65	1.95
1903	2,241,848	38·16	27·12	1.03	0.15	11.30	1.73
1904	2,241,848	37.73	<b>27·</b> 60	1.64	U·01	10.47	1.82
1905		É					
1906							
1907			MIN	M			
1908		4					
1909			सन्यमेव	जयते जयते			
1910							
1911							i
1912			ļ				
						i	
	11				<u> </u>	J	

TABLE VI.

PARTICULARS.		1900-01.	1901-02.	1902-08.	1 <b>9</b> 03-04.	1904-05.	1905-06.
		Acres.	Acres.	A cree.	Acres	A Ozea.	A Cres.
Total cropped area	•••	2,504,058	2,585,834	2,564,609	2,493,020		
Rice	•••	1,966,930	2,071,815	2,075,650	2,061,000	 	1
Mustard	•••	88,433	38,911	38,767	37,000		[
Sugarcane	•••	11,346	14,414	14,565	15,000	l	•
Pulses 🚥	•••	5,582	2,857	3,808	8,000		
Linreed	•••	68,340	69,029	68,598	69,000		1
Jute	•••	8,000	9,205	7,400	9,200		1
All other crops	•••	410,427	359,103	355,821	298,820		ł

		1906-07.	1907-08.	<b>1908</b> -09.	1909-10.	1910-11.	1911-12.
		Acres.	A0108.	Acres.	Acres.	Acres.	Acres.
Total cropped area			G-A-J-A	41421	ļ		
Rice					ļ		
Musterd	•••			<u>}</u>			}
Sugaronne	•••			<u> </u>	}		
Pulsen	•••		1		Ì	1	1
Lingeed			ĺ				
Jute	•••		}	}			
All other drops	•••				1	}	

Note—So far as these figures relate to the permanently settled area, they are estimates only.

# TABLE VI-contd.

# Crop statistics.

	1901.	1902.	1903.	1904.	1905.	1906.
TEA. NORTH SYLHET SUBDIVISION. Number of gardens	25	23	22	22		
Area in acres	18,961	18,190	18,613	26,711		}
Area in acres under plant	8.002	7,831	7,475	7,684		
Outturn of manufac- tured tes in lbs	2,779,283	2,411,859	2,862,299	2,391,570		
Labour force	8,331	8,123	7,734	7,211		
Labourers including dependents imported during the year(a)	238		99	202		
		72148	44			
	1907.	1908.	1909,	1910	1911.	1912.
TEA. NORTH SYLHET SUBDIVISION. Number of gardens Area in acres under plant Outtorn of manufactured tea in lbs Labour force Labourers including		सन्धमेव	यने			
dependents imported during the year(a)	1	1	1	1 1		1

<sup>(</sup>a) From 1903 immigration statistics relate to period from lat July to 30th June.

Table VI—contd. Crop statistics.

Particulars.	1901.	1902.	1903,	1904.	1905.	1906
HABIGANJ SUBDIVISION.						
Number of gardens	13	13	12	12		
Area in acres	27,113	29,615	32,310	35,818		
Area in acres under plant	9,890	9,952	9,931	9,990		
outturn of manufac- tured tea in lbs	3,831,869	4,045,517	4 ,787,124	5,278,538		
abour force	11,573	11,958	9,322	9,505		
shourers including dependents imported during the year(a)	385	1/1	247	170		
SOUTH SYLHET SUBDIVISION.	1	सन्यमेव व	्रायन यन			
sumber of gardens	58	57	55	55		
Area in acres	89,839	90,568	90,679	98,225		
rea in acres under plant	33,333	33,090	33,248	33,410		
outturn of manufac- tured tes in lbs.	14,855,519	14,053,105	16,359,878	17,165,522		
Labour force	50,168	46,589	89,913	38,555		}
abouters including dependents imported during the year(a)	1,178	 	1,560	1,498		

<sup>(</sup>a) From 1903 immigration statistics relate to period from 1st July to 30th June.

Table VI—contd.

Crop statistics.

	CF	op sta	(19/169			
Particulars.	1907.	1908.	1909,	1910.	1911.	1912.
HABIGANJ SUBDIVISION.	1					
Number of gardens			}	}	}	
Area la acres		entra e				
Ares in acres under plant	É					
Outturn of manufac- tured tea in lbs	6					
Labour force		W 1000	14			
Labourers including dependents imported during the year(2)	(	!/ ! ( \				
BOUTH SYLHET SUBDIVISION.		सन्यमव	गयन			
Number of gardens		ļ				
Area in acres						
Area in acres under plant						
Outturn of manufac- tured tea in lbs				}		
Labour force						
Labourers including dependents imported during the year(a)						
Į		}		<u> </u>	<u> </u>	

<sup>(</sup>a) From 1903 immigration statistics relate to period from 1st July to 30th June.

Table VI-contd. Crop statistics.

Partioulars.	1901.	1902.	1903,	1904.	1905.	1906.
KARIMGANJ BUBDIVISION.						
Number of gardens	36	36	85	35		
Area in acres	46,507	49,595	50,005	49,066		
Area in acres under plant	21,063	21,036	22,886	21,413		
Outturn of manufac- tured tea in lbs	9,811,139	11,568,622	13,048,187	14,002,735		
Labour force	34,270	29,796	22,825	24,126	ļ	
Labourers including dependents imported during the year(a)	<b>1,</b> 196		1,364	907		
TOTAL DISTRICT.	1	calus)				
Number of gardens	132	129	124	124		
Area in acres	182,420	187,968	191,607	207,820		
Area in acros   Euro- peans. under plant   Held by Natives.	68,279 4,009	68,149 8,760	69,527 <b>4</b> ,013	72,497		
Outturn of manufac- tured tes in lbs	31,277,810	32,079,103	37,007,488	38,838,365		
Labour force	104,343	96,466	79,794	79,397		
Labourers including dependents imported during the year(a)	2, <del>94</del> 7	(6)	8,270	2 777		

<sup>(</sup>a) From 1903 immigration statistics relate to period from let July to 30th June.
(b) Figures not available.

# Table VI—concld. Crop statistics.

Particulars.	1907.	1908.	1909.	1910.	1911.	1912.
KARIMGANJ SUBDIVISION.						
Number of gardens						
Area in acres		COURSE.				
Area in acres under plant	E	1128	223		}	
Outturn of manufac- tured tea in lbs	6					
Labour force	B		<i>29</i>			
Labourers including dependents imported during the year(a)  TOTAL DISTRICT.	Ó					
Number of gardens		प्रयागेत ज	तान प्रते	1		
Area in acres		1-4-1-1-1			ŀ	
Area in acres   Held by Euro-peans   Held by   Natives.						
outturn of manufac- tured tes in lbs		}				
abour force	1		}	}	1	
dependents imported during the year(a)						

<sup>(</sup>a) From 1903 immigration statistics relate to period from 1st July to 30th June.

# TABLE VII. Reserved Forests.

Name of reserve.   Square   Locatis.   1900-01, 1901-02, 1902-03, 1903-04, 1906-07, 1907-08, 1908-09			Ares in	Oberacter of						BECEIPTS.	PTS.					
80 Mixed evect. 16,223 10,863 7,346 Ba.	<b>MADTY</b> E		square milee.	forests.	1900-01	1901-02	1902-03.	1903-04.	1904-05.	1905-06.	1906-07.	907-08.	1908-09	1909-10.	1910-11.	1911-12.
280 Mixed everther the strength of the strengt					B.	Bs.	lls.	Ba	点	á	ä	<b>88</b>	Be	ßå,	Ke	#
growth, causes and greepers a bund ant, interpersed areas. The predominate Champers are Champers	ı	:	38	Mixed ever- green forest, dense under-		16,523	10,963	7,346	8							
and the terminal of the control of t				growth, canes and creepers abundant,			1									
Ing species are Cham. Poun, Rosa. Poun, Ro	:	;	2	interpersed with swampy areas. The	यमेव	1,331	1,184	668		Fire						
Ping, Jam &co.				ing species are Cham, Poma, Rota Jarol	जयन					3						
				Ping, Jam &c.	1	5		9	1							
								_			-					·

TABLE VIII.

Outturn of timber and fuel and value of minor lorest produce.	noer a	na ra	ei an	a var	ne o		JOE	OPE	st pr	npo	S	1
DETAILS.	1900-01.	1901-02.	1902-03.	1902-04. 1904-05, 1905-06, 1905-07, 1907-09, 1903-09, 1909-10, 1910-11, 1911-12,	1904-05.	1906-06.	1906-07.	1967-08.	1903-09,	1909-10.	1910-11.	1911-12.
BESERVED FOREST8-												
Area in square miles	103	103	103	103								
Outturn (Government and purchasers only)-	80 27				4	<del></del> -						
Timber (0. ft.)	.) 36,110	83,302	48,584	50,157	3							
Fuel (c. ft.)	œ	204	88	198		600						
UNCLASSED STATE PORESTS-	এ ল	93)	1		[ ]	win.						
Area in square miles	211	136	179	177								
Ontturn (Government and purchasers only)	E	1	à.	Ì	3							
Timber (0, ft.)	.) 42,476	39,427	72,732	100,810			·-					
Fuel (c. fk.)	.) 153,449	137,500	184.594	165,463								
	<b>a</b> i	Br	Rg	Ra.	. B8	B3.	88	B.	B.	B3.	В8.	ä
Forest receipts	130'69	69,424	060'89	70,425								
Forest expanditure	17.069	31,966	22,781	20,637								
Burplus or deficit	+41,973	+37,458	+45,309	+19,788								
		_	_	_	_				_	_	_	

ł	ļ	Prices	Prices of food staples in seers obtainable per	Sta	uple	i sa	n S	eer	s ok	itai	nak	le	per	2	rupee.	ë.			
,				έã -	TEET	STLEET TOWN.		SUNAN	SUNAMGANJ,		HABI	HABIGANJ.		FAULA	BAULAVI BAZAR;	ZAR;	KAB	KARINGANJ.	2
!	:			eoir domaioù	Common rice.	toloditeM	.telediteM	Common rios.	Salb.	Common rice.	- <del></del> -	,41a8	Matikalsi.	Common rice.	.stag	Metikelei.	Common rice.	Salt.	Matikalai.
1880	2nd week	2nd week of February	:	:	74	84 1	16	- <u>-</u> -	:	:	<u> </u>		  :		:	:	:	:	:
<u> </u>	2	, Angust	٠:	-:	**	£ 6	12	-			<u>:</u>	:		:	:	:	:	1	:
) voor		. February	સહ	-		16	15	91	8	18	9		91		œ	81	16	<del>6</del>	2
Ž	z g	. Angust	44		101	10	17.	<u>2</u>	8	13,5 1	*		91	23	60	8	21	۵	12
-	:	. February	9	-	184	101	91	91	-	13	 2	 g		==- 유	<b>10</b>	36	178	ð.	8
~	;	" Anguet	14		91	10.	13\$	13	6	13	16	2			10	13	18	for	36
<b>•</b>		. Pebruary	d :		 	0	123	10	- -	1 1				=	01	11	12	10	2
7061		" Angust	ŧ	:	0	10	124	2	*	124				•	2	2	2	្ព	13
- 00.	£	. Pebraary	:	 :	<u> </u>	 	13}			13	13	2	*	17	ŧo:	::	16	104	92
7041	£	" August	:	<u>-</u> :		101	132		- e			_	51		11	2	2	104	=
-	1	February	:	<del>-</del>		10%	134	<u> </u>	10}	13	124	101	781		=	22	27	101	12
•	:	, Angust	:	<del>-</del>	**	187	133		124 1	- 1	<u> </u>	Ť	164	134		=	=	11	13
38.		" February	i	<u>-</u>	17.	124	13		134	124		121	13,	2	**	2	91	13	2
•	:	, Angust	:	<u>-</u>	174		=	- 61	124 1	_ 	<u>_</u>	124	134	17	124	2	15	124	7
1005		, February	:	<del>-</del>	<u> </u>	- Tag	<u> </u>	 82	124		-	13	†er		Ť	=	154	13	#
•	2	. Augnet	:	<del>.</del>	•					_	_	_	_						

TABLE IX—concld.

			Prices	Prices of food staples in seers obtainable per rupee.	od s	tal	oles	in	80	BJE	obt	ain	able	<b>X</b>	7	ad n	ė			
						Втгв	SYLHBY TOWN.	Ė	SC	SUBANGAHJ.	Ä.	A	Habigars,		MAULAVI BASAB.	VI BAS	5AB.	KA	Karingans.	胃
						Common rice.	Balt.	.lafazlizals	Oommon rioe.	dia8.	Metikelel,	Common rice.	.s[aB	Matikalsi.	Common slee.	t) la B	Matikalai.	Common rice.	.alaB	Matikelei.
8	id week	2	(2nd week of February	:	स	(Kapp	概		B	4	3					-				L
9	:	r	August	:	यम							55								
} 2001	:	:	Pebruary	:	a :	22		18		7	3	TELS:						_		
~	•	£	August	:	न्य			8				7								
9001	:	2	February	:	ते	الأو	H		9		2									
<b>ب</b>		2	Angust	1	:		1			7	3									
3000	=	=	Pebruary	:	:	,						_								
<b>~</b>		=	August	:	:											_				
) (101	*	2	February	:	:							_								
~	•		Angust	1	;			•								_				
<b>}</b> 1011	£	=	February	:	:															
_	:	2	Angust	:	:									-						
€ 0101	£		February	:	:															
سے	:	;	Angust																	

Statistics of eriminal and civil justice.

1912.	Detected.							
L	frae.							
1911.	Detected.							
2	True.							
1910.	Detected.							
1 2	.eusT	]						
1909.	Detected.							
=	Trae.							
1908.	Deteated.							
2	.eniT							
1907.	Detected.	S	26	0	5			
E S	True,		2	禁	3			
1906.	Detected.							
=	Trae.	A PORT		Y				
1306.	Detected.	IA	1 27	L				
	True.	1		2	\		····	
<u>8</u>	Detected.	(CON			တ	<i>9</i> 3	~	
	True.	सद्यां	व न	यते	00	8		
1908.	Detected.				13	-	<u> </u>	
<u>=</u>	True.				77	<b>89</b>	<u></u>	
1908	Detected.				31	<b>~</b>	<b>c</b> 4	
2	.eptT		····		<b>3</b> 8	64	•	
	Heads of Crime.	NORTH SYLBET SUB- DIVISION.	CREMINAL JUBRICE.  Number of cases.	(i) Rioting or unlawful assembly. Sees 143,153	157, 158 and 159 (ii) Other offences against	the State, public tran- quillity, &c. (iii) Murder, attempt at	in rier and culpable omicide. Secs. 302-304, 77, 308, and 396	

Table X-contd.

Statistics of eriminal and eivil justice.

	3	1903.	1903.	83	L <sub>E</sub>	1904.	1905.	55	1906.	9	1907.		1908.		1909.		1910.		1911.	ļ	1912.	۱
Heads of Ceiar.	.9nzl	l)etected.	.enrT	Detected.	True.	Detected.	True.	Detected.	True.	Deteoted.	True.	Detected.	Trae.	Detected.	True.	Detected.	True.	Detected.	Detected.	1	True	Detected.
NORTH SYLHET SUB- DIVISION—contd.						सन्यमव	Communication of the second		111				51/3/		<del></del>					<u> </u>		
ORIMINAL JUSTICE. Number of cases.						जयत	2//68		337				100							<del></del>		
(iv) Grievous hurt and hurt by dangerous weapon. Secs. 324-336. 339, 331, 333 and 335	13	4	16	-4	8	ဖ									<del></del>							
Secs. 353, 364, 356 and 367	4	ಣ	4	:	es -	61						<u>-</u>									······································	
against the person (vii) Dacoity. Secs. 395.	10	=	6.4	:	9	41											<del></del>					
	:	1	:	:	-	_	_,	_	_		_		_		_	_	_		_	_	_	

1	:
	ī
	:
	:
	i
	<del></del> -
+	
75 80 to to to to	38
2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	374
: 9 % : 9 % <del>*</del> H	82
21 22 11 11 28 21 22 4	472
6 7 1 24 2 1 6	139 274
51 07 01 :: 88 £2 42 ss	316
ef by gr, vr nimal. 2, 428. f. 408. f. 408. f. 408. f. 465. f. 465. f. 465. f. 465. f. 465. f. 465. f. fences on and and and 414. fiminal Secs. f. fences fecs. f.	ı
· 語:『 正	<u>.</u>
iii) Serious misel including mischief killing, poisoning, malwing any ani Sect. 270, 281, 282, 429, 429, 429, 429, 429, 429, 429, 439, 439, 439, 439, 439, 439, 439, 43	Total
iii) Serious rincluding mise miseluding mise miseluding mise most mastern and 429, 430-53, and 429, 430-53, and 457-460 Wrougful and 457-460 I) Uther serious against the perty II) Libert Secs. 910-910, III) Theft. Secs. 910-910, III) Receiving 8 perty III) Receiving 8 perty III) Lutking and homes-treapses. House-treapses. House-treapses. House-treapses. House-treapses. House-treapses. House-treapses.	
wiii) Seriincluding, haliing, haliing, soat 23, 430-3, 420, 430-3, 430-3, 449 Secs. 440 Chiner a sec	

## Table X-contd.

Statistics of criminal and civil justice.

913.	Detected.			<del></del>				
<u> </u>	True.					· <del></del>		
77	Detected.							
13	True.							
	Defected.							
19	True.							
	Deteoted.							
 	.eurT							
ģ	Detected.							
18	True.		27925			·····		
	Deteoted.	40	1	1	1			
81	True.	(a)			P.	<del></del>		
99	Detected	6						
<u>8</u>	True.	T/	TL	M.		<i>-</i>		
.55	Detroted.	d.E	18	JP.				
19(	True,	150			-			
	Detected.	(Barrier)		1111111				ಣ 
<u>,                                     </u>	.entT	सत्य	मव व	THE S	. «	, ıq	4.	
 8	Detected.				:			
<b>6</b> 1	True.			6	-	4		
	Detected.						ەر	<i>∽</i>
18	True.							<del>ه</del>
	Beads of Crime.	SUNAMGANI SUB- DIVISION:	OBIMINAL JUSTICE. Number of cases.	(i) Ricting or unlawful assembly, Secs. 143-153, 157, 159, 20, 150	(ii) Other offences against the State, public tran-	(iii) Murder, attempt attempt attempter, and culpable homicide. Secs. 302-304, 307, 308, and 396	(iv) Gricovous hurt and hurt by dengerous wespon. Sees. 324-326, 331, 333, and 335	(v) Berious criminal force. Secs. 353, 354, 356 and 357
	1902. 1903. 1904. 1905. 1906. 1907. 1908. 1909, 1910. 1911, 1913.	True. Detected. True. Detected. True. Detected. Detected.	True.   1903   1904   1905	1909  Series of the control of the c	1903.   1903.   1904.   1905.   1906.   1907.   1908.   1909	1903.   1903.   1904.   1905.   1906.   1907.   1908.   1909	1903   1903   1904   1905   1906   1907   1908   1909	Heads of Ceines   1902   1903   1904   1905   1906   1907   1908   1909   190

					8 =									. <del></del>						
	<u>:</u>	<u>:</u> :	<u>:</u> :	<u> </u>	<u>:</u>	•														
maining any animai. Recs. 270, 281, 282, 428, 429, 430, 430, 430, 430, x) House-breaking and		<del></del>	91	<del></del>	:	······································														
	2	- <del>- 2</del>	# . 95			673	d	1	6	6	5		<del></del>							
	01		 21	ea ea		61					135									
perfy or against property or against property or against property.		<del></del>	<u>:</u>	ব্যধ	300	12	MF	TY	7/4	1	12	-								
	- 2	<u>용</u>	45   16	22	23	<u>}                                    </u>				37	à			<del></del>						
	17		18 15	8		-														
	9	<u>~</u>	<del>-</del>	-2													·			
		-	:	<b>C1</b>	:									•						
<u> </u>	<del></del>	92 195	12	15	- 1		Ţ			j -	<u> </u>	1	+	1	<del> </del>	<u> </u>	1	-	<u> </u>	1_

Table X—contd.

Statistics of eriminal and civil justice.

	1903.	Š.	1903.	3.	1904.	4	1905.		1906.	- <u>-</u> -	1907.	<u> </u>	1908.	-	1909.	118	1910.	81	1911.	11	1912.
BEADS OF CRIME.	Trae.	Detented.	True,	Lefected.	ourT	Detected.	True.	Detected.	True.	Detected.	True.	Detected.	True.	Trae.	Detected.	.earT	Detected.	Trae.	Detected.	True.	Detected.
HABIGANJ SUB- DIVISION.				-	सरा		兵	70	AND THE		CZ 55 5	_ 5				<u> </u>					
CRIMINAL JUSTICE.					पेव ः	8		VV.				Trees.									
Number of cases.				-	तथने तथने	1.5		W	10		E	\									
i) Ricting or unlawful assembly. Secs. 143-153, 157, 158 and 159	72	45	æ	æ	35	8	À		1		3							· <u></u>			
	4	93	စ္	:	41	41													·		
murder, and culpable homicide. Secs. 302 to 304, 307, 308 and 396 (iv) Grievous hurt and	<b>®</b>	69	27	۵	00	6				<del></del>											
nur. by dangerous weapon. Becs. 524-526, 329, 331, 333 and 335	8	129	- 88	22	123	=======================================															




Table X—contd. Statistics of criminal and civil justice.

	1911. 1912.	True. Detected. True.								- <i>-</i>
t	• <u>•</u>	Detected.								~_
1	1910.	True.								_
l	1909	Detected.								
	8	l'rue.								
١	1908.	Detected.								
	61	True.						<del></del>		
	1907.	Detected.		-	- 69			······································		
	_ <b>≘</b> 	.eurT	5	13		2				
1	1906.	Detected.	. C.E.			37				_
1	81	True.	18			9				
١	1905.	Detected.	_ \	T						
	61	True.	- 4	14	MI	_				
1	شد	Detected.	177		ء سا	<u>F4</u>		<del>-</del>	<u> </u>	~~ ~~
1	⊢ & ∷	I				2 1		C4	59	8
	1904	.eurl'	UK!	3000	-				<b>64</b>	
		Deteoted.	전	ार्ड त्यमे	ज्य		e	<b>1</b>	60	~ ?I
	1903. 1904	<del>}</del>	7.	यमे	। जय	<b>3</b>	#	<del></del>		- 62 - 73
	1903.	Detected	स्	यमे	6	A (	*	63	8 19 9	- :
		True.	SUB-	त्यमे	। जाय <sup>8</sup> इ	α σ (	#	<del></del>	8 61 9 91	- 2

64	:		4	•	. 64	88	2	4	64	1 &
10	တ	90	20	10	m	8	18	18	41	<u> </u>
63	-	:	10	सन्ध्ये	व जया	19	<b>-</b>	<b>60</b>	:	=
	673	63	£	89	:	2	13	8	10	237
•		<b>—</b>	-4	П	:	15	52	60	~	=
စ	:	===	22	ιĊ	:	23	12	10	7	908
Other serious offen- against the person	(vii) Dacotty, Secs. 395, 897 and 198 (viii) Serious mischief,	killing, poisoning or killing, poisoning or maiming any aritmal. Pecs. 370, 281, 282, 428, 429, 430-433 and 435-440 (fx) House-breaking and	Secs. 449-462, 453, 455 and 457-460 restraint.	and confinement, Secs. 341-344 Sections offences	against the person and property or against pro- porty	(xii) Theft. Secs. 379 to 382	jani) kecelving stolen pro- perty. Secs. 411 and 414 (xiv) Lurking and cri- minol homestremess	Secs. 453, 456, 447 and	egainst property	Total

Table X—contd.

	l	St	atik	itic	0	5	틸	ji	7	Pu l	ह	7	jus	Statistics of criminal and civil justice.	أير	}		-	- 1	
	<b>8</b> .	1902.	1903.	<u>.</u>	1904.	- <del></del> -	1905.		1906.	 	1907.		1908.		1909.		1910.			1911.
HEADS OF CRIME.	1,tne.	Detected.	.en1'I	Detected.	True.	Detected.	.euaT	De tected.	True.	Detected.	True.	Detected.	True.	Detected.	True.	Detected.	True.	Detected.	True.	Detected.
KARIMGANJ SUB- DIVISION.				स	Vár	AT.	1	- 1	68	6	0									
CRIMINAL JUSTICE.				त्यमे	500	5/8	W	TY			12	0.150552								
(i) Ricting or unlawful assembly. Secs. 143-153,		;	8	जय			103	119			8/2									
(ii) Other offences against	5	=	3	9	3	3		1	9	100	2									
the Stave, puolic tran- quillity, &c (iii) Murder, attempt at	-	-	7.5	41	41	64						<del></del>					<del></del>			
marder, sad culpsble homicide. Secs. 302- 304, 307, 308 and 386 (iv) Grievous hart sad	-	~			rð.	81											<del></del>			
nurt by cangerous weapon. Secs. 334-326, 329, 331, 333 and 335 (v) Serious criminal force.	11	20	14	83	15	7				-			<del></del>							
Secs. 353, 354, 356 and 857	4	64			8	-								_				_		_

-67	:	10	က	G.d.		25	<b></b>	<b>C4</b>	တ	122
20	:	#	#	<b>∞</b>		106	<b>a</b>		က	88
	:	41	9	c4	जमत	4	- SI	63	:	12
<u>e</u>	:	11	7	<b>3</b>		8	19	13	61	181
-	:	:	တ	64	:	岩	6	-	-	8
က	:	27	3	မှ	63	64	21	Ca	က	88
(vi) Other serious offences against the person (vii) Dacoity. Sees 395,	297 and 896 Viii) Serious mischief,	hilling. poisoning, or maining any wimal. Secs. 270, 281, 282, 428, 428, 438, 480-440 (ix) House-braking and excitons to prose-braking and excitons	8608. 440-452, 454, 455, and 457-460	and confinement, Seca. 341-844 xi) Other serious offences	property or against pro-	(xii) Their, Sect. 5/3 to 382 (xiii) Beceiving stolen	perty La	minai nouse-tree pass. Secs. 453, 466 447 and 448	against property	Total

ontd.	
X—con	
able	
I	

	1912.	Detected.	]							
	_ <u> </u>	True.				_				
	1911.	Detected.								
	19	True.								
	1910.	Detected.								
	61	True.								
	1909.	Detected								
9	_ e	True,								
sti	1908.	Detected.								
ı ju	61	True.								
ivi	1907.	Detected.	£	W.E		0				
O	13	True.	(6)		۹,		3			
an	1906.	Detected	8							
[g]	119	True.		Pope		Y				
nin	1905.	Detected.		14	y y.	11				
rit	61	True.	A			30.00 15.1	\			
70	1904.	Detected.	V		<u> </u>	8	15	13	<b>8</b>	13
28	61	True.		सद्यां	विव	\$	27	53	83	23
Statistics of criminal and civil justice.	1903.	Detected.				96	6	55		<b>~</b>
ati	15	.enr1'				114	19	<u> </u>	8	16
S	1902.	Detected.				143	<b>2</b> 0		*	97
	- <del></del>	.entT				83	2	27		
		Heads of Crime.	DISTRICT TOTAL	GRIMINAL JUSTICE.  Number of cases.	(i) Rioting or unlawful	αρ.σο	the State, public tran- quillity, &c. Giil Murder attemnt et	gas.	weapon. Secs. 324-326, 329, 331, 338 and 335 (v) Serious criminal force.	Sect. 353, 354, 356 and 357

<u> </u>	_		56	80		130		4, 4,	 01	1 2
27	-		386	<del>2</del> 4	70	352 13	8		-16	
*		9	** ***	0	व जय		23	53		62
4	<del>- 63</del>	8	604	3	69	373 134	- 6	8	14	1,393 459 1,305
15	=	70 12	22	13	9	148	64	33	2	637
প্ত	61	20	371	45	12	374 148	28	42	18	88.
(vi) Other serious offences against the person	11) Decoup. Som. 380, 387 and 398	killing, poisoning or maining any animal. Seca. 270, 281, 282, 428, 429, 430, 430. House-breaking and exions honse-treenses.	Secs. 449-452, 454, 455, and 457-460	and confinement. Secs, 341-344 (xi) Other serious offences	property or against pro-	ng stolen	property. Secs. 411 and 414	Secs. 455, 447 and	against property	Total

Table X—concld.

Statistics of criminal and civil justice.

HEADS OF CRIME.	1902.	1903.	1904.	1905.	1906.	1907.	1908.	1909.	1910.	1911.	1912,
Civil. Justica. Suits for money and movables Title and other suits Rent suits	12,334 3,046 4,095	3,311				4					
Total	19,375	18,906									

TABLE XI. Finance—Receipts.

						2							
PRINCIPAL HEADS.	1890-91.	1900-01.	1901-62.	1905-08.	1901-04. 1904-05.	1904-08.	1905-06	1906-07. 1907-08.	1907-08.	1908-091	1909-10. 1916-11. 1911-19.	1910-11.	1911-13.
	Bs.	ä	ž	ä	ā	a	ä	3	Æ	ä	á	ā	ă
Land revenue (ordinary) 6,34,103	6,34,103	7,76,800	7,83,009	9,12,356	8,42,443								
ons) " (miscellane	48,350	190'19	67,916	78,489	69,995								
Provincial rates	2,16,374	3,35,895	3,35,166	2,74,490	2,37,418	-	6						
Judicial stamps	3,36,731	3,86,128	2,92,103	2,92,103 4,12,787	4,04,169		2000						
Non-Tudicial stamps		1,38,076 1,48,475	1,44,878	1,64,350	1,51,633			57					
Opium	45,491	87°58	18,818	38,065	24,877			pag					
Country spirits	2.82	1,10,676	164,791	577,08	1,06,729			8					
Ganja	1,11,675	1,19.896	1,12,950	1,33,096	127,106	99				-			
Other heads of excise	2,443	1,367	3,639	3,846	780.8		3						
Assessed taxes	979'09	71,074	70,070	70,753	619'83								
No. of sames per thousand		1	-	-	:	•	_			•			
Forests	\$90'0#	59,041	69,424	68,090	70,486								
Registration	33,677	42,480	41,00\$	1,884	\$3,700			•					
						Ī							
TOTAL	17,10,116 30,33,339 20,19,294 32,77,887 21,37,406	20,33,339	20,12,284	12,77,887	21,37,406								
					1		-		-			_	

# TABLE XII. Miscellaneous land revenue.

NOBTH SYLHET STREAM STANDY ISLON.   Rs.	PAE	Particulars.		1900-01.	1900-01. 1901-02. 1902-03.	1902.03.	1903-04.   1904-05.   1905-06.   1906-07.   1907-08.   1908-09.   1910-11.   1911-12.	1904-05.	1905-06.	1906-07.	1 907-08.	1908-09.	1909-10.	1910-11.	1911-12
	NOBTH SYL	HET SUBD	IVIBION.	B8.	Be.	B.	Be.	ā	ag.	ä	88.	Bas	ä	Ba.	ä
ANJ SUBDIVISION.  ANJ SUBDIVISION.  ANJ SUBDIVISION.   11,832  13,600  12,573  14,414  13,203  14,414  13,203  14,414  13,203  14,414  13,203  14,414  13,203  14,414  14,414  13,203  14,414  14,414  13,203  14,414  14,	Plaberies	ı			26,557	26,636	25,835								
ANJ SUBDIVISION,   8,312 6,440 5,466 6,466 6,466 6,466 6,460 12,573 14,   11,852 13,690 12,573 14,  14,114 13,203 14,  14,114 13,203 14,  14,114 13,203 14,  14,114 13,203 14,  14,114 13,203 14,  14,114 13,203 14,  16,946 18,466 20,076 11,943 11,9	Total revenue				26,397	\$8,733	25,816								
8,335 6,440 8,466 B,  INJ SUDDIVISION 11,852 13,600 12,573 14,  12,374 14,414 13,203 14,  1,397 1,495 2,160  2,698 3,433 3,588  ANJ SUBDIVISION 16,946 16,466 20,075 116,  17,943 17,272 21,499 16,  IAL DISTRIOT 66,640 68,994 66,910 64,  66,640 68,994 66,910 64,  61,091 67,506 72,499 63,	BUNAMGA	NJ BUBDI	VISION.												
NAT SUBDIVISION.  11,852 13,600 12,573 14,  1.18T BUBDIVISION.  1.1997 1,992 2,160  ANJ SUBDIVISION.  1,997 3,433 3,588  ANJ SUBDIVISION.  1,998 3,433 3,588  ANJ SUBDIVISION.  1,994 1,1993 16,166 16,166 16,166 16,169 16	Fisheries	:						É							
**************************************	Total revenue	:			4	Ø.	5,144								
THET BUBDIVISION. 1,5374 14,414 13,203 14,714 13,203 14,714 13,203 14,714 13,203 14,714 13,203 14,714 13,203 14,714 13,203 14,714 13,203 14,714 13,203 14,714 13,203 14,714 13,203 14,714 13,203 14,714 13,203 14,714 14,71	HABIGAP	vi subdiv	TRION.		3	1			_						
THER SUBDIVISION.  1.397  1.397  1.398  2.160  ANJ SUBDIVISION.  16,946  16,466  20,076  16, 18  17,943  17,943  11,94	Fisheries	:				ã.		2	YTHE						
THEF BUBDIVISION.	Total revenue	:			50		22		53.						
ANJ SUBDIVISION 1,997 1,992 2,160  ANJ SUBDIVISION 16,946 16,466 20,075 15,  TAL DISTRIOT 17,943 17,273 2,1499 16,  66,640 68,984 66,910 61,  61,061 67,956 72,499 63,	SOUTH SYL	HET SUBI	IVISION.	यत		1									
ANJ SUBDIVISION. 16,945 16,466 20,075  TAL DISTRIOT. 66,640 68,984 66,910  66,640 68,984 66,910  61,081 67,956 72,499	Plaberies	:			1,993	2,160	475	3							
ANJ SUBDIVIBION.  16,945 18,465 20,075  17,942 17,373 21,499  1AL DISTRIOT.  66,640 68,984 66,910  4,421 3,973 5,889  61,061 67,956 72,499	Total revenue	:					87.8								
	KABINGA	NJ SUBDI	VIBION.												
17,942 17,273 21,499 [AL DISTRIOT 66,640 68,084 66,910 4,421 3,972 5,889 61,061 67,956 72,499	Fisheries	:													
TAL DISTRICT 66,640 63,984 66,910 4,421 3,972 5,889 61,061 67,656 72,499	Total revenue	,					16,483								
66,640 68,984 66,910 4,481 3,973 5,889 61,061 67,956 72,499	TOT	L DISTRIC	ŧ												
61,061 67,856 72,499	Pieheries	:													
61,061 67,956 79,499	Other heads	:													
	Total revenue	:													

## TABLE XIII.

LHEIT SUBDIVISION. Acres. Assets of the control of	Accor.  Accor.	Acres. 347,866 230,262 211,735 18,500 16,532	A crea	A 0768.	Acres.	Acres.	Acres.	Aores.	Acres	
A Acrea. A Acrea. A Acrea. A Acrea. A Acrea. B A	4 0 MM			A 0766.	Acres.		Acres.	Aores.	Acres.	
246,636 99 212,236 22 212,236 22 213,236 23	65 M M	247,866 230,262 211,752 18,500 16,632	50							AOTO.
220,036 212,036 20,040 20,040 20,040 21,473 21,473	di lite	230,262 211,752 18,500 16,632	50							
212,296 212,296 212,296 212,296 20 21,773 21,578	nn dill	230,262 \$11,758 18,800	50							
23/1/346 21/3/36 21/3/3 20/4 21/3/73 21/3/73	13/	230,262 \$11,753 18,500 16,632	S							
18,640 00 17,773 876 11,578	430	18,500	20			_				
976 11,773	الأرا	16,638	50							
under raise of 1876 of Settlement raise d under other special	737		15		•					
7	Ω,	11,688		-						
rules	í	6,004								
	178,200 71	894,650	100							
Total unsettled area of the subdivi-	12,939	80,860	K							
BUNAMBANJ SUBDIVISION.			2							
Parmanently settled 830,133 830,046	829,848	830,983	5							
Total land settled for coltivation of										
	11 <b>33,034</b>	80,449	_							
1966		1								
coini stapica Area settled unde	-	:			-					
roles		:								
200	861,973	860,733					_			
Total Library of the subdiffe 93,906 93,964	279'88	94,788						_	_	

## Table XIII—contd.

### Wild and settled for cultivation of the mobel; settled area of the mobe								Î				Ī	
### OF SECTION Acres. A	PARTICULARS.	1900-01.	1\$01.02.	1902-03.	1903-04.	1904-06.	1906-06.	1906-07.	1907-08	1908-09.	1909-10.	1910-11	1911-12.
for cultivation of 17,458 17,7957 18,554 15.50,711 5.50,7	HARIGANJ 96BDIVISION,	Acres.	Aores.	Acres.	Acres.	Acres.	Acres.	Aores.	Acres.	Acres.	Acres.	Aores.	A cres
for cultivation of 17,458 17,557 18,544 14,003 free cultivation of 10,487 10,483 10,48	:	858,373	555,872	555,371	555,463								
for cultivation of 11,458 17,537 18,534 14,003 15,500 15,5	TEMPORARILY SETTIND.												
cultivation of 48.79 13,376 14,611  cultivation of 10,482	ţo	97.4	1	20 622	10 000								
cultivation of 16,482 4461 4,481 cultivation of 10,482 10,482 10,482 cultivation of 18,405 8,405 8,405 8,405 tibe anbdivit 883,282 883,781 864,407 striken cultivation of 48,794 82,681 11,702 cultivation of 81,471 86,400 91,766 cultivation of 81,471 86,401 11,454 11,753 cultivation of 81,471 86,401 11,454 11,753 cultivation of 81,471 86,401 11,454 11,753 cultivation of 81,471 86,441 11,454	inery tenuite	13,876	13,376	14,003	14,736								
Truice of 1876  Truice and 1876  Other special  Other special  SECOND STATE STATE  SECOND STATE STATE  SECOND STATE STATE  SECOND STATE  SECON	Held revenue free		1987	4,551	4,551	6							
Truken of 1876  cuther special  cuther special  supering and 1875  supering and 1876  sup	10tal land settled lot cultivation of special staples		10,483	10,482	19,834	25							
the ambdivi- the ambdivi- the ambdivi- the ambdivi- sea 282 sea,781 sea,407 sea,678 sea,781 sea,678 se	Area settles under rules of 1876 and Sec. I of Settlement rules		8,405	8,40\$	8,249	E							
the ambdivi-  of the mbdvi-  of the mbdvi-  benth in the mbdvi-  benth in the mbdvi-  cultivation of delras  cultivation of delras  cultivation of delras  subject to the mbdivi-  the ambdivi-  the ambdivi- the am	Area settled auder other special	2,077	2,077	2,077	11,586	100							
### ### #### ### ### ### #### #### #####		583,282	583,781	584,407	889,198								
### ### ### ### ### ### ### ### ### ##	unsettled area of the subdi	56,078	55,579	54,953	44,777	2							
FITLED.  Sultivation of 48.794 60,884 62,035 10,333 cultivation of 81,471 84,460 91,766 robe of 1876 48,090 80,989 86,387 other upcoint 33.441 34,441 35,433 the subdivir 422,614 428,643 436,146 the subdivir 114,986 108,987 101,454 1	BOUTH SYLHET SUBDIVISION.		>			5							
eutivation of 48.794 60,834 63,035 10,333 cuitivation of 81,471 84,460 91,766 cuitivation of 81,471 84,460 91,766 cuitivation of 81,471 84,460 91,766 cuitivation of 81,471 84,460 80,387 cuitivation of 82,614 43,644 438,643 436,146 the subdivir 422,614 428,643 436,146 the subdivir 114,986 108,987 101,454 1	į		292,349	292,345	189'845								
entiration of 48,794 60,884 63,035 11,702 11,703 10,333 10	TREPORABLLY SETTLED.												
Enter 11,702 10,533 10,	Total land settled for sultivation of		<b>80 89</b>	62.035	\$3.00X								
10,233 10,333 10	nary tenure		40,561	41,702	41,753								
contivation of 81,471 86,400 91,766 rubs of 1376 lement rubs 183,411 84,411 35,433 the ambdiv: 422,614 428,643 436,146 the ambdiv: 114,986 108,987 101,454	:	_	10,333	10,333	10,23								
ed under robe of 1876 48,030 80,385 86,335 fod under other special 33,441 84,441 35,433 area of the subdivir 422,614 428,643 436,146 area of the subdivir 114,986 108,987 101,454	coltivation		86,400	91,786	88,898								
led under other special 33,441 84,441 35,433 area of the subdiri- area of the subdiri	Area settled under raise of 1876 and Sec. I of Settlement rules	48,030	80,989	36,353	81,180			· 					
area of the subdiri- area of the subdiri- ii. II4,986 108,987 101,454	Area settled under other special	33,441	34,441	35,433	62.848				_				
area of the subdivi-	pettled area of		428.643	436,146	458,909								
114,986 108,957 101,454	area of		•		1							_	
	:		108,957	101,454	108,621								

KARIMGANT BUBDIVIBION.							
Permanently settled TREPORABLY SETTLED.	284,156	<b>\$84</b> ,15 <b>6</b>	384,164	384,576			
Total land settled for entitivation of ordinary orops	F0,254	66,063	1,694	512,83			
Held on ordinary tenure	46,970	52,738	64,410	860,03			
Held revenue free	3,284	1887	1884	187			
special staples	59,463	60,506	60,506	\$4,765			
ted grants	1,878	1,878	1,878	1,878			
and Sec. I of Settlement rules	39,634	162.01	162'0\$	41,741			
rales	17,941	18,136	18,336	11,146			-
THE DATASE	492,863	500,748	\$02,353	496,663			
Total unsettled area of the substate	176,857	169,977	168,967	175,068	1		
TOTAL DISTRICT.	中		1				
Permanently settled	2,407,545	2,407,545 2,407,407 2,407,190 2,411,018	2,407,190	2,411,018		_	
TREPORARIET BRITLED.	ज न		4		8		
Total hand settled for caltivation of ordinary crops	878, 806	294,523	\$89,933	\$86,888			
Held on ordinary tenure	241,133		861,599	350,769			
Held revenue free	\$4,763	37,736	\$7,734	27,623			
Special orops	169,179	174.160	180,537	75,124			
Agra of ree-minper age outsing-	1,878	1,878	1,578	1,878			
and Sec. I of Settlement rules	107,647	111,233	116,607	92,668			
raics	59,65	61,049	270'29,	80,578			
Tetal sattled area of the district	2,946,619	2,966,619 2,976,190 2,987,060	2,987,060	3,974,536			
Total angettled area of the district	622,781	603,310	491,850	£03,874			
						_	

went classes of actains have been revised and banes do not agree with those shown in the printed reports. NOTE. -The areas under att

## TABLE XIV

	l					_							
PRINGFAL HRADS.		1900-01.	1901-03.	1902-03.	1903-04.	1504-05. 1905-05 1905-07, 1307-08, 1908-09, 1909-10, 1910-11 1911-15.	1905-06	1906-07.	1307-08.	1908-09.	1909-10	1910-11	1911-13.
North Stlart Burdivision— No. of optim shops Amount paid for lieunes	. :	\$.166	2.664		3 5								
	ă	md srs 5 36 6,726	md srs 4 36 5,641	100 are 5 32 6.613	32 6 2 0	nd ser ob mad ere ch mad ere ch mad ere ch mad ere ch mad ere ob mad ere ch	nd ser cb	nd sr ch	nd sr ch	nd er ch	nd er ch	md sr cb	nd or ch
	. :	10,838	17 7,980	8,490	-						<del></del>		
2	. i		34 27 8	13,258	43 24 18 13,731	add Broth mad sreb	od er ch	ad er eh	nd ar cb	pd are by	nd ar cb	nd er ob	ग्वे इस ch
	<u>.</u>	30,133	16,963	16,782	20,798	THE STATE OF THE S	- , . , -						
	# A	त्रःव			:::		•					· · · · · · · · · · · · · · · · · · ·	
:	2 A : :	636	1,846	1,198	. 788	2				•			
BUNAMGANJ SUBDIVISION— No. of opium shops Amount paid for licenses	. :	on <b>06</b>	64 88	87.8	* #	5.	·		<del></del> -				
	. : :	md srs 1 13 1,482 14	md srs 1 6 1,283			med er ob mad er ob med er ob	ader cha	Bd ar ob	nd arr ch	ad ser eb	nde m ba	nder ob	ad arr ob
<b>.</b> 2	<b>a</b>		8,398 md ars ob 81 1 4	6,996 7,766 md are ob 12 5,7 16 10		md ar eb ond ar eb and ar eb med ar eb med er eb med er eb med ar eb ond ar eb	nd ar ch	od ar ob	od er ob	od er ob	न्युः अकृ	ad ser ch	युक्त अप
Mount on ganja sold  Mo. of country spirit shops Amount paid for thousan	A	6,603 6.83	5,893 6,074	7,649	7,109								
: P :	:::	:::	: <b>: :</b>		. : : 1								
		_		_						_			

A A	4 4
	ž ž
49 49	र्व र्व
<u> </u>	<u>H</u> H
	3 3
₹ 6	8 8
5 E	
	<u>8</u>
<b>5</b> 5	7 7 F
• • • • • • • • • • • • • • • • • • •	
	# # # # # # # # # # # # # # # # # # #
<b>2 2</b>	g g
4 4	<del>ৰ</del> স্থ
ŭ ŭ	<u>š</u> i k
143  153  163  163  163  164  175  1764  1764  1764  1764	373 373 373 373 374 375 376 377 377 378 378 378 378 378 378 378 378
<del>ਰ ਰ</del>	4 4
	불 분 명 전
<u> </u>	<u> </u>
4 4	18 6
	No. of the second
	~\&\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\
11 12 12 12 12 12 12 12 12 12 12 12 12 1	373-373-373-373-373-373-373-373-373-373
11. 14. 14. 14. 14. 14. 14. 14. 14. 14.	
4 4 5 4 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	210 210 0 10 6 288 11 28 11 18 86 48 14 20 19,960 10,960 10,960 10,960 10,960 1
2. 2. 2. 2. 2. 2. 2. 2. 2. 2. 2. 2. 2. 2	े हिंद्रों निद्देष्ठले के राज्य राज्य स्थापन के स् स्थापन के समित्र के स्थापन के
1, 12, 14,	
2 2224222	
	11,420 11
Bo Hazz Arrivit	
15.00 11.00	204 1 20 1 20 1 20 1 20 1 20 1 20 1 20 1
	No 65
::: 1:::::::::::::::::::::::::::::::::	
	:: :::: :::::::::::::::::::::::::::::::
9	
Mo. of reball shops  Manous paid for licenses Diblar beads of excise revenue  M. of opium shors  Manount paid for licenses Dashity of opium issued Daty on opium shops  Amount paid for licenses Genish of opium issued Daty on print shops  Amount paid for licenses Manount paid for licenses Amount paid for licenses Mo. of country spirit shops  Mo. of cetall shops  Mo. of retail shops	No option shops Anotat paid for licenses Amotat paid for licenses Constity of option served Daty on option sold No of gauls shops Amotat paid for licenses Amotat of gauls shops Amotat paid for licenses Amotat paid for licenses Re of contart spiff shops Readity of chattilers Read of distillers Read of distillers Amotat paid for licenses Re. of distillers Amotat paid for licenses Re. of distillers Amotat paid for licenses Chart of retail shops Amotat paid for licenses Chart band of the licenses Chart band of the licenses
The state of the s	inees in the control of the control
A Paris in the par	and
for the form of th	for
Manual Ma	and of the state o
Series of the se	The state of the s
TAN AND CONTRACT OF CONTRACT O	Fig. 1
Mo. of reball shops Amouns paid for licenses Oblar beads of axies revenue M. of oplum shors Amount paid for licenses Quantity of oplum saned Duty on oplum saned Oblar of ganja hops Amount paid for licenses Quantity of ganja hops Amount paid for licenses Gandly of gunja saned Oblary sugais soil four saned No. of confly spicit shops Amount paid for licenses Ko. of distilleries Amount of ly huper issued M. of reteal shops Amount paid for licenses Obbar bases of exches revenue	NOTE STLEET BUBDITISION Amoust paid of licenses Constity of optum such Duty on optum such Amount paid of licenses Amount paid of licenses Amount of ganja siened Duty on ganja sold Amount paid for licenses Guantity of liquor issued Relibead data Amount paid for licenses Relibead data Amount paid for licenses Relibead data
M40 STA CHTA CHTANATAC	On - CAMP THRIADBARD

## TABLE XIV—concld. Excise.

PRINCIPAL HEADS.	1900-01.	1901-02.	1903-03.	1903-04.	1904-05.	1906-06.	1906-07.	1904-05, 1906-06, 1906-07, 1907-08, 1908-09, 1908-10, 1910-11, 1911-19,	1908-09.	1909-10.	1910-11.	1911-19.
EARINGARY SURDIVISION— No. of opium shops Amount paid for ticenses Quantity of opium issued Daty on opium sold No. of saxis shops Amount paid for licenses Quantity of gan is lead ed Daty on gan is and No. of chillieries Amount paid for Houses No. of chillieries Sulli-band daty No. of retail shops Amount paid for licenses Sulli-band daty No. of retail shops Amount paid for licenses Other bands of excise revenue	15 15 15 15 15 15 15 15 15 15 15 15 15 1	20 00 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1,866 md srs 7 16 7 16 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9	10.00 md srife to 10.00 md sri	nd se ob	Ed er ch	स्त्रवं हर क	md ser ob md er ob	nd or ch	ed st ob	md er eb	40 H G H G H G H G H G H G H G H G H G H
TOTAL DISTRICT—  No. of optim shop  Amount paid for licenses Quantity of optim farned Duty on optim sold  No. of san s alone Amount paid for licenses Quantity of graps sense Just on graps sold  No. of distilleries Amount paid for licenses No. of distilleries Recordingly of graps Amount paid for licenses No. of distilleries Recordingly of liquor leaded Buil-band duty Recordingly of liquor leaded Recordingly of liquor leaded Recordingly of liquor leaded Recordingly of liquor leaded	Be of 6,665  Be of are ob or	5 27 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	8,737 md srm 16,88 17,328 81,328 81,328 80,04 78,034 80,778	\$ 5,737	nd st eb	and ser ob	nd er ch nd er eh	med streb med strob med st	nd er ch	6 49 49 49 49 49 49 49 49 49 49 49 49 49	md बर cb	nd srob nd ireb

Table XV.

Income and expenditure of Local Boards.

North Sylhet.

Sources of		Inc	OMB.	Heads of		Expen	DITUBE.
income.		1890-91.	1900-01.	expenditure.		1890-91.	1900-01,
		Re.	Re			Re.	Re.
Provincial rates	•••	49,859	52,550	Post office	•••	3,512	3,618
Police		2,860	5,669	Administration		205	205
Tolls on ferries	•••	8,925	9,778	Education	•••	10,750	19,068
Contributions	•••	7,200	10,995	Medical	•••	8,497	6,769
Debt	-	•••	2,959	Olvii works		36,657	59,144
Miscellaneous	•••	189	34	Debt	•••	188	215
		(2		Miscellaneous	•••	299	809
TOTAL		68,783	81,978	Total		55,083	89,828

### Sunamganj.

Sources of		Ino	om B.	Heads of		Expan	DITURE,
income.		1890-91	1900-01	expenditure.	•	1890-91	1900-01.
		Rs.	Ra.	जयते		Rs	Rs.
Provincial rutes		37,217	37,378	Post office	•••	5,157	4,736
Police		2,334	8,751	Administration	l	138	151
Tolls on ferries	***	2,407	8,361	Education	•••	8,474	11,606
Contributions		1,183	3,435	Medical	•••	2,226	5,126
Debt	•••	•••	4,060	Civii works	•••	19,427	23,696
Miscellaneous	•••	153	641	Debt	•••		5,257
				Miscellaneous	•••	<b>78</b> I	2,808
TOTAL	•••	43,294	52,626	TOTAL	•••	86,203	51,790

Table XV—contd.

Income and expenditure of Local Boards,
Habiganj.

Sources of		Inco	ME.	Heads of		EXPEN	DITURS.
income.		1890-91.	1900-01.	expenditure.		1890-91.	1900-01.
Provincial rates	<u></u>	Rs. 55,333	Rs. 56,326	Post office	•••	Rs. 8,759	Rs. 4,212
Police	•••	4,100	5,609	Administration 2	211	228	
Tolls on ferrics	•••	3,435	4,852	Education	•••	18,685	19,328
Contributions	•••	•••	9,160	Medical	•••	4,937	5,413
Debt	,	***	6,613	Civil works	•••	29,955	44,301
Miscellaneous		235	57	Debt	•••		6,616
		1		Contributions	•••	205	•••
		N.		Miscelleneous	•••	250	445
TOTAL		63,103	75,119	TOTAL	••	53,002	80,566

## South Sylhet.

Sources of		Ind	OME.	Heads of		Expenditure.		
income.		1890-91.	1900-01.	expenditure	)	1890-91.	1900-01	
Provincial rates Police Tolls on ferries Contributions Debt Miscellaneous	•••	its. 86,191 8,175 6,700 16,606 	Re. 87,423 5,036 7,287 21,600 8,457 480	Post office Administration Education Medical Oivil works Deha	•••	Rs. 3,165 130 18,866 3,528 28,804	Rs. 1,416 130 20,277 9,092 86,117 8,418	
Total	•••	62,887	75,288	Miscellaneons Total	•••	85 49,576	1,900	

Table XV—concid.

Income and expenditure of Local Boards.

Karimganj.

Sources of		Inc	COM R.	Heads of		BEPER	DITURE.
income.		1890-91.	1900-01.	expenditure.		1890-91.	1900-01.
Provincial rates		Ra 40,493			Re. 3,760	Ra. 945	
Police	,,,	1,820	2,875		148	146	
Tolls on ferries	•••	10,683	11,575	Education	•••	9,180	12,494
Contributions		4,000	17,607	Medical		8,816	7,944
Debt	•••		8,891	Oivil works	•••	34,031	52,125
Miscellaneous	•••	129	91	Debt	•••		8,891
		3		Contributions	•••		1,690
				Miscellaneous	•••	1,279	1,194
TOTAL		57,125	79,920	TOTAL	•••	51,712	79,929



## TABLE XVI.

## Income and expenditure of Municipality and Union.

SYLHET MUNICIPALITY.

	Inc	OME.	Heads of	Expeni	OITURE.
Bources of income.	1890-91	1900-01	expenditure.	1890-91	1900-01
	Rs.	Rs.		Rs.	Rs.
	SY	LBET M	UNICIPALITY.		
Opening balance	8,500	2,362	Administration	2,799	2,464
Taxes on houses and lands		1,191	Conservancy	5,108	6,907
Pounds	1,760	671	Public works	5,499	4,412
Tax on persons		6,036	Public instructions	565	718
Tolls on roads and			Drainage	868 4.947	1,093 4,507
ferries	6,915	6,342		603	925
Conservancy	2,621	8,437	Olosing balance	003	820
Other sources	667	987	1444		
TOTAL	20,389	21,026	Total	20,889	21,026
	Н	ABIGAN	J UNION.		
Opening balance	110	4,751	Administration	402	504
Tax on houses and lands	784	132	Conservancy	487	3,024
Pounds	956	1,104	Police	1,051	795
Fees from markets	975	•••	Public works	108	510
Grants from Pro-			Public instructions	52	196
vincial and Local Funds		1,000	Drainage	20	275
Tax on persons		1,544	Other heads	1,802	1,821
Tolls on roads and ferries	426	1,230	Olosing balance	7	8,414
Other sources	128	278			
TOTAL	3,379	10,039	Total	3,879	10,039

TABLE XVII.
Strength of Police Force.

Particulars.		1881.	1891.	1901.
CIVIL POLICE	•			
Supervising Stai	FF.			
District and Assistant	Super-			
intendents	•••	1	1	2
Inspectors	•	5	6	6
SUBORDINATE STAI	F.Q			
Sub Inspectors		16	15	27
Head Constables	6	54	74	58
Constables	•••	836	450	527
Rural Police	点框	4,376	5,611	5,318
Union and Municipal	Police	82	7	7
Total expenditure	Rs.	2,28,685	3,43,538	8,74,885

Actual strength for 1881 and sanctioned strength for other years. As the full sanctioned number of Sub-Inspectors was not entertained during the year 1901, only the actual number of Sub-Inspectors and Head Constables is shown for that year.

TABLE XVIII.

Police Stations and Out-posts in 1904.

		8.	Anotioned	STHENGTH.	
NAME OF POLICE STATE	ons.	Sub In- spector.	Head Con- atables	Con- stables.	Total.
Balaganj P. S Biewanath O. P. Fenchuganj O. P. Golapganj O. P. Goyainghat O. P. Jaintta O. P. Kanairghat P. S. Sylhet P. S Do Town O. P.	***	2 1  1 1 1 2 8	 1 	8 5 5 5 4 8 12 88	10 6 8 6 6 5 9 15
Chhatak P. S Dharmapasha P. S. Dirai P. S Jagannathpur. O. P. Nunawganj P. S. Tahirpur O. P	*** *** *** ***	2 2 1 1 2 1	 1 	8 8 6 12 4	10 10 10 7 14 5
Abidabad O. P Baniyachung P. S. Habigani P. S. Lakhai O. P Madhabpur P. S. Muchikandi O. P. Nubiganj P. S	   	1 2 4 1 2 2 2 2	*** *** *** ***	6 8 16 4 8 8	7 10 20 5 10 10
Kamalganj P. S. Kulaura P S Maulavi Bazar P. S. Hajnagar O: P Srimangal O. P.	•••	1 2 2 1 2	1 	12 8 14 5 6	14 10 16 6 8
Jaldhub P. S Karimjanj P. S. Patharkandi O. P. Ratabari U. P	•••	2 3 1 1	i 	8 16 5 5	10 20 6 6

## TABLE XIX. Statistics of Jails. Sylhet Jail.

	1881.	1891.	1901.
Average daily population { Male Female	513.83	356.29	540-21
Female	12.20	6.88	5.68
Rate of mortality per 1,000	Rs. 17	80 Bs,	33 Rs.
Expenditure on jail maintenance	36,722	25,544	42,372
Coat per prisoner (excluding civil prisoners)	36	38	53
Profits on jail manufacture	8,933	5,806	814
Earnings per prisoner †	17	18	<b>2</b>

## Sunamganj Subsidiary Jail.

		1881.	I891.	1901.
Average daily population	Male	21.61	20.64	29.23
(	Female	·08	∙01	•08
Rate of mortality per 1,000	•••	92 Rs.	97 Rs.	84 Re.
Expenditure on jail maintena	nce	1',440	1,419	1,806
Cost per prisoner (exclude prisoners)		25	28	49
Profits on jail manufacture	10)	166	<b>37</b> 0'	1,125
Earnings per prisoner †	• • •	. 9	. 23	. 52

On rations and clothing only.

<sup>†</sup> Calculated on the average number sentenced to labour.

## Table XIX—contd. Statistics of Jail. Habiganj Subsidiary Jail.

			1881.	1891.	1901.
Average daily population {	Male Female	•••	29·24 •34	30·55 ·08	51·63 ·81
Rate of mortality per 1,000		•••	34 Rs.	33 Re.	Bs.
Expenditure on jail maintens	ance	•••	1,882	2,029	1,710
Cost per prisoner (exc prisoners)	luding c	ivil	28	37	24
Profits on jail manufacture	NE	***	125	228	1,068
Earnings per prisoner † .		•••	5	11	22

### South Sylhet Subsidiary Jail.

d		1883.	1891.	1901.
A recess deily population   Male		13.64	20.15	23.99
Average daily population { Female	मेव ज	पूर्व ·20	·12	•40
Rate of mortality per 1,000	•••	Äs.	49 Rs.	 Rs.
Expenditure on jail maintenance	•••	1,138	1,513	1,509
Cost per prisoner (excluding prisoners)	oivil	27	31	45
Profits on jail manufacture		40	196	208
Earnings per prisoner†		4	12	13

<sup>•</sup> On rations and clothing only.

<sup>†</sup> Calculated on the average number sentenced to labour.

## Table XIX—concld. Statistics of Jail. Karimganj Subsidiary Jail.

	1881,	1891.	1901.
Avarge daily population { Male	1839	17.87	50.92
(Female	03	•••	•46
Rate of mortality per 1000	54	•••	340
Expenditure on juil maintenance	Re. 1,488	Ra. 1,298	Rs. 1,359
Cost per prisoner (excluding civil prisoners)	80	29	81
Profits on jail manufacture	892	248	268
Earnings per prisoner	27	19	11
	132007	l	

On rations and clothing only.

<sup>†</sup> Calculated on the average number sentenced to labour.



## TABLE XX Education.

	1000	1 and	1 000 01	1002.00	30 20 0	20 3001	1000.01	1007 00	20,000	0.000	9.62	
	T A	,	130000	Tone	00-40er	200-00	Tane 1	00-1081	TB00005	nt-ther.	1	1916-15
COLLEGES.		•										
Mamber	<del>-</del>	-	-	_								-
Number of boys	\$	\$	£	2								
Number of passing F.A	22	**	<u>a</u>	7.								
SHOONDARY BUROOLS,	(	Ø.	B	G.	0						<del></del>	
High Behools-					-8			•	-			
Mumber		1		7	201							
Namber of boys reading in High Bobool classes	618	493	33	264	3							
Numbre of boys reading in Middle School classes	3	827	109	5								
Number of boys reading in Primary clauses	633	741	863	208								
Meddle Bugitad Behools—								-				
Number	<b>9</b>	\$	#	. 9								
Number of boys reading in Middle School classes	<b>28</b>	379	\$25	331								
Number of boys reading to Primary classes	1,911	2,586	2,633	2,767								,
Middle Vernacular Schools—			-							-		
Number	- 12	91	=	<b>#</b>								
Number of boys reading in Middle School chases	251	133	8	10.		_						
Number of hoys reading in Primary classes	662	748	108	787							_	
			•	_	_	-	_	_	•		-	•

Primary schools.							_	-		
Upper Primary Babools—										
:	1	•	5	3	**					
Number of boys reading in Upper Primary classes	:	833	22	232	193					
Number of boys reading in Lower Primary classes	:	1,474	1,488	1,380	1,928					
Lover Primary Schools—						· · <del>- ·</del> ·				
:	Ē	828	928	\$	751	,				
Number of boys resting in three upper chance	1	(8)	(a) (a)	10,070	9,238	5				
Mumber of boys reading in lower classor	el c	86.80e	\$75°78	15,907 15,959	15,869	723				
FEMALE BOUCATION.	14					100				
Mumber of girls' Schools	10	181	a	104	22	500		<del></del>		
Number of girls reading (whether in girls' or	. s. 60	11	77	Y		E.				
Schools) in—		d	A	y		h				
High Schools	i	i	:	i	i			·		
Middle English Sebool	1	i	8	:	:			<u>, -</u>		
Middle Vernsoular Schools	!	ŧ	;	<del></del>	:				·	
Upper Primary Schools	፡	\$	2	9	82	- <u></u>				
Lower Primary Schools	į	879	3,414	2,637	018'1					

## TABLE XXI. Educational Finance.

		•80	EXPENDIT	Expenditure on institutions maintained or alded by public found in 1900-01 from	STITUTIONS MA FUNDS IN 190	AINTAINED	OR AIDED			
Particulars.		o .oV oitutitaai	Provincial Revenues.	District bna Monicipal Funds.	Feeg.	Other.	Lotal.	Expend of	Expenditure per bead of scholar.	r bead
		1	Ba	S.	Rs.	æ	Rs.	Rs.	Α8.	ъ.
Training and Special Schools	:	80		1,382	1,467	2,060	4,899	L.	*	<b>∞</b>
Secondary Boys' Schools—		प्रमेव प्रमेव								
Upper (High)	:	ज	7,363		23,454	2,764	33,581	21	11	9
Lower (Middle)	:	9	1,554	17,276	18,631	13,357	47,718	13	10	01
Primary Boys' Schools-			).	7	3					
Upper	i	47	•	5,176	3,575	2,498	11,249 (	9	16	64
Lower	:	833	:	45,340	15,158	1,731	62,229	63	<b>C4</b>	2
Girla' Schools	:	181	į	4,803	41	1	4,806	64	4	70
TOTAL	:	1,088	8,917	73,976	621'69	23,410	1,64,483	4	4	•

## TABLE XXII. Medical.

DA DETARTA DA	North 83	lhet sub:	livinion.	Suname	ganj subd	livision.	Habig	anj subdi	vision.
PARTIQUIARS.	1881	1891	1901	1881	1891	1901	1881	1891	1901
Number of dispensaries	1	8	10	1	В	6	1	7	7
Daily average of in-door patients	6-06	17-11	20.67		-96	2.00		••••	8-58
Daily average of out-door patients	47-17	212-38	383-16	4:17	94-77	118-34	8-91	89.45	190-02
Cases treated	7,689	49,755	58,131	1,526	19,051	29,658	1,098	31,344	43,597
Operations performed	249	1,177	2,251	. 83	682	817	4	890	3,684
Total income Re.	1,866	15,898	2:,102	\$80	8,539	9,779	887	6,346	10,333
Income from Government Bs.	977	8,799	4,578	49	1,815	1,207	43	1,838	1,433
Income from Local and Municipal funds Rs.	815	6,084	8,768	-0-	9,898	4,756	••••	4,026	4,510
Subscriptions Rs.	490	568	704	268	850	492	209	438	241
Total expenditure Rs.	1,756	15,184	20,816	336	6,419	9,848	802	6,116	10,04
Expenditure on establishment Rs.	1,055	4,520	6,167	171	3,328	3,075	100	2,962	3,416
Ratio per mille of persons successfully vaccinated				<b></b>			••••		
Cost per case Rs.			Y	χ			••••	•	

DA DETOTE A DA	South 8	lylbet sut	division.	Kerima	anj subd	livision.	To	tal Distr	iot.
PARTICULARS.	1881	1891	1901	1881	1891	1901	1881	1891	1901
Number of dispensaries		6	10	1	7	10		84	48
Daily average of in-door patients	<b></b>	1.04	1.65		2.18	\$-85	6.06	21-48	81:26
Daily average of out-door patients		186-18	851.78	9-22	178-66	320.70	69-47	711-89	1,171:48
Onces treated	<b></b>	99,113	(a) 56,877	8,269	40,619	42,998	18,652	153,782	180,091
Operations performed		944	1,868	108	1,107	1,677	890	4,800	8,060
Total income Bs.		10,908	19,470	820	7,127	13, 781	3,925	46,148	74,448
Income from Government Rs.		1,818	1,702	84	1,788	2,106	1,109	9,923	11,020
Income from Local and Municipa funds Rs.		4,318	7,841	102	8,183	6,841	417	19,984	32,100
Subscriptions Re.	1	595	1,407	154	275	631	1,130	3,209	4.158
Total expenditure Rs.		10,708	19,106	318	6,698	12,987	2,711	45,117	73,440
Expenditure on establishment Ba.		2,653	5,083	116	2,584	4,668	1,448	15,056	23,396
Ratio per pole of persons successe fully vaccinated	1 -						(8) 0.80	19.67	30-11
Cost per case Rs.		[						0-1-4	0-1.0

<sup>(</sup>a) Excludes 905 persons treated in the private dispensary at Maulavi Bazar.
(b) Figure for 1861-82.

## TABLE XXIII. Dispensaries.

	. 19	00.	19	01.	19	02.	19	08.	19	04.	19	05.	19	06.
Name of Dispensary.	Total cost.	Oases treated.	Total cost.	Cases treated.	Total cost.	Onnes treated.	Total cost,	Cases treated.	Total cost.	Onses treated.	Total cost.	Onese treated.	Total cost.	Oases treated.
	Rs.		Rs.		Re.		Re.		Rs.		Rs.		Ra.	
Bylhet .	. 8,966	10,596	6,095	12,228	5,077	14,070	8,467	14,498	8,538	14,023				
Sylbet (Municipal)	1,151	8,574	1,148	8,532	1,159	8,864	1,893	7,655	1,840	8,827				
Balaganj	. 2,022	5,804	1,695	5,190	1,125	5,274	1,293	5,461	1,325	5,926			1 ;	
Fenchuganj .	1,584	6,054	1,657	5,885	1,370	8,816	1,507	9,182	1,398	9,855			}	
Jaintispur .	1,794	5,516	1,778	5,802	1,299	6,208	2,068	0,848	1,150	7,891				
Kanairghat .	9,416	8,016	3,838	5,508	679	6,369	904	5,586	<b>\$2</b> 6	5,814				
Goyainghai	. 1,469	4,826	1,570	5,672	989	6,169	985	6,065	790	5,794				
Digit .	2,052	8,906	1,761	4,221	846	4,853	1,003	4,864	1,017	4,982			'	
Thakurbari .	1,776	4,930	1,464	5,306	1,087	6,801	1,482	6,921	1,257	6,838			:	
Sunamganj	2,168	6,924	9,711	7,850	1,523	7,991	988	8,684	1,988	8,870			1	
Ohhatak .	1,558	8,682	1,588	9,090	1,227	8,896	1,681	8,101	1,687	7,927		1	1	
Jagannathpur .	1,083	5,867	1,250	5,244	1,288	5,671	976	6,640	1,082	6,887			1	
Tahirpur	. 806	2,506	1,420	1,611	882	2,382	1,807	3,887	820	8,103			1	
Dirat	1,825	8,821	1,438	2,888	1,085	8,856	970	4,427	924	5,857				
Madhyanagar	1,189	3,118	1,195	3,025	900	8,783	691	8,814	582	5,470			1	
Habiganj	5,085	8,555	2,370	11,586	8,089	13,116	2,429	12,928	9,130	18,729		}	}	
Baniyachung .	1,677	5,817	1,623	7,879	1,340	8,664	1,297	8,917	1,568	8,810		,		
Muchikandi	1,586	5,271	1,065	5,206	748	5,228	1,040	5,054	909	5,324			j	
Nabiganj	1,044	8,938	967	2,906	1,698	8,524	1,508	4,174	1,093	5,141	)			
Jalsuka	931	8,725	1,038	4,262	927	4,377	1,094	5,040	804	4,903		ł		1
Jagadiepur	1,479	4,841	1,608	4,707	908	4,505	1,184	5,176	899	4,851		}		
Sabubal Bazar	1,262	5,749	1,870	8,481	1,015	6,988	1,057	5,907	1,087	6,808		1	ĺ	
Manlavi Bazar	2,970	8,214	2,984	8,821	1,494	10,702	1,418	19,208	1,616	18,588		1		
Punchgaon	1,797	8,388	1,787	4,018	1,896	3,970	1,046	8,982	1,017	4,475				
Rabir Basar	1,622	10,425	1,538	11,054	1,917	11,534	1,808	12,292	1,567	18,168			} '	
Srimangal	1,990	4,000	2,955	4,664	2,671	5,018	1,108	6,618	1,817	6,240				

### Table XXIII—contd.

#### Dispensaries.

		19	1907.		1908.		1909.		1910.		1911.		13.
Name of Di	Total cost,	Osees treated.	Total cost.	Ohnes treated.	Total cost.	Onses treated.	Total cost,	Oners treated.	Total cost.	Oases treated.	Total cost,	Oass treated.	
		Ro.		Rs,		Rs.		Rs,		Rs.		Ra.	
Sylbet													
Sylbet (Municipal		j	•		[	] :							
Balaganj	•••	}											
Fenchuganj	••	•		J. 53	THE S	_							
Jaintiapur	••	}	2	rish		副	9.						
Kanairghas	•• ••	l	6		$\sim$		9						
Goyainghat	••	{	6										
Digli	••	}	B	1988		1889							
Thakurbari	•• ••	1	j	Q.A.	11.	Y							
Bunamyanj	••	l		140.	3 24	13							
Ohhatak		ļ	£			920							
Jagaunathpur	••	1	- 65			17	-						
Tahirpur	••	}	- 10	111-310	S. 72	AFF.							
Dirai	••	Ì	1	II-Ti	वि उ	यने							
Madhyanagat	••			선택.	44 4	लव							
Habiganj	••	•	l	ł		{	1	}					
Baniyachung		}	}	}	<b>,</b>		1						
Muchikandi	••	1	1	1		}	}			'			
Nabiganj		1	}	j			1						
Jaleuka	••	1	}	1		1	}	]		[			į
Jagadispur	••		1	1	l	l			ŀ	ł	}		
Bahubal Basat	••		1	1	1	1	j		}				
Manlavi Basat			1		1		}	}		}			
Panchgaon		1			1	1	Ì	i					}
Babir Basar	·• ··	1	1		{	1	[	1		]	1	i	ļ
Srimanga!					1		1		1	1	ŀ		

# Table XXIII—contd. Dispensaries.

		1900. 1901.		01.	1902.		1908.		1904.		1905.		1906.		
Name of Dispensary.		Total cost.	Cases treated.	Total cost.	Onces treated.	Total cost.	Cases treated.	Total cost.	Oases treated.	Total cost.	Osses treated.	Total cost.	Oaces treated.	Total cost.	Oases treated.
		Re.		Rs,		Rs.		Rs.		He.		Rs.		Rs.	
Kamalganj		2,178	5,019	1,765	5,875	845	5,482	1,185	6,222	942	8,474		٠.		
Manumukh		9,014	3,800	1,424	4,000	841	6,692	980	6,081	970	7,840				
Indeswar	••	1,656	2,409	1,824	8,484	884	2,464	939	8,889	1,038	2,616				
Munshibasar	•••	1,764	8,598	1,887	8,542	980	4,687	1,096	5,082	1,070	8,987				
Shamsherganj		1,330	8,140	1,902	8,679	738	5,377	1,708	8,624	1,368	6,874	1			
Kulaura	••	1,808	4,972	1,091	8,245	770	9,729	1,250	10,029	1,551	10,186				
Karimganj	••	2,091	4,515	1,767	6,013	1,532	7,109	935	8,049	1,029	8,458				
Atgram		1,362	8,580	1,951	3,879	748	9,616	774	4,879	1,020	4,014		!		
Bhanga	•-	1,419	6,705	1,519	6,952	1,860	6,818	1,111	8,189	1,690	8,886				
Bianibasar	••	1,588	6,252	1,611	6,121	1,191	6,079	1,480	6,167	1,602	6,094				
Patharkandi	••	1,635	3,380	1,303	8,248	732	8,514	809	8,406	<b>67</b> 0	1,690				
Tilpara				••				•••		488	2,827				
Lata		1,650	8,893	908	2,808	826	2,968	729	8,230	879	8,840				
Nilam Bazar		1,737	4,488	1,848	4,383	755	4,114	1,092	8,611	95)	4,528				
Barlekha		1,236	9,710	1,409	4,467	815	4,035	1,608	2,893	1,006	4,606				
Ohargola		942	8,839	938	3,189	989	8,028	96?	4,825	967	5,483	ĺ	1		
Kaliganj			]			794	4,110	1,085	5,489	1,805	6,988				

## Table XXIII—concld. Dispensaries.

	19	1907.		1908.		1009.		1910.		1911.		1913.	
Name of L	Total cost.	Cases treated,	Total cost.	Cames treated.	Total cost.	Ower treated.	Total cost.	Cases treated.	Tótal cost.	Chass treated.	Total sect.	Cases treated.	
		Ra.		110.		Rs.		Re		Re.		Rs.	
Kamalganj													
Manumukh													
Iswesbal				- 5	The Paris								
Munshibasar			É			1	3						
Shamsherganj	•• ••		6				300						
Kulaura	••		1	65%									
Karimganj				70	Ŋ,	U							
Atgram	•• ••		ú			4							
Bhanga			- {		8	15	7						
Bianibasar	••			सद्य	मेव ः	 गयने							
Patharkandi													
Tilpara	•• ••												
Latu	••										ļ	į	
Nilam Bazar	•• ••									ļ			
Barlekha													
Uhargola	•• ••	}											
Kaliganj	••												
		L	<u> </u>									<u> </u>	



सद्यमेव जयते

#### INDEX.

Abed Reja.—Raja of Baniyachung, p. 25. Adampur. - Kuki raids on villages near, p. 44. Ahoms.—Conquest of Jaintia by, pp. 29-31. Ajmiriganj.—Steamer station, p. 182. Trade centre, pp 195, 202. Akhailkura.—Village noted for brass and bell-metal work, p. 152. Akhras--p. 108-112. Alabakshpur--Darga at, p. 83. Ali Amjad Khan.—Head of the wealthiest family, p. 93. Alinagar. - Kuki raid on a village near, p. 45. Railway station, p. 181. Amusements-p. 102-104. Animists—p. 90. Archæological remains—p. 62. Asfrai.—Raja of Sylhet, p. 27. Badarpur.—Noted for brass and bell-metal work, p. 152. Railway station, p. 181. Steumer station, p. 182. " Dak bungalow at, p. 186. Bairagi.—Steamer station, p. 182. Balaganj. -Do. p. 182. Trade centre, p. 195, 202. Rural Sub-registry Office at, p. 254. Balisira case - p. 223. Bulisira range—p. 6. Bandasil - Christians at, p. 91. Baniyachung Rajas-p. 25. Baniyachung.—Inspection bungalow at, p. 189. Large village, p. 203 Rural Sub-registry office at, p. 254. Barak or Surma. - River, p. 7. Barakia.—Sacred place, p. 86. Baramohal.—Pargana noted for lac industry, p. 166. Barlekha.—Railway station, p. 181. Inspection bungalow at, p. 190. Bell-metal working-p. 152. Bengadoba. Village noted for pottery, p. 151.

Betelnut.—p. 124. Bhadair Deol.—Country spirit shop at, p. 242, Bhanga.—Railway station, p. 181. Bhanga Bazar.—Steamer station, p. 182. Saw mill, p. 160. Bhanubil.—Riot at, p. 250. Bhanugach or Rajkandi hills-p. 6. Bhanu Naryan,—First Sylhet Raja, p. 22. Bhaterah, - Pargana noted for lac industry, p. 166. Bholagani.—Trade centre, p. 192. Bibisaua.—Fishery, p. 162. Bibiyana. - Biver, p. 7 Bithangal. - Sacred place, p. 87. Boat building-p. 155. Boat traffic-p. 183. Bogapani.—Tributary of the Surma, p. 8. Bondassye —Attack on, p. 37. Brahmans—p. 75. Brahmos-p. 90. Brass working—p. 152. Buffaloes—p. 130. Bunds-p. 49. Burmese war—p. 42. Byng, Major.—Killed by mutineers, p. Cane work-p. 158. Castes-p. 74-79. Cattle-p. 132. Cattle disease -p. 133. Champigny — French settler, p. 51-53. Chandipur - Sacred place, p. 86. Chandura.—Railway station, p. 181. Chandu.—p. 243. Chapghat pargana - Raid on, p. 38. Noted for palanquins, p. 157.

"Noted for palanquins, p. 157.
"Noted for mats, p. 158.
Charabhanga—Darga at, p. 83.
Chargola thana.—Attack by Radha Ram on, p. 41.
Chargola.—Railway station, p. 181.
Chatla bil.—Fishery, p. 162
Chatlapur.—Steamer station, p. 182.
Chaualis.—Pargana noted for sitalpati, p. 158.
Chaukidars—p. 255-257.
Chengar Khal.—Tributary of the Surma, p. 8.
Chhatachura range.—p. 5.

Chhatak.—Steamer station, p. 182.

"Trade centre.—p. 195 & 203.
Christianity—p. 90.
Chunarughat.—Inspection bungalow at, p. 189.
Civil justice—p. 254.
Commerce and trade.—p. 191-195.
Communications—p. 180-191.
Companyganj.—Inspection bungalow at, p. 187.
Condition of district in 1837—p. 60.
Cotton—p. 124.
Country spirit—p. 239-242.
Criminal justice—p. 249-253.
Currency—p. 58-55.

Dakhinbhag.—Railway station, 181. Do. p. 181. Daragaon Dastidar family-p. 94. Dewan families—p. 25 & 95. Dhaleswari.—River, p. 7. Dhakadakshin or Thakurbari.—Sacred place, p. 87. Inspection bungalow at, p.-188. Dhakadakshin. - Pargana noted for **Hooden** plates and vessels, p. 157. Dhan Manik. - Jaintia Raja, p. 29. Dholai.—Tributary of the Manu, p. 9. Dohaliya or Pratapgarh hills, -p. 5. Dress —p. 172. Dullabchara. -- Inspection bungalow at, p. 190. Durbar Khan.—Head of the Jagannathpur branch of the Raj family, p. 25. सत्यमव जयत

Earthquakes.—p. 18-16.
Economic condition of people—p. 174-179.
Education—p. 261-264.
Enathganj.—Steamer station, p. 182.
Eri silk—p. 154.
European settlers—p. 51-53.
Excise—p. 55-57 & p. 239-245.

Fatchpur—Darga at, p. 83.
Fauna—p. 16.
Fenchuganj.—Steamer station, p. 182.
" Dak bungalow at, p. 188.
Festivals—p. 99-102.
Fishing industry—p. 160-166.

Floods.—p 12,46-51, & 134. Food—p. 172. Forests.—p. 144-148.

Ganga Singh-Khasi free booter, p. 34. Ganja-p. 244.

Gaur-Kingdom of, p. 23.

Gaur Gobind- Raja of Gaur, p. 23 and 24.

Geology-p. 11.

Ghagtia.—Village near which Panatirtha river is sacred, p. 98.

Goats-p. 184.

Gobind Singh.—Raja of Baniyachung, p. 25. Golapganj.—Inspection bungalow at, p. 186.

Gopla.-River, p. 9.

Government—p. 247. Govindganj.—Inspection bungalow at, p. 186.

Goyain Gong.-Tributary of the Surma, p. 8

Habiganj-Dak bungalow at, p. 189.

" Town,—p. 197 and 200. Haijongs—Caste, p. 77

Hakaluki haor. - Origin of name, p. 22.

,, Fishery-p. 161.

Haors-p. 18-20.

Harargaz or Langla hills-p. 6.

Hari or Kusiya.—Tributary of the Surma, p. 8.

Haripur.—Inspection bungalow at, p. 187.

Hatakeswar.—Sacred place. p 87.

Henniker.—Expedition against Jaintia Raja by Major, p. 31.

Hinduism-p. 83-90.

Hingsjiya.—Country spirit shop at, p. 242.

Rural Sub-registery office at, p. 254.

Houses and furniture—p. 173.

Ilam lands-p. 226-230.

Immaum Mehadri alias Aga Mhd Reza.—Attack on Bondassye by, p. 37.

Income-tax-p. 245.

Infirmities .- p. 73.

Ishamati-Khasi raid on, p. 84.

Itakhola.-Railway station, p. 181.

Jadukata.—Tributary of the Surma, p. 8.

Jaflang.—Trade centre, p. 192.

Jagadishpur.—Inspection bungalow at, p. 189.

Jagannathpur. - Sacred place, p. 87. Rural Sub-registry Office at, p. 254. Jaile - p. 257-261. Jainpur.-Sacred place, p. 86. Jains--p. 90. Juintia Parganas. - History of the, p. 27-32. Revenue account of the, p. 283-235. Jaintiapur. - Inspection bungalow at, p. 187. Trade centre, p. 192. Jaldhub .- Rural Sub-registry office at, p. 254. Jasa Manik.—Jaintia Raja, p. 30. Joynagar Bazar-Damage by earthquake to, p. 15. Jugaltila.-Sacred place, p. 88. Jugirgaon - Damage by earthquake to, p. 15. Juri.—Railway station, p. 181. Jute—p. 123. Kacharipara.—Kuki raid on, p. 45. Kachua.—River, p. 8
Kaitak.—Inspection bungalow at, p. 186. Kalni. - River, p. 7. Fishery, p. 161. Kanaihati.—Pargana noted for lac industry, p. 166. Kanairghat.—Inspection bungalow at, p. 187. Rural Sub-registry Office at, p. 254. Kanta Kal.-Khasi raid on, p. 37. Karimganj.—Railway station, p. 181. Steamer station, p. 182. Town, p. 202. Keshab Misra.—Ancestor of the Laur Raj family, p. 25, Khasis.—Early dealings with, p. 33-37. Khowai.—River, p. 9. Khowaj Osman.—Moslem invader, p. 23. Kochabari. - Kuki raid on, p. 48. Koch invasions—p. 26. Krishnapur.—Sacred place, p. 89. Kukis.—Raids by, p. 43-46. Kulaura.—Railway station, p. 181. Inspection bungalow at, p. 190. Kurma.—Steamer station, p. 182. Kusiari.—Caste, p. 77. Rusiya or Hari.—Tributary of the Surma, p. 8. Kusiyara.—River, p. 7.

Lac industry, p. 166.

Lakhat.—Trade centre, p. 192.

Lakhi Bazar.—Steamer station, p. 182. Lal Chokla—Kuki chief—Raid by, p. 48. Land revenue -p. 212-239. Langai. - River, p. 9. Railway station, p. 181. Longaighat.—Steamer station, p. 182. Langla or Harargaz hills, p. 6. Langla.—Residence of the wealthiest family in Sylhet, p. 93. Langla—Village noted for palanquins, p. 157. Pargana noted for lac industry, p. 166. Language-p. 73. Laskarpur.—Village noted for palanguins, p. 157. Latu—Fighting with mutineers at, p. 61. Latu.—Railway station, p. 181. Laur—Attack on thana at, p. 41. Laur Rajas-p. 25. Leper asylum—p. 272. Lime-p. 149. Lindsay, Mr. -- Account of riots in 1782 by, p. 39-41. Account of floods in 1781 by, p. 46 & 47. Linseed. - p. 120. Lister, Colonel.—Expedition into the Lushai Hills under, p. 44. Live stock—p. 130-134. Lobha .- Tributary of the Surma, p. 7 and 8. Local Boards—p. 204-206. Lukra.—Village noted for pottery, p. 151.

Madak.—p. 243. Madhabpur - Viltage noted for brass and bell-metal work, p. 152. Rural Sub-registry Office at, p. 254. Madna.—Steamer station and inspection bungalow at, p. 189. Manipuris.—p. 78. Mantala.—Railway station, p. 181. Manu. - River, p. 9. Manumukh—Steamer station, p. 182. Dâk bungalow at, p. 188. Markhali. - Steamer station, p. 182. Marriage--p. 71. Marriage customs—p. 95-99. Marshes-p. 10 and 17-20. Masulia-Sacred place, p. 88. Mat work-p. 158. Maulavi Bazar. -- Town, p. 201. Mauzumdar family-p. 94. Medical — p. 264-272.

Migration—p. 68-70.
Mirpur.—Inspection bungalow at, p. 189.
Mosques and tombs, p. 81-83.
Muchikandi—Traffic Registrar's office at, p. 198.
Muhammadanism—p. 79-83.
Malagul—Principal bazar, p. 192.
Mullapara.—Inspection bungalow at, p. 189.
Municipalities—p. 195-197.
Murders—p. 251-253.
Mustard—p. 119.
Mutiny in 1857—p. 61.

Nahairghat.—Steamer station, p. 182.

Nandanpur.—Village noted for brass and bell-metal work, p. 152.

Navigable rivers—p. 182 and 207-211.

Nayagaon.—Sacred place, p. 88.

Nidhipati—Ancestor of the Sylhet Raj family, p. 22.

Nilam bazar.—Inspection bungalow at, p. 180.

Nirmai—Sacred place, p. 86.

Nowakhali—Traffic Registrar's office at, p. 193.

Occupations—p. 92. Opium—p. 243.

Pachwai-p. 242. Pagla. - Inspection bungalow at, p. 186. Panatirthra—Sacred river, p. 89. Panduah.—Khasi raid on, p. 35. Panisail.—Sacred place, p. 88. Pan vine—p. 125. Patashah .-- Tomb of fakir, p. 83. Pathariya hills-p. 5. Pathariya - Deposits of coal near, p. 11. Patharkandi.—Inspection bungalow at, p. 190. -Rural Sub-registry office at, p. 254. Permanent settlement--p. 213-224. Phaljor—Sacred place, p. 86. Plantain-p. 124. Police—p. 254-257. Ponies—p. 134. Postal— p. 191. Pottery-p. 150. Pratapgarh or Dohaliya hills-p. 5.

Prices—p. 170-172. Public Works—p. 246. Pulse—p. 119. Putijuri.—Inspection bungalow at, p. 189.

Radha Ram.—Attack on Chargola thana by, p. 41. Raghunaudan hills-p. 6. Railway-p. 180-182. Rainfall-p. 11. Rajkandi or Bhanugach hill, p. 5. Rajnagar.—Village noted for palanquins, p. 157. Ramda.—Inspection bungalow at, p. 186. Ramnagar.—Country spirit shop at, p. 242. Ram Sing .- Jaintia Raja, p. 80. Rarh or Kusiari.—Caste, p. 77. Rasidpur.—Railway station, p. 181. Registration ... p. 254. Religion-p. 79-92. Rice - p. 114-119. Riots-p. 89-41 and 250. Roads - p. 184-190. Rupnath.—Sacred place, p. 87.

Sachna. -- Inspection bungalow at, p. 189. Sacred places—p. 85-90 and 105-112. Saistaganj. - Railway station, p. 181. Inspection bungalow at, p. 189. Saraspur hill—p. 5. Sarbananda.—Sacred place, p. 87. Satgaon or Dinarpur hills, p. 6. Satgaon.—Railway station, p. 181. Sayed Nasir Dey.—Invasion by, p. 23. Sex—p. 71. Shah Abu Turab—Founder of a mosque, p. 82. Shahaj Bhajan.—Hindu sect, p. 84. Shah Fatch Ghazi.—Darga of, p. 82. Shah Jalal - Fakir, p. 24. " Mosque, p. 81. Shahji Bazar.—Railway station, p. 181. Inspection bungalow at, p. 189. Shamshernagar.—Railway station, p. 181. Sharergaj - Country spirit shop at, p. 242. Sheep - p. 184. Sheolamukh.—Steamer station, p. 182.

Inspection bungalow at, p. 186.

Sherpur. Steamer station, p. 182. Inspection bungalow at, p. 188. Siddheswar temple—p. 86. Sikandar Shah, -Invasion by, p. 28. Silarai. - Koch invader, p. 26. Singla.—River, p. 8. Social restrictions-p. 180. Son bil—Fishery, p. 161. Srimangal.-Village noted for brass and bell-metal work, p. 152. Railway station, p. 181. Inspection bungalow at, p. 158. Stamps-p. 246. Storms—p. 12, Subdivisions. - Opening of, p. 248. Subid Narayan.—Raja, p. 22. Subtenancy—p. 167-169. Budras - p. 76. Bugarcane-p. 121-123. Sunamganj.—Steamer station, p. 182. Town, p. 201. Supatala—sacred place, p. 87. Surms or Barak.—River, p. 7. Surveys —p. 272. Swamps—p. 10 and 17-20. Sylhet.—Town, p. 195 and 197-200. Sylhet jail.—p. 257-261. Tajpur.—Inspection hungalow at, p. 188. Tamptakunds—Sacred pool, p. 89. Taraf—Pargana noted for molasses, p. 123. Tea-p. 135-144. Temperature—p. 11. Temples.—p. 105-107. Temporarily settled estates —p. 225-286. Telegraph-p. 191. Thackeray, Mr.—First resident in Sylhet, p. 32. Thakurbari—Sacred place, p. 87. Inspection bungalow at, p. 188. Til-p. 120. Tilagaon. - Railway station, p. 181. Tungeswar.—Sacred place, p. 87. Umed.—Raja of Baniyachung, p. 25.

Volunteering-p. 257. Vegetables-p. 125.

Wages-p. 169.

Weaving-p. 153.
Willes, Mr.—Collector of Sylhet—His dealings with the Khasis,

p. 34-36.
Willes, Mr.—Survey made by, p. 213-216.
Wood working—p. 156 and 157.

